

Corrigendum – 1 for Tender Notice No. K RIDE/Projects/61/2020,**Date: - 06.11.2020**

Sub : Electrical Engineering Department - Baiyyappanahalli– Hosur and Yeshwanthpur-Channasandra Doubling Projects – “Execution of Design, Supply, Erection, Testing & Commissioning of 25 KV, AC, 50 Hz, Single Phase, Traction Over Head Equipment works for Railway Electrification works” in Bangalore division of South Western Railway, in Two (2) Packages” (MULTIPLE PACKAGES)

Sl. No.	Description	Page no.	As Published	To Be Read As
1.		104	<p>“1.3.6 Safety Fencing :..... as per the relevant item in the BOQ.”</p> <p>“1.4 (a) The contractor shall not start any work without the presence of Railway supervisor at Site”</p> <p>“1.4 (d) A competency certificate to the contractor’s supervisor as per proforma annexed shall be issued by AEN which will be valid only for the work for which it has been issued.”</p>	<p>Clause 1.3.6 : “Deleted”.</p> <p>1.4(a) “The contractor shall not start any work without the presence of nominated supervisor at site”.</p> <p>1.4(d) “AEN” shall be replaced by Manager/Electrical.”</p>
2.	<u>1.18 Ensuring Safety at work site</u>	110	<p>“1.18 Ensuring Safety at work site Ensuring safety at work site while carrying out of doubling works is of paramount importance..... In terms of contract conditions, preventing entry of outsiders at the worksites is the responsibility of contractor and this has to be ensured.”</p>	<p>In addition to the clause at 1.18 add the following “All safety precautions required to be adhered while working on 25 kV OHE or in the vicinity of OHE as stipulated in AC traction manual. The contractor shall make sure that all the Labour working on the site shall adhere to the safety precautions and shall be trained accordingly. They shall be supplied with Personal Protective Equipment like Safety Shoes, Jacket, Ladder, Helmet, Safety Belt, Flags, safety rope etc., It is the personal responsibility of the contractor to ensure that all staff working at site wear and conversant to use the protective and safety</p>

Sl. No.	Description	Page no.	As Published	To Be Read As
				equipments.”
3.	2.2. Scope of Present Tender	114	The proposed work is in connection with Railway Electrification of “ proposed line Baiyappanahalli and Hosur ”.	proposed line Baiyappanahalli and Hosur & <u>Yeshwanthpur and Baiyappanahalli</u> ”.
4.	2.4. The contemplated works as a part of this tender consists of	115	“2.4 d. Making and supply of ‘As erected’ drawings of all the assets created.”	d. Making and supply of ‘As erected’ drawings of all the assets <u>Modified/created</u>.
5.	2.5 The Nature of Service/work	116	“2.5 h) Defects liability of permanent Works after commissioning as stipulated in the General Conditions (GC),”	“Defects liability of <u>Traction Distribution 25 kV AC OHE work after commissioning as per 2.6.12</u>”
6.	2.5 Document Submitted during Construction Stage by Contractor	116	“2.5 X.As erected drawings”	Drawings for <u>“Layout Plan (LOP),Cross Sectional Drawing(CSD), Structure Erection Drawing(SED), sectioning diagram, General power supply drawings.”</u>
7.	2.6.3.design and Drawing	117	“2.6.3 i) The contractor shall execute the work..... Parallel Clamp part (150/240) – RDSO drawing no. ETI/OHE/P/1530-1, Revision ‘C’”	Add <u>“f) Provision of saddle for catenary shall be as per RDSO guide line”.</u>
8.	2.6.7 Execution	123	“2.6.7 (x) (b) In case if the work, usually doneand take prior approval of the Employer.”	2.6.7 (x) (b) <u>“Deleted”</u>
9.	18.SCHEDULE20001(OH E-NON FERROUS ‘A’)ITEM OHE-18	271	“ The price shall also cover supply & erection of contact wireshall be payable under SOR OHE 23(b). Insulated catenary shall be payable under OHE -30	shall be payable under <u>“ITEM OHE -19”</u> “Insulated catenary shall be payable <u>“Deleted”</u>”
10.	Bill of Quantities of Baiyyappanahalli Cabin A(205.5 km) (Including) – Hosur (157.5 km) (Including) Section (60Track Kilometer approximately)	307-309,311-314.	“If there is any discrepancy in figures and words then only words”	If there is any discrepancy in figures and words then only <u>“words will be taken for assessment”.</u>

Sl. No.	Description	Page no.	As Published	To Be Read As
11.	Section 9 Bill of quantities BYPL-HSRA package-1 and Section 9 Bill of quantities BYPL-YPR package-2	306,316	<p>“Note:1 a)Please mention the percentage words, c)Bidder should ensure that theambiguity Note 2: a) The item rates..... b)..... c) The Successful bidder who..... (RCM) and deposit the same to the concerned authority.”</p>	<p>Add Note : 3 <u>Usage of Road cum Rail Vehicle crane with suitable arrangement for Auger foundation, Mast Erection and simultaneous stringing of catenary and contact wiring machines/appliances along with associated equipment by the contractor are preferable. Contractor shall indicate rate and the usage of the above machine in their covering letter saperately. However final decision will be taken by KRIDE.</u></p>
12.	4.1 (i) Schedule No.16001 b	328	“4.1.(i) (b) 45% of Scheduled rates shall be paid after the submission & acceptance of as erected/completion drawings by RVNL.”	<p>By RVNL shall be replaced by <u>K-RIDE</u></p>