Corrigendum-1

Date: 08.02.2021

Tender Notice No.K RIDE/DL/05/2021 Date: - 02.02.2021

Name of Work: Signaling works at one IBS and 7(seven) LC Gates in connection with doubling of Yesvantpur - Channasandra section of Bangalore Division. (single package)

SN	Description	As published	Revised
1	Section 9	----	Revised Schedule-H of BOQ is uploaded

All other terms and conditions including BOQ (except Schedule-H) will remain the same in the above tender notice. Please keep referring to the KRIDE website for any further corrigendum

Name of the work: Signaling works at one IBS and 7 (Seven) LC Gates in connection with doubling of Yesvantpur -Channasandra section of Bangalore Division.

SCHEDULE-H

Sl. No.	Description	Unit	Estimate rate in Rs.	Quantity	Amount in Rs.
1	Supply and installation of Multi section Digital Axle counter (MSDAC) as per RDSO specification no.RDSO/SPN/176/2013 version.3.0 with latest amendments a) Supply of Multi section Digital Axle counter (MSDAC) consists of i) The tenderer shall design the scheme for provision of required number of Evaluators, track side junction Boxes, detection points etc. ii) MSDAC application in the yard shall be in place of track circuits with single detection, IB application shall be with dual detection. iii) length of cable required for each track deviced-5/10/15 mtrs. b) Installation, Design, wiring, testing and commissioning of Multi section digital axle counter outdoor and indoor work	Per DP	682611.22	16	10921780.00
				Schedule-H total in Rupees	**1,09,21,780.00**

Tenderer / Contractor Percentage (At par / Below / Above) in figure.	
Tenderer / Contractor Percentage (At par / Below / Above) in words.	

Please ensure there are no over writing. In case of any discrepency in figures and words, words only will be taken for consideration.

Seal & Signature of the Bidder