

REPLY TO PRE-BID QUERIES

REPLY TO PRE-BID QUERIES		
1	As per document	Approved list of KRIDE (Section-9) for CSS- any ESCOM approved make with latest approval.
	Q1	CSS can we supply any ESCOM approved make.
	Remarks	Any BESCOM approved CSS can be supplied and it should meet the specification as discussed in section-8B. Before supply of the approval of makes to be obtained from JGM/KRIDE. Also, routine, acceptance etc. tests as mentioned in technical specification are required to be carried out in the presence of KRIDE/BESCOM's representative.
2	As per document	Approved list of KRIDE-(Section-9) for LT/HT cables- Sbee, Unistar, Finolex, Havells, Gloster, KEI, Universal, GEMSCAB
	Q2	For HT and LT cable can we supply any BESCOM approved make.
	Remarks	Any BESCOM approved LT/HT cables can be supplied.
3	As per document	Sl.no 49 of BOQ (Section-9) Supply of Tubular Poles for Street Lights.
	Q3	Please confirm the height of tubular pole and for swaged pole, please permit us to get the pole from any reputed manufacturers as per your specification.
	Remarks	Pl. refer Sl. No.48 of BOQ (Page No.604). The height of the pole is 9 mtr. as per the detailed description of swaged tubular pole. The approved make of GI/steel tubular poles is given in page No.624 of section-9.
4	As per document	<p>17. RESPONSIBILITIES OF CONTRACTOR (Section 8A- Employers Requirement)</p> <p>17.1 The Contractor shall liaison with ESCOM/ KPTCL/ PGCL, State/Central Government and local bodies till completion of works in all respect. It is the responsibility of the contractor to ensure proper liaison and co-ordination with State Authorities for availing line clearance, joint inspection, testing & commissioning energization of in to the full satisfaction of State Authorities and handing over, and KRIDE intervention should not be sought for any of the above.</p> <p>17.2 ROW issues if any shall be sorted out by the contractor.</p> <p>17.2.1 It is the responsibility of the Successful contractor to liaison with EB authorities for arranging joint inspections along with KRIDE supervisor as and when required and to ensure for early preparation of estimations, obtaining approvals at various stages, getting</p>

		<p>sanctioning of estimations and supervision charges intimations (Modification work of HT/LT power line crossings, Additional load/ Availing new power supply for railway installations)</p> <p>17.2.2 In connection with the work Contractors has to liaison with EB authorities / statutory authorities in getting the intimations towards the payment of the following and submit the same to this office in time to facilitate for processing the payment by Railway.</p> <p>a. Availing of new supply/service connection charges/deposit (3 MMD).</p> <p>b. Supervision charges (10% of estimate or latest as per EB guidelines) based on sanctioned estimate of ESCOM / KPTCL / PGCL authorities along with copy of sanctioned estimate.</p> <p>c. The contractor shall coordinate for payment of "Supervision Charges" to electricity authority and other charges payable to individual Govt. agencies as per the prevailing government rules, such payment shall be paid by KRIDE.</p> <p>17.2.3 All the other incidental charges payable to ESCOM / KPTCL/ PGCL / BBMP, GAIL, BWSSB, BDA, Electrical Inspectorate charges (State Govt.), charges for stamp duties/ agreements, inspection charges, TAQC/ MR charges as applicable, statutory amount to remit for approval from local bodies etc. to be borne by contractor.</p> <p>17.2.4 Execution of agreement with KRIDE / Railways and SEB authorities/ DISCOM submitting Relevant documents for EIG approval as per the requirement. It is the responsibility of the contractor for proper handing over of released materials to State Authorities. For this purpose, it is suggested that a joint inspection with the State Authorities officials concerned shall be carried out, the items and quantities of materials to be released are assessed properly before the work is started.</p>
	Q-4	Approval for Electrical Inspectorate for the work carried out will be comes under whose scope and approval from BBMP/KIADB/BDA/Railway's or any other Government approval is coming under whose scope.
	Remarks	Please refer clause No.17.2 section 8-A (page-258). The responsibility of obtaining approval for Electrical Inspectorate, BBMP/KIADB/BDA/Railway's or any other

		Government Agency is lies with the successful contractor. KRIDE shall assist fully in the matter.
5	As per document	Section-1 (NOTICE FOR INVITATION FOR TENDERS (IFT)) 27. Contract prices shall be inclusive of all taxes and duties etc., The rates quoted by the tenderer must be inclusive of all Taxes, Duties etc.
	Q-5	What is the percentage Of GST payable by K-RIDE.
	Remarks	In this tender the Contract prices shall be inclusive of all taxes and duties etc.. The rates quoted by the tenderer must be inclusive of all Taxes, Duties etc. and the percentage of GST is 12%.
6	As per document	Sl.no 46 of BOQ (Section-9) Supply of LT current transformer, 3.75 VA ring type as per IS 2705 part 172 CT ratio 400/5A, 0.5 accuracy class
	Q-6	As per BOQ SI No. 46 you have requested for the Distribution box with SMC material. Can we offer the material with CRCA enclosure.
	Remarks	No such discrepancy observed. However, it is clarified that as per SI. No.45 of BOQ, page No.604, the requirement of distribution box shall be SMC.
7	As per document	Section8B: Specification for RMU
	Q-7	In CSS technical specification page no. 413,417, it indicates the requirement of 500KVA CSS, but in page number 414 it indicates 750 KVA Hermetically sealed Kindly confirm the KVA rating of CSS.
	Remarks	No such discrepancy observed. Please refer Technical Specification Section-11
8	As per document	Section 8B (Technical Specifications for Compact substation)
	Q-8	In CSS technical specification page number 423 it indicates 750 KVA Hermetically sealed transformer with Aluminium wound. Kindly confirm the winding material copper or aluminium.
	Remarks	No such discrepancy observed. Please refer Technical Specification Section-11
9	As per document	Section 8B (Technical Specifications for Compact substation)
	Q-9	In CSS technical specification page number 415 it indicates 1250A ACB as incomer and outgoing feeders as 400A MCCB — 3Nos. But in page number 430 it indicates Incomer of 1600A ACB and outgoing feeder 250A MCCB — 7Nos. kindly confirm the requirement.
	Remarks	No such discrepancy observed. Please refer Technical Specification Section-11
10	As per document	Section-2 (ITT)-3.2.a.2: Required average annual turnover (in all contractual works): The intending Tenderer/Firm/Company/ Joint Venture should have achieved a minimum minimum Average Annual

		Construction Turnover of Rs.16.56 Crores in last Five financial years from 2017-18 to 2021-22.
	Q-10	Minimum Average Annual Turnover of Rs.16.56 Crores in last five financial years from 2017-2018 to 2021-22. Request you to consider MAAT of Rs.16.56 Crores in last five financial years from 2016-17 to 2021-22. Also request you to consider turnover for the year 2016-17 to 2020-21
	Remarks	Tender condition shall prevail. However, in case the audited balance sheet of the last financial year is not made available by the bidder, he has to submit an affidavit certifying that "The balance sheet has actually not been audited so far". In such case the financial data of previous 4 audited financial years will be taken into consideration for evaluation. If audited balance sheet of any year other than the last financial year is not submitted, then the bid will be considered as non-responsive.
11	As per document	Section-2 (ITT) 10.3: Documents comprising tender.
	Q-11	Hard copy submission of documents-Please clarify or provide the list for which all documents are need to be submitted.
	Remarks	All the relevant documents as per the tender conditions are required to be scanned and uploaded in e-proc portal. However, in case the Tenderer has opted for Tender Security in the form of unconditional Bank Guarantee, the Tenderer should upload the scanned copy of Bank Guarantee with the tender. The original bank Guarantee should be delivered in person to the official nominated as indicated in the Tender data sheet within 5 working days of deadline of submission of tenders. Non submission of scanned copy of Bank Guarantee with the Tender on e-tendering portal and/or non-submission of original Bank Guarantee within specified period shall lead to summary rejection of tender. The details of BG, physically submitted should match with the details available in scanned copy and data entered during submission time, failing which the Tender will be rejected.
12	As per document	Section-2 (ITT) 13.7: In this tender, the tender security/EMD has to be paid.
	Q-12	Request you to provide Tender fee and EMD exception for the bidder who is registered as a vendor under the category of Micro, Small and medium Enterprises (MSME), and must furnish Udyog Aadhar Memorandum No.
	Remarks	Tender condition shall prevail.
13	As per document	Section-1 (NIT) Sl. No.8: Validity of Tenders: Tenders shall remain valid for a period of 180 days after the Tender submission deadline date prescribed by the employer. A Tender valid for shorter period shall be rejected by the employer as non-responsive.

	Q-13	We explained our difficulties for offering 180 days for finalization of tender is too long. As in open market the rates are increasing on daily basis it is requested kindly finalized the contract within 4 to 6 weeks.
	Remarks	Tender condition shall prevail.
14	As per document	Section-5 (CC & SCC): Defect liability period will be ONE year from the date of commercial operations of the Section/Corridor.
	Q-14	As per General condition of contract the defect liability will be of one year from the date of work not after operation of the Section/Corridor.
	Remarks	The defect liability period will be one year from the date of satisfactory completion of work.
15	As per document	<p>Clause No.17.2.3 of Section-8A: Employer's requirement Clause No.2.3 of Section-8C: Explanatory Notes 17. RESPONSIBILITIES OF CONTRACTOR (Section 8A- Employers Requirement)</p> <p>17.3 The Contractor shall liaison with ESCOM/ KPTCL/ PGCL, State/Central Government and local bodies till completion of works in all respect. It is the responsibility of the contractor to ensure proper liaison and co-ordination with State Authorities for availing line clearance, joint inspection, testing & commissioning energization of in to the full satisfaction of State Authorities and handing over, and KRIDE intervention should not be sought for any of the above.</p> <p>17.2 ROW issues if any shall be sorted out by the contractor.</p> <p>17.2.1 It is the responsibility of the Successful contractor to liaison with EB authorities for arranging joint inspections along with KRIDE supervisor as and when required and to ensure for early preparation of estimations, obtaining approvals at various stages, getting sanctioning of estimations and supervision charges intimations (Modification work of HT/LT power line crossings, Additional load/ Availing new power supply for railway installations)</p> <p>17.2.2 In connection with the work Contractors has to liaison with EB authorities / statutory authorities in getting the intimations towards the payment of the following and submit the same to this office in time to facilitate for processing the payment by Railway.</p>

		<p>d. Availing of new supply/service connection charges/deposit.</p> <p>e. Supervision charges (10% of estimate or latest as per EB guidelines) based on sanctioned estimate of ESCOM / KPTCL / PGCL authorities along with copy of sanctioned estimate.</p> <p>f. The contractor shall coordinate for payment of "Supervision Charges" to electricity authority and other charges payable to individual Govt. agencies as per the prevailing government rules, such payment shall be paid by KRIDE.</p> <p>17.2.3 All the other incidental charges payable to ESCOM / KPTCL/ PGCL / BBMP, GAIL, BWSSB, BDA, Electrical Inspectorate charges (State Govt.), charges for stamp duties/ agreements, inspection charges, TAQC/ MR charges as applicable, statutory amount to remit for approval from local bodies etc. to be borne by contractor.</p> <p>17.2.4 Execution of agreement with KRIDE / Railways and SEB authorities/ DISCOM submitting Relevant documents for EIG approval as per the requirement. It is the responsibility of the contractor for proper handing over of released materials to State Authorities. For this purpose, it is suggested that a joint inspection with the State Authorities officials concerned shall be carried out, the items and quantities of materials to be released are assessed properly before the work is started.</p>
	<p>Q-15</p>	<p>Since there is no provision in the tender schedule for remitting government fees towards BESCO/BBMP/GAIL/BWSSB, BDA, ELECTRICAL Inspectorate charges (State Govt.) charges for stamp duties/agreements, inspection charges, TA&QC/MR charges may please be arranged by K-RIDE as per standard practice for which official receipts will be submitted to your office.</p>
	<p>Remarks</p>	<p>KRIDE will be pay necessary statutory supervision charges, Electrical Inspectorate and inspection Charges.</p> <p>Charges of stamp duties /agreements, TAQC/ MR charges as applicable and statutory amount to remit for approval from local bodies etc. or any other incidental charges payable to ESCOM / KPTCL/ PGCL / BBMP, GAIL, BWSSB, BDA, to be borne by contractor.</p>