

REPLY TO PRE-BID QUERIES

S. N	Clause Reference	Relevant Quote	Query/ Comment/ Suggestion	Employer's Response
1	Section 8A Part 1 15.2.6 Pg. no. 291	15. Scope of work	We request you to kindly confirm, Roof sheeting is in the scope of station contractor or in the cope of Architectural works contractor	Refer clause 15.2.6 of Employers-Requirements pg.no.291, Roof sheeting with combination of Polycarbonate sheet as per codal norms for lighting, is in the scope of station civil contractor.
2	Section 8A Part 1 15.2.9 Pg. no. 293 SN XXXV	15. Scope of work	We request you to kindly clarify whether the structural steel painting of FOB over Track portion is of Epoxy paint or Metalizing steel paint.	Refer Clause 15.2.9 of Employers-Requirements pg.no.293, all structural steel structures shall be painted with Epoxy paint of approved color by Employer.
3		Scope of work General	We request you to kindly clarify the structural steel support works of OHT line is under whose scope?	1. The structural steel support works of OHT line for BSRP comes under station civil contractor scope. 2. Any modification of OHT line of IR tracks, is not in the scope of this tender.
4		General	Once again sincerely requesting you to kindly extend the due date of submission of the tender till 30.09.2023, please	Refer SN 4 of Corrigendum 2.
5	Section 6 CD Pg.no.113	Annexure1 - Part A - Contract Data KEY DATES	We request you to kindly provide the revised Key Dates for 24 months duration please	Revised Key Dates are as below.

KEY DATES (REVISED)

The Contractor shall prepare and submit their detailed Program of Work so as to achieve key dates of various activities on time. The Contractor shall complete the work in a phased manner by fixing priorities to different stretches of work to give access to the other interfacing contractors as per the requirement of project from time to time and as per the key dates (milestones) indicated below:

Key Date	Time to achieve. (In Days from the Commencement Date)	Description of Key Date	Delay Damages for non-achieving the Key Dates
GEKD01	84	Submission and Engineer's approval of Contractor's Detailed Baseline Program. (Section 8A, Part-1, Clause 3.4.2)	0.01% of price quoted in Schedule 'A' per week of delay for the key date
GEKD02	84	Engineer's approval of, and mobilization of, all Key Personnel (Section 8A, Part-1-Clause 1.3 and 1.4)	0.01% of price quoted in Schedule 'A' per week of delay for the key date
GEKD03	84	Submission and Engineer's approval of Contractor's Design, Quality, Health & Safety and Environment policies and manuals. (Section 8A, Part-1 Clauses 5, 6, and 17)	0.01% of price quoted in Schedule 'A' per week of delay for the key date
GEKD04	126	Submission and approval of Design Stage 1, Preliminary Design. (Section 8A, Part-1, Clause 5.14)	0.01% of price quoted in Schedule 'A' per week of delay for the key date
STKD05	126	Completion of first Pile Load Test, including submissions and Engineer's approval of test reports. Submission and Engineer's approval of First detailed pile design / Raft footing design. (Section 8B, Clause 9.4)	0.01% of price quoted in Schedule 'A' per week of delay for the key date
STKD06	140	Commissioning of Casting Yard and Casting of First 'I' / Double 'T' Girder.	0.01% of price quoted in Schedule 'A' per week of delay for the key date
STKD07	180	Submission of final approved Detailed design for Architectural finishes & MEP works	0.01% of price quoted in Schedule 'A' per week of delay for the key date
STKD08	300	Completion of all Foundations (Piles and Pile Caps or Open Foundations).	0.01% of price quoted in Schedule 'A' per week of delay for the key date

Key Date	Time to achieve. (In Days from the Commencement Date)	Description of Key Date	Delay Damages for non-achieving the Key Dates
STKD09	390	Completion of Structural Framework up to and including concourse	0.01% of price quoted in Schedule 'A' per week of delay for the key date
STKD10	450	Completion of Structural Framework up to and including Platform Deck for all stations.	0.01% of price quoted in Schedule 'A' per week of delay for the key date
STKD11		Complete all Works to Degree 3 and Clear within the Platform Screen Door and Track Areas. Contractor to agree completeness with Trackwork Contractor and Engineer. Issuance of Full Access to the Trackwork Contractor.	
STKD 11.1	480	For any two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 11.2	490	For next two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 11.3	520	For balance Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD12		Complete all Works to Degree 3 and clear the access to Architectural finishes & MEP work contractor to agree completeness. Issuance of Shared Access & Permit to Work to the Systems Contractors.	
STKD 12.1	510	For any two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 12.2	530	For next two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 12.3	560	For balance Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD13		Complete all Works to Degree 3 and clear the Front of House Technical Rooms (TOM, EFO and SCR etc.) and common Areas. Contractor to agree	

Key Date	Time to achieve. (In Days from the Commencement Date)	Description of Key Date	Delay Damages for non-achieving the Key Dates
		completeness with the System contractors (AFC, S&T and PSD) and the Engineer. Issuance of Shared Access & Permit to Work to the System contractors.	
STKD 13.1	540	For any two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 13.2	560	For next two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 13.3	590	For balance Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD14		Complete all Works to Degree 3 and Clear to allow installation of equipment. Contractor to agree completeness with Lift and Escalator Contractor and the Engineer. Issuance of Shared Access & Permit to Work to the Lift and Escalator Contractors.	
STKD 14.1	570	For any two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 14.2	590	For next two Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STKD 14.3	630	For balance Stations	0.02% of price quoted in Schedule 'A' & 'B', per week of delay for the key date
STTO15	720	Completion of the Works for Take Over in accordance with the Contract including the submission of all Quality Control Records and As Built data as described and receipt of the Engineer's Statement of No Objection.	0.05 % of price quoted in Schedule 'A' & 'B', Accepted Contract Amount) per week of delay for the key date