

1 | BASEMENT LEVEL 02 PLAN
- | Scale (A1) 1:350, (A3) 700

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration



NOTE :

- * HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
- * HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

NOTES:


1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC/STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE			K-RIDE GC		
			Project Director GC		
			Architect GC		



BANGALORE SUB URBAN RAIL PROJECT CORRIDOR - 2					
Drawing for Tender Purpose only					
YESWANTE PUR BASEMENT LEVEL - 02 PLAN					
DRG.NO.	REVISION NO.	DRAWN BY	CHKD BY	APRVD BY	
KRIDE / BSRP / C2 / TD / YPR / AR / 1000		VSA	VSA		
DRG ISSUE DATE	15 / 06 / 2024	01			

ARCHITECTURAL



ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration

NOTE :

- * HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
- * HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS



LEGENDS	
	UNPAID AREA
	PAID AREA
	BACK OF HOUSE AREA
	PUBLIC DOMAIN (BARE SHELL)
	OPERATIONAL AREA
	BLOCK WALL
	FACADE
	RCC

	IR LAND BOUNDARY
	BSRP BOUNDARY

NOTES:


1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC/STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE		K-RIDE GC	
		Project Director GC	
		Architect GC	



BANGALORE SUB URBAN RAIL PROJECT CORRIDOR - 2				
Drawing for Tender Purpose only				
YESWANTPUR BASEMENT LEVEL - 01 PLAN				
DRG.NO. KRIDE / BSRP / C2 / TD / YPR / AR / 1001	REVISION NO. 01	DRAWN BY VSA	CHKD BY VSA	APRVD BY -----
DRG ISSUE DATE 15 / 06 / 2024				

ARCHITECTURAL



1 | GROUND LEVEL PLAN
- | Scale (A1) 1:350, (A3) 700

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration

NOTE :
★ HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
★ HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

LEGENDS



- UNPAID AREA
- PAID AREA
- BACK OF HOUSE AREA
- PUBLIC DOMAIN (BARE SHELL)
- OPERATIONAL AREA
- BLOCK WALL
- FACADE
- RCC

IR LAND BOUNDARY

BSRP BOUNDARY

NOTES:
1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC./STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE			K-RIDE GC		
			Project Director GC		
			Architect GC		



BANGALORE SUB URBAN RAIL PROJECT
CORRIDOR - 2


Drawing for Tender Purpose only

**YESWANTPUR
GROUND LEVEL PLAN**

DRG.NO.
KRIDE / BSRP / C2 / TD / YPR / AR / 1002

DRG ISSUE DATE 15 / 06 / 2024 REVISION NO. 01 DRAWN BY VSA CHKD BY VSA APRVD BY

ARCHITECTURAL



1 | CONCOURSE LEVEL PLAN
- | Scale (A1) 1:300, (A3) 600

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration


NOTE :
★ HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
★ HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

LEGENDS	
	UNPAID AREA
	PAID AREA
	BACK OF HOUSE AREA
	PUBLIC DOMAIN (BARE SHELL)
	OPERATIONAL AREA
	BLOCK WALL
	FACADE
	RCC

	IR LAND BOUNDARY
	BSRP BOUNDARY

NOTES:
1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC./STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE		K-RIDE GC	
		Project Director GC	
		Architect GC	



BANGALORE SUB URBAN RAIL PROJECT CORRIDOR - 2			
Drawing for Tender Purpose only			
YESWANTPUR CONCOURSE LEVEL PLAN			
DRG.NO. KRIDE / BSRP / C2 / TD / YPR / AR / 1003	REVISION NO. 01	DRAWN BY VSA	CHKD BY VSA
DRG ISSUE DATE 15 / 06 / 2024		APRVD BY -----	

ARCHITECTURAL



NOTE :

- * HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
- * HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

NOTES:


1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC/STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

KEY PLAN

CHIKKABANAVARA
(Km. 24.306)

YESWANTPUR STATION
(KM: 16.900)


BENNIGANAHALLI
(CH. -0+570)



Drawing for Tender Purpose only

YESWANTPUR LOWER PLATFORM LEVEL PLAN

DRG.NO.				
KRIDE / BSRP / C2 / TD / YPR / AR / 1004				
DRG ISSUE DATE	REVISION NO.	DRAWN BY	CHKD BY	APRVD BY
15 / 06 / 2024	01	VSA	VSA	----



1 | UPPER PLATFORM LEVEL PLAN
- | Scale (A1) 1:300, (A3) 600

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration



NOTE :
★ HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
★ HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

LEGENDS	
	UNPAID AREA
	PAID AREA
	BACK OF HOUSE AREA
	PUBLIC DOMAIN (BARE SHELL)
	OPERATIONAL AREA
	BLOCK WALL
	FACADE
	RCC

	IR LAND BOUNDARY
	BSRP BOUNDARY


NOTES:
1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC./STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE		K-RIDE GC	
		Project Director GC	
		Architect GC	



BANGALORE SUB URBAN RAIL PROJECT CORRIDOR - 2				
Drawing for Tender Purpose only				
YESWANTE PUR UPPER PLATFORM LEVEL PLAN				
DRG.NO. KRIIDE / BSRP / C2 / TD / YPR / AR / 1005	REVISION NO. 01	DRAWN BY VSA	CHKD BY VSA	APRVD BY -----
DRG ISSUE DATE 15 / 06 / 2024				

ARCHITECTURAL



1 | PD LEVEL
- | Scale (A1) 1:300, (A3) 600

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration

NOTE :
★ HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
★ HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

IR LAND BOUNDARY

BSRP BOUNDARY

UNPAID AREA

PAID AREA

BACK OF HOUSE AREA

PUBLIC DOMAIN (BARE SHELL)

OPERATIONAL AREA



BLOCK WALL

FACADE

RCC

NOTES:
1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC./STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE			K-RIDE GC		
			Project Director GC		
			Architect GC		



BANGALORE SUB URBAN RAIL PROJECT
CORRIDOR - 2

Drawing for Tender Purpose only

YESWANTPUR
PD LEVEL PLAN

DRG.NO.
KRIDE / BSRP / C2 / TD / YPR / AR / 1006

DRG ISSUE DATE
15 / 06 / 2024


REVISION NO.
01

DRAWN BY
VSA

CHKD BY
VSA

APRVD BY

ARCHITECTURAL



ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration


NOTE :

- ★ HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
- ★ HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS

NOTES:


- ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
- ALL DIMENSIONS ARE IN MILLIMETERS.
- ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
- ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
- CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
- BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
- ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
- THE CUTOUT FOR FUTURE ESC./STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE		K-RIDE GC	
		Project Director GC	
		Architect GC	



BANGALORE SUB URBAN RAIL PROJECT CORRIDOR - 2				
Drawing for Tender Purpose only				
YESWANTPUR LONG SECTION - A				
DRG.NO. KRIDE / BSRP / C2 / TD / YPR / AR / 1007	REVISION NO. 01	DRAWN BY VSA	CHKD BY VSA	APRVD BY ----

ARCHITECTURAL



ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
1	SER 1	10950	6950	69 SQM
2	TER 1	10950	5540	60 SQM
3	SER 2	10950	7076	70 SQM
4	TER 2	11950	5100	60 SQM
5	UPS & BATTERY ROOM	11950	4928	60 SQM
6	S&T MAINTENANCE	9250	4838	35 SQM
7	SOLAR PANEL	15000	4800	75 SQM
8	DG ROOM	10504	13038	136 SQM
9	ASS ROOM	19800	20612	400 SQM
10	PUMP ROOM	8200	20988	172 SQM
11	FIRE WATER TANK (2 NOS) 100 KL CAPACITY	9200	9500	87 SQM
12	DOMESTIC WATER TANK (2 NOS) 50 KL CAPACITY	4813	5965	28 SQM

ROOM AREA SCHEDULE				
S.NO	ROOM NAME	LENGTH	WIDTH	AREA
13	SECURITY ROOM	2967	4524	13 SQM
14	FIRST AID ROOM	3199	3149	10 SQM
15	STAFF AREA	5300	4121	41 SQM
16	SCR	6350	7900	50 SQM
17	EFO/TOM-1	5100	3900	20 SQM
18	EFO/TOM-2	5100	3900	20 SQM
19	CLEANERS ROOM	3133	3199	10 SQM
20	REFUSE ROOM	3135	3199	10 SQM
21	LACTATION ROOM	4179	4612	18 SQM
22	OPERATION & MECHANICAL MAINTENANCE	16929	13039	218 SQM

OPENING SCHEDULE						
OPENING TYPE	WIDTH	HEIGHT	LINTEL HEIGHT	SILL HEIGHT	Nos.	REMARKS
D1	900	2100	2150	---	07	SINGLE LEAF DOOR
D2	1200	2100	2150	---	01	SLIDING DOOR
D3	1000	2100	2150	---	04	SINGLE LEAF DOOR
FD1	1500	2400	2450	---	12	FIRE RATED DOOR
FD3	1900	2400	2250	---	01	FIRE RATED DOOR
FD4	1100	2100	2150	---	02	FIRE RATED DOOR
RS1	3000	3000	3000	---	03	ROLLING SHUTTER
RS2	4000	3500	3500	---	02	ROLLING SHUTTER
RS3	3000	3500	3500	---	02	ROLLING SHUTTER

ABBREVIATIONS	FULL FORM
F.F.L	Floor Finish Level
TOM	Ticket Operating Machine
SCR	Station Control Room
EFO	Eccess Fare Office
SER	Signaling Equipment Room
TER	Telecom Equipment Room
UPS	Uninterruptible Power Supply
S&T	Signaling & Telecom
ASS	Auxiliary sub station
MMI	Multi Modal Integration

NOTE :

- * HEIGHTS AND LEVELS MARKED ARE INDICATIVE ONLY
- * HEIGHTS AND LEVELS ARE SUBJECT TO CHANGE AS PER EXISTING SITE CONDITIONS



LEGENDS	
	UNPAID AREA
	PAID AREA
	BACK OF HOUSE AREA
	PUBLIC DOMAIN (BARE SHELL)
	OPERATIONAL AREA
	BLOCK WALL
	FACADE
	RCC

	IR LAND BOUNDARY
	BSRP BOUNDARY

NOTES:

1. ALL DIMENSIONS ARE TENTATIVE FOR ILLUSTRATION PURPOSE, BOQ CONTRACTOR WILL DO ACTUAL DESIGN AS PER SITE CONDITION, SPACE AVAILABLE, CONSTRUCTION FEASIBILITY ETC.,
2. ALL DIMENSIONS ARE IN MILLIMETERS.
3. ALL DIMENSIONS ARE TO BE READ AND NOT TO MEASURED.
4. ROOF SHOULD BE DESIGNED FOR INSTALLATION OF SOLAR PANELS, ROOF SHAPE AND SIZE IS INDICATIVE. CONTRACTOR TO PROVIDE OPTIONS SUFFICIENTLY DETAILED FOR EMPLOYERS APPROVAL. FOR FURTHER DETAIL PLEASE REFER THE EMPLOYERS REQUIREMENT.
5. CONTRACTOR TO DESIGN A AESTHETICALLY PLEASING , STATE OF THE ART FACADE SYSTEM TO STOP INGRESS OF WATER IN THE STATION. ANY STRUCTURAL LOAD ON ACCOUNT OF THE FACADE WILL BE TAKEN CARE BY THE CONTRACTOR IN THEIR STRUCTURAL DESIGN
6. BARE SHELL IS WITHOUT ANY ARCHITECTURAL FINISHES AND E&M PROVISIONS.
7. ALL FOB SUPPORT LOCATIONS ARE INDICATIVE CONTRACTOR TO CO-ORDINATE WITH CONCERNED AUTHORITIES AND FINALIZE THE LOCATION AS PER ACTUAL SITE CONDITION ENSURING ALL NECESSARY CLEARANCES.
8. THE CUTOUT FOR FUTURE ESC./STAIRCASE SHALL BE CONSTRUCTED AS PRESENT SCHEME AND SHALL BE COVERED WITH A TEMPORARY SLAB FOR USE AS PUBLIC DOMAIN SPACE.

K-RIDE		K-RIDE GC	
		Project Director GC	
		Architect GC	



BANGALORE SUB URBAN RAIL PROJECT CORRIDOR - 2				
Drawing for Tender Purpose only				
YESWANTPUR CROSS SECTION - B				
DRG.NO. KRIDE / BSRP / C2 / TD / YPR / AR / 1008	REVISION NO. 01	DRAWN BY VSA	CHKD BY VSA	APRVD BY -----
DRG ISSUE DATE 15 / 06 / 2024				

ARCHITECTURAL