

Ancillary work of BWSSB (Water and Sewer line diversion) of Corridor – 2

Providing and laying water supply pipe line at various locations including Excavation, Laying and back filling as per specification

1. Shifting of 100mm, 150mm, 200mm, 250mm, 300mm, 400mm, 450mm, 600mm, 700mm, 800mm, 900mm, 1000mm, 1200mm, 1500mm, 1800mm dia both M.S pipeline and Ductile iron water supply pipe.

2. Sewer line.

Providing and laying stone ware

Pipe line including excavation, laying pipe line and back filling etc. as per specification.

- a. 150mm dia stone ware pipe.
 - b. 200mm dia stone ware pipe.
 - c. 230mm dia stone ware pipe.
 - d. 250mm dia S.W pipe line.
 - e. 300mm dia R.C.C NP3 Class pipe line.
 - f. 400mm dia R.C.C NP3 Class pipe line.
 - g. 450mm dia R.C.C NP3 Class pipe line.
 - h. 600mm dia R.C.C NP3 Class pipe line.
 - i. 900mm dia R.C.C NP3 Class pipe line.
 - j. 1200mm dia R.C.C NP3 Class pipe line.
 - k. 1800mm dia R.C.C NP3 Class pipe line.
3. Providing a fixing various types of valves i.e. Cast iron valves, ductile iron valves of various diameters as per specification.
 4. Providing and constructing man holes as per specifications of various diameters as per site condition and specification.
 5. Providing R.C.C and R.C.C concrete for encasing pipe lines of sewer line as per specifications.
 6. Providing and laying Sanitary and water lines by trenchless method for crossing Railway lines, highway roads and other places.
 7. Taking permission for execution of works pertaining to their respective concerned departments for taking up the work before commencing by paying necessary charges like, BBMP, BESCOM, KPTCL, GAIL, BWSSB, Traffic police and departments by authorized approval.