

ಬೆಂಗಳೂರು ಸಂಯೋಜಿತ ರೈಲು ಮೂಲಸೌಲಭ್ಯ  
ಅಭಿವೃದ್ಧಿ ಉದ್ಯಮ ನಿಯಮಿತ (ಬಿ-ರೈಡ್)

BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi-RIDE)

**Bi-RIDE**

**NAME OF WORK**

**C2/PACKAGE – 2**

“NAME OF WORK: “Design & Construction of formation in embankments, cutting including blanketing, Major bridges, Minor bridges, RuB, ERS/retaining wall, sacrificial retaining wall, drains, boundary wall ,fencing works and Station boxes of Nagawara & Kankanagar for at-grade section of length 11.569 km (Ch: -0.964km to Ch -0.675 km & Ch -0.050km to Ch 4.700km & Ch 4.700km to Ch 11.230km) for BSTP Corridor and also (Ch 4.700km to Ch 10.800km) 6.10 km (approximate) for IR corridor and other related infrastructural works (balance works) from Bennigenahalli to Banaswadi & Banaswadi to Hebbal including validation of design and stability check wherever applicable for works executed by previous contractor (excluding station buildings) of Corridor - 2 of Bengaluru Suburban Transport Project (BSTP)”.

**BID DOCUMENT**

**SECTION-8A  
EMPLOYERS' REQUIREMENT-1  
GENERAL INFORMATION  
AND SCOPE OF WORK**

# **SECTION - VIII**

## **EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK**

## TABLE OF CONTENTS

SL. NO.	DESCRIPTION	PAGES
	<b>GENERAL INFORMATION &amp; SCOPE OF WORK</b>	
I)	NAME OF THE WORK	
II)	BRIEF SCOPE	
	1. Deleted	
	2. AT GRADE FORMATION	
	3. MISCELLANEOUS WORKS	
	4. Deleted	
III)	<b>BROAD SCOPE OF THE WORK</b>	
	1. Deleted	
	2. AT GRADE FORMATION	
	3. MISCELLANEOUS	
	4. Deleted	
IV)	<b>DETAILED SCOPE OF THE WORK</b>	
	1.0 OBJECTIVE	
	1.1 DETAILED SCOPE OF THE WORK	
	A. Deleted	
	B. EARTHWORK IN EMBANKMENT AND CUTTING INCLUDING RETAINING WALL AND DRAINS	
	C. MINOR BRIDGES, MAJOR BRIDGES, RUB	
	D. MISCELLANEOUS: INCLUDING ROADS, BARRICADING, QUALITY, INTERFACE WORK, CASTING YARD, SITE OFFICE AND EQUIPMENT, PERSONNEL, ETC.	
	E. ROAD WORKS	
	F. DELETED	
	G. SALIENT FEATURES OF DESIGN & CONSTRUCTION AND OTHER INSTRUCTIONS	
V)	<b>GENERAL INFORMATION AND INSTRUCTIONS</b>	
	1. ITEMS PAYABLE UNDER LUMP SUM COMPONENT OF THE WORK IN SCHEDULE -C	
	2. PHASES OF WORK	
	3. REFERENCE DOCUMENTS	
	4. GENERAL PROJECT INFORMATION	
	5. AVAILABILITY OF LAND	
	6. APPROACHES TO THE PROJECT SITE	
	7. INTER COMMUNICATION FACILITIES	
	8. SITE INFORMATION	
	9. GENERAL CLIMATIC CONDITIONS	
	10. OBTAINING CLEARANCES/ CERTIFICATES FROM AUTHORITIES	
	11. RESTRICTIONS IN WORKING	
	12. POWER AND TRAFFIC BLOCK	
	13. PROVISIONAL ACCEPTANCE	
	14. GUARANTEE	
	15. ACCOUNTABILITY AND DISPOSAL OF RELEASED MATERIALS	
	16. CODES AND SPECIFICATIONS	
	17. SURVEY AND FIXING WORKING BENCHMARKS AND ALIGNMENT MARKERS	
	17.1 BENCHMARKS	
	17.2 ALIGNMENT	
	17.3 INTERFACING AND INTEGRATIONS OF WORKS	
	17.4 SURVEY EQUIPMENT	

Section VIII – Vol 1 – Employer's Requirement  
General Information and Scope of Work

SL. NO.	DESCRIPTION	PAGES
	18. DAMAGE TO PROPERTY	
	19. STRUCTURAL ELEMENTS, SHAPE AND FORM	
	19.1 STABILITY OF THE ELEMENTS	
	19.2 STABILITY OF THE STRUCTURE	
	19.3 TEMPORARY WORKS	
	19.4 DESIGN FOR TEMPORARY WORKS	
	20. DRAWINGS	
	20.1 GFC DRAWINGS	
	20.2 MEANING AND INTENT OF SPECIFICATIONS AND DRAWINGS	
	20.3 RESPONSIBILITY FOR SPECIFICATIONS, DESIGN AND DRAWING	
	20.4 DRAWINGS FOR PERMANENT WORKS	
	20.5 DESIGN, DRAWINGS AND SPECIFICATIONS FOR TEMPORARY / ANCILLARY WORKS	
	20.6 DRAWING MANAGEMENT	
	20.7 SHOP DRAWINGS SHALL BE PREPARED FOR THE FOLLOWING WORKS	
	20.8 DRAWING MANAGEMENT AT SITE	
	20.9 DOCUMENTS BY CONTRACTOR	
	20.10 COMPLETION OF DRAWINGS	
	20.11 PLANS AND DRAWINGS FOR LAYOUT OF PLANT AND EQUIPMENT	
	21. TRAFFIC MANAGEMENT	
	22. LIGHTING AND FIRE PREVENTION	
	23. UTILITIES	
	23.1 DAMAGE TO UTILITIES	
	24. INTERFACE WORKS	
	25. RESPONSIBILITIES OF CONTRACTOR	
	25.1 CASTING YARD	
	25.2 THE CONTRACTOR SHALL CARRY OUT EXPEDITIOUSLY & WITHOUT DELAY	
	26. ASSOCIATED WORKS DEEMED INCLUDED IN SCOPE OF PERMANENT WORKS	
	26.1 PLANT AND EQUIPMENT	
	27. PENALTY FOR NON-COMPLIANCE	

**SECTION VIII: VOL-1****EMPLOYER'S REQUIREMENTS GENERAL INFORMATION & SCOPE OF WORK****I) NAME OF THE WORK –**

C2/Package – 2

"Name Of Work: "Design & Construction of formation in embankments, cutting including blanketing, Major bridges, Minor bridges, RuB, ERS/retaining wall, sacrificial retaining wall, drains, boundary wall ,fencing works and Station boxes of Nagawara & Kankanagar for at-grade section of length 11.569 km (Ch: -0.964km to Ch -0.675 km & Ch -0.050km to Ch 4.700km & Ch 4.700km to Ch 11.230km) for BSTP Corridor and also (Ch 4.700km to Ch 10.800km) 6.10 km (approximate) for IR corridor and other related infrastructural works from Bennigenahalli to Banaswadi & Banaswadi to Hebbal including validation of design and stability check wherever applicable for works executed by previous contractor (excluding station buildings) of Corridor - 2 of Bengaluru Suburban Transport Project (BSTP)".

**II) BRIEF SCOPE**

The proposed work is in connection with the Package-2 of Corridor- 2/BSTP between Bennigenahalli to Banaswadi & Banaswadi to Hebbal (Excluding Station Buildings) including station boxes of Nagawara & Kankanagar and approx. Length of 11.569 Km from Ch: -0.964km to Ch -0.675 Km & Ch -0.050km to Ch 4.700km & Ch 4.700km to Ch 11.230km, (Including sidings).

**AT GRADE FORMATION**

This bid is for Design and construction of At-grade section comprising, earthwork in embankment in cutting and filling, Major Bridges, Minor Bridges, RUB's, including side drains & allied works approach road work viz., Retaining wall, Sacrificial retaining wall, R E Wall, elimination of level crossings by raising the formation level with retaining wall (BSTP & IR as applicable), RUB's and construction of service roads at required locations.

**MISCELLANEOUS WORKS**

- a) Miscellaneous items which are not covered in scope of work of Schedule A and B, shall be executed under Schedule-C, Provisional sum latest schedule of rates 2023-24 and its amendments or latest as published by KPWD/USSOR/CPWD/BWSSB/BESCOM/KPTCL as on date of award of work based on actual quantity executed at site.

**III) BROAD SCOPE OF WORK:**

- 1) Deleted
  - 2) **At Grade:Design and Engineering:** Detailed design as per the Employers requirement and Scope of work for both permanent and temporary works and proof-checking of all the works.
- a) Balance works for: "Design & Construction of formation in embankments, cutting including blanketing, Major bridges, Minor bridges, RuB, ERS/retaining wall, sacrificial retaining wall, drains, boundary wall ,fencing works and Station boxes of Nagawara & Kankanagar for at-grade section of length 11.569 km (Ch: -0.964km to Ch -0.675 km & Ch -0.050km to Ch 4.700km & Ch 4.700km to Ch 11.230km) for BSTP Corridor and also (Ch 4.700km to Ch 10.800km) 6.10 km (approximate) for IR corridor and other related infrastructural works (balance works) from Bennigenahalli to Banaswadi & Banaswadi to Hebbal including validation of design and stability check wherever applicable for works executed by previous contractor (excluding station buildings) of Corridor - 2 of Bengaluru Suburban Transport Project (BSTP)".
- b) Design and Construction of Minor bridges, the details are provided in Employer's requirement Vol-2 Annexure-1. Construction of MIB also includes the part works left out by the previous Contractor such as transportation and erection of precast elements, protection works etc.

- c) Design and Construction of Major bridge (1 No). The details are provided in Employer's requirement Vol-2 Annexure-1 and tender drawings. Major bridge with open web girder for two BSTP tracks and two IR tracks with pile and pile cap arrangements. The open web girder are four numbers for four tracks of this major bridge.
- d) Design and Construction of RUBs on At grade section. The details are in schedule of Employer's requirement Vol-2 Annexure-1.
- e) At Hebbal (RUB): Partially pre-cast segments for RuB are casted at site (14 Nos, each segment having 1.5m length box size (5.0x2.75) for IR side, for remaining RuB for BSTP side cast in-situ box shall be casted (i.e., 13.425m barrel length).
- f) Construction of minor bridges for full length/balance length, RUBs of full length/balance length for accommodating both BSTP and IR tracks and retaining walls, sacrificial walls and the work will have to be carried out in stages for continuing the IR traffic. The details are in schedule of Employer's requirement Volume 2 Annexure-1.
- g) Design and Construction of RCC drains 13Km along the track of BSTP and between IR & BSTP track is required in At-grade section.
- h) **ERS/retaining walls:** The retaining walls of approximately 11.00 Km length is required to be constructed and the height is varying from 1m to 12m for supporting the embankment/cutting slope and the details are in Tender drawing. And partially executed ERS/ retaining also shall also be completed. The details of the work executed by previous Contractor is indicated in Annexure 1A of Employer's requirement Vol-2. Respective approved structural drawings enclosed in the tender. The contractor has a liberty to follow the same or redesign with the DDC
- i) Design and Construction of fencing approximately 11.00 Km in between BSTP line and Indian Railway line and some of the fencing at Railway Boundary as mentioned in the drawing. Screw piling shall be done for the foundation of the Fencing or Boundary wall and the screw pile shall be anchored minimum 1m in parent strata. Including disposal for excavated/drilled soil/unsuitable soil and completion of work in all respect included in the lumpsum price.
- j) Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge
- k) Cable Tray Bolts / Brackets Fixture along the BSTP track.
- l) Design and Construction of Drainage work at about 22 Km of length.
- m) The work executed by previous Contractor for each chainage is enclosed herewith as Annexure 1A of Employer's requirement Vol.-2. **The design validation and stability check may be carried by the successful bidder, so as to submit the guarantee for the design & structure.** The bidder shall visit the site and satisfy itself for the work executed by previous Contractor and if any modification required thereto as per his own assessment must be carried.
- n) Design and Construction of Station Boxes of Nagavara & Kankanagar including structural works as per the GAD & drawing attached.

### 3) MISCELLANEOUS WORKS

- a. Miscellaneous items for works which are not covered in schedule A and B shall be executed under Schedule C of Price Schedule.
- b. Scope of work also includes Construction and maintenance of Project Offices and site offices for the Engineer and the Employer, at the locations approved by the Engineer / Employer and office at the casting yard for the Employer and the Engineer, till the end of DLP. the decision of the Engineer / Employer is final in this regard

- c. Road work: The road work is required for diversion of traffic during construction, earthwork/retaining wall locations, major and minor bridge locations and RUB locations. After completion of RUB structures, the permanent roads are required to be constructed on ramps and approaches of RUB as per the approved. Drawings. The road area for each layer comprises GSB, WMM, DBM and BC layers and this may vary during execution.

#### IV) DETAILED SCOPE OF WORK

##### 1.0 OBJECTIVE:

**The objective of the contract is construction, testing and commissioning of the permanent works, construction and removal of the Temporary Works and the rectification of defects appearing in Permanent Works by the contractor in the manner stipulated by the Contract.** In full recognition of this objective, and with full acceptance of the obligations, liabilities and risks which may be involved, the Contractor shall undertake the execution of the Works. The general and specific requirements of the employer are detailed out in this document for understanding of the bidders and for mandatory compliance by the successful bidder/contractor. The Employer's requirements have been divided into different sections / sub-heads for convenience only. They do not restrict any cross-references. The Contractor shall take into account inter-relations between various parts of works. No claim shall be entertained on account of compartmental interpretations.

##### 1.1 DETAILED SCOPE OF THE WORK

###### A. Deleted

###### B. EARTHWORK IN EMBAKEMENT AND CUTTING INCLUDING RETAINING WALL AND DRAINS:

GAD enclosed in the tender documents (Section-11) may be referred. Salient details of GAD are given below:

The Design of formation and specification for 25 T axle load shall be referred and followed. The scope includes the following:

- 1) Earthwork in embankment & cutting.
- 2) Earthwork for laying of a blanket layer as per RDSO guidelines with suitable materials as approved by Engineer.  
Specification no. RDSO / 2020 / GE: IRS-0004 (Including ACS No-01 dated 16.12.2021) and latest guidelines shall be referred for earthwork in embankment and for blanket layer.  
Earthwork shall be provided with contractor's own earth, wherever Railway cut spoil is not available / not feasible.  
Useful Railway cut spoil released from cuttings shall be utilized subject to suitability of cutting soil as per the RDSO Guidelines with the approval of Engineer/Employer.  
The top width of embankment and cutting of BSTP lines and stabling lines will be as per the drawings and specifications.  
The drainage arrangement between IR tracks and BSTP tracks at formation level, side drains at toe / ground level, drains at berm level, catch water drains / saucer drains are included in the scope of work.  
The contractor to work out the methodology suitably for stagewise construction for continuing the IR traffic without any hindrances and this aspect may be considered while quoting. Nothing extra shall be payable for phase-wise construction. The improvement of existing RUBs of IR with plastering, painting, pitching, and lighting also to be carried out along with the new construction of RUB.  
Plastering, painting, lighting, and electrification is required to be carried out in all new RUBs for full length.
- 3) Earthwork in cutting by mechanical means (Hydraulic excavator) including leading disposing off the surplus unusable cut spoils to outside of Railway limits as per directions of the engineer including cutting in hard rock

requiring blasting, cutting in rock requiring controlled blasting and chiseling. The scope includes loading, unloading and disposal of surplus excavated material using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer.

- 4) Construction of side drains, yard drains, catch water drains, etc. to the designed profile. The contractor shall ensure that during transportation, the carried material does not spill out.
- 5) Turfing / planting, including all lead and lift, and watering as required until properly rooted in embankment. The turfing shall be provided on slopes of the embankment for one side of BSTP slope. The turfing shall be provided on the approach roads of RUB.
- 6) Major Bridges, Extension of existing Minor Bridges / RUBs, side drains & allied works approach road works viz., Retaining wall, Sacrificial retaining wall, R E Wall, at required locations.
- 7) Loading, transportation and fixing of precast sacrificial retaining wall already cast panels to positions at site complete as per approved drawings, details are covered in Annexure 1A of Volume 2 employers' requirement and technical specifications.
- 8) Providing safety barricading as per drawing with contractor's materials and labour including all leads and lifts complete, including foundation work as per the drawing and as directed by Engineer in charge. The precast RCC posts shall be transported to duly handling carefully without causing any damage and erected at nominated locations as per the drawing, duly ensuring safety of running trains.
- 9) Maintaining including watch & ward and repairs of the barricading provided as per above item including cost of all contractors' men, materials, tools and plants required in this regard.
- 10) Supplying, laying Non-woven Needle Punched and Mechanically or Thermally bonded type Geotextile for use as Separator / Filtration for Railway formation as per RDSO Specification No. RDSO / 2018 / GE: IRS-0004 - Part / made of Polypropylene / Polyethylene / Polyamide or combination thereof having apparent opening size of s 85 microns and elongation at failure > 50% in both directions including transportation labour, lead & lift complete as directed by Engineer

On top of subgrade or prepared subgrade before laying blanketing layer with minimum strengths in Grab test, Trapezoidal Tear test and Puncture test of 700N, 250 N and 1800 N respectively of full formation width at required locations shall be conducted.

- 11) Compaction of embankment slope using hydraulic vibratory plate slope vibratory plate compactor attached to Excavator by doing 2 or more passes as required to get firm and neat compacted slope of embankment as directed by Engineer

The item is inclusive of all men, materials, equipment, watering arrangement, fuel etc. complete.

- 12) Providing & laying Reinforced cement concrete M35 grade using 20mm maximum nominal size aggregates, reinforced cement concrete using Portland slag cement (Directly from manufacture or blending of OPC+GGBS) for following concrete works: Open Foundation / stepped foundation / Raft, Combined Footing, Columns, Grade beam, monopile pedestals, and Structures of road widening works such as foundation, substructures and superstructures of culverts, retaining walls, RE Wall foundations, return walls, precast / cast-in-situ culvert deck slabs, road median, drains, RUB etc. including excavation for all depths from lowest ground level through existing water bound macadam road / bituminous road / concrete road / soil / moorum / hard rock / soft rock old structures below ground as encountered of all thicknesses, dismantling other structures, dead utilities, dewatering, pumping and bailing out water, strutting and shoring, formwork, backfilling in foundation with good earth / quarry dust / sand watering, compacting with a vibratory plate compactor complete as per specifications.

The scope includes loading, unloading and disposal of surplus excavated material using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer. The contractor shall ensure that during transportation, the carried material does not spill out. The scope includes the cost of using required dosage of admixture in concrete for obtaining required workability as per approval of Engineer, curing of concrete.



- 13) Levelling Course: Providing & laying plain cement concrete M15 / M20 grade using 20mm maximum nominal size aggregates in open foundation, stepped foundation, combined footing, raft foundation, retaining walls, return walls, walls, UG water tank, culverts, drains, slab on grade, tie beams, basements, levelling course or any other works as directed by the Engineer, etc. rate is inclusive of required dosage of admixture in concrete for obtaining required workability and as per specifications, approved drawings, laid in layers not exceeding 15cms thick layers, as per drawing including cost of all material, form work / shuttering, dewatering during concreting, vibrating, compacting, curing, hire charges of machinery, all lead and lift, loading, unloading, transporting, stacking, finishing the exposed faces etc., complete. Skin reinforcement, if necessary, shall be provided.
- 14) Providing Boulder backing behind abutment, wing wall, return wall, retaining wall with hand packed boulders & cobbles with smaller size boulders toward the back including all lead, lift, labour & other incidental charges as complete work in all respects
- 15) Demolition and removing of signal post / water columns / lighting towers / BG gate boom posts & rail columns etc., including foundation in concrete, masonry to entire satisfaction of the Engineer-in charge, with all men, material & equipment
- 16) Fixing of reference pillars at the edge of formation as per specification
- 17) Providing and laying of filter media consisting of granular materials of GW, GP, SW groups as per IS 1498-1970 in required profile behind abutments, minor bridge RCC boxes, RUB RCC Boxes, wing walls and return walls etc., above bed level with all labour and material complete job as per drawing and technical specification of RDSO.
- 18) Providing Weep Holes in stone masonry / Plain / Reinforced concrete abutment, wing wall, return wall, retaining walls and drains with 100 mm pipe extending through the full width of the structure with slope of 1V:20H towards drawing force.
- 19) Providing cast in situ plaques for bridge foundations details of size 45x45x5 cm in cement concrete 1:2:4 mix using 20mm hard stone aggregate embedded in 30mm deep notch over abutment & piers, engraving the letters & figures with CM 1:3 and finished smooth.
- 20) Construction of high bank / deep cutting slope based on slope stability analysis as specified by RDSO / theoretical methods, for railway cuttings / embankment more than 6m in height / depth based on the material available in cutting / embankments, including collecting required number of soil samples and conducting required laboratory tests as per RDSO specifications so as to find out soil parameters .required in slope stability analysis, working out design slope based on manual method / computer software including furnishing detailed calculations in a report form with contractor's men, material, machinery etc. and as directed by Engineer-in-charge.
- 21) supply, fabrication and erection of cable tray supports/hangers made out of Hot dip galvanized (65 micron) GI angle / channels / flats fabricated to the required size and shape falling in the category of standard GI sections. Rate shall include cost of Anchor Fasteners and other accessories/fittings/fixtures as required for Installation of supports at RCC Columns over the ERS Wall.
  - a) GI channel section of 100 x 65 mm
  - b) GI channel section of 75 x 75x 50 mm
  - c) GI channel section of 50 x 50 x 40 mm
  - d) GI L-Angle section of 75 x 75 x 8 mm
  - e) GI L-Angle section of 50 x 50 x 6 mm
  - f) GI L-Angle section of 40 x 40 x 5 mm
  - g) GI L-Angle section of 25 x 25 x 5 mm
  - h) GI L-Angle section of 25 x 25 x 3 mm
  - i) GI flat section of 75 x 10 mm
  - j) GI flat section of 65 x 10 mm
  - k) GI flat section of 65 x 8 mm
  - l) GI flat section of 50 x 6 mm
  - m) GI flat section of 40 x 5 mm
  - n) GI flat section of 25 x 5 mm
  - o) GI flat section of 25 x 3 mm

Or any other Sections as per design and site requirement

- 22) Supply, filling and stacking of sand bags layer by layer filled with Railway Sand/railway quarry dust in Contractor's empty polythene cement bags of 50 kg bags with all contractors labour, tools, plants, lead, lift etc., including stitching the same with machine using polythene thread complete as directed by Engineer-in charge at site.
- 23) Manufacture and supply of Precast Kilometer Posts of size 1.15 x 0.50 x 0.075 m in RCC 1:2:4 mix, engraving letters and leading to work spot, fixing in position with CC 1:3:6 concrete duly making pits of size as required, painting the post, writing the letters on both sides of the post with 2 coats of enamel paint of approved quality to the Railways drawings/IRPWM with contractor's materials, cement, steel, labour, tools, plant, with all lead and lifts etc., complete as per specifications and as directed by the Engineer-in-charge.
- 24) Manufacture and supply of Precast gradient Posts of size 1.65 x 0.60 x 0.075 m in RCC 1:2:4 mix, engraving letters and leading to work spot, fixing in position with CC 1:3:6 concrete duly making pits of size as required, painting the post, writing the letters on both sides of posts in 2 coats with enamel paint of approved quality to the Railways drawings/IRPWM with contractor's materials, cement, steel, labour, tools, plant, with all lead and lifts etc., complete as per specifications and as directed by the Engineer-in-charge.
- 25) Fencing work: Earth work excavation by manual means for drains, canals, waste weir draft, approach channels, key trench, foundation of Buildings & Bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work.
- 26) Boring, providing and installing cast in situ single under reamed piles of specified diameter and length below pile cap in M-25 cement concrete, to carry a safe working load not less than specified, excluding the cost of steel reinforcement but including the cost of boring with bentonite solution and the length of the pile to be embedded in pile cap etc. all complete. (Length of pile for payment shall be measured upto to the bottom of pile cap) : 20.3.1 300 mm dia piles.
- 27) Anchoring arrangement of Precast Column Placing over BSTP ERS
- 28) Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.
- 29) Galvanization of Structural steel
- 30) Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer in-charge. -(Made of G.I wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade)
- 31) Cable Tray Square Bolt Fixture as required.
- 32) Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 m openable length ( total length 90 m), having 50 nos rounds per 6 m length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/mm<sup>2</sup> with tape (0.52 mm thick) and weight 43.478 g/m
- 33) Construction, loading, transportation and fixing of precast RCC Pannels of M30 Grade, aggregate size not exceeding 12 mm, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, c/c spacing between vertical post not to exceed 2400 mm, leaving adequate space between vertical post for expansion, complete as per approved drawings and technical specifications.

- 34) loading, transportation and fixing of precast RCC Pannels of M30 Grade, aggregate size not exceeding 12 mm, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, c/c spacing between vertical post not to exceed 2400 mm, leaving adequate space between vertical post for expansion, complete as per approved drawings and technical specifications

**C. MAJOR BRIDGES, MINOR BRIDGES, RUB, and Other Special Spans.**

The scope includes the following:

**Embankment and all the structures are to be designed and executed for 25MT axel load for At-grade portion**

- 1) Design and Construction of foundation works for different structures i.e., track structure, Major bridges, Minor bridges, RUB's etc. including piles and pile caps / open foundations / rafts for columns / piers (wherever required).
- 2) Design and Construction of foundation work for different structures i.e., track structure, Minor bridges etc. including piles and pile caps / open foundations / rafts for columns / piers (wherever required) shall be constructed for the minimum depth 22 D for friction pile and for end bearing with anchoring in hard rock 1D & in weathered rock 6D as per relevant IS code. The Construction methodology is required to be approved by Engineer before carrying out the works. The founding level will be decided by Geotechnical Engineer of GC/ Employer during construction depending on sub soil strata. Pile depth mentioned is minimum, if depth of pile required is more than 22D as per design, the same is included in in the lumpsum cost. Scope also includes cutting / chipping of pile up to cut off level or up to good concrete and built up of pile up to required level. The scope also includes loading, unloading and disposal of surplus excavated material along with pile heads using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer. The contractor shall ensure that during transportation, the carried material does not spill out

The Construction methodology is required to be approved by the Engineer / Employer before carrying out the works. The founding level will be decided based on the Geotechnical reports by Engineer / Employer during construction.

- 3) Design and Construction of Abutments / piers, Pier caps / Bed blocks, bearings, as specified or as directed.
- 4) Design and Construction of Composite / Open Web Girders for Obligatory or Railway Spans according to RDSO Standards design & drawings (Major Bridge)

The Standard Drawings of box culverts (25 T Axle loading) of RDSO for minor bridges are applicable including any skew, curvature, or any cushions. The tentative spans are given in the minor bridges list.

The standard drawings of RDSO for major bridge is applicable including any skew, curvature, or any cushions. The tentative spans are given in the bridges list.

The standard RUB Drawings (Segmental Construction) as per IRS / RDSO are applicable including any skew, curvature, or any cushion. The IRS Codes shall be followed in principle, and the design criteria is based on IRS Codes viz. IRS-Bridge Rules, IRS Concrete Bridge Code & IRS Bridge Substructure & Foundation Code.

- 5) Pile caps / Open Foundations resting at any depth depending upon the site condition shall include excavation, leveling course, PCC, dewatering, sheet piling / soldier piling & wooden lagging, if required, Backfilling complete in all respects

Driving 'Z' section MS sheet piles by using 8mm to 10mm thickness, side by side in all kinds of soil mechanically using vibro hammer / suitable means / manually as per the directions of Engineer-in-charge for earthwork excavation in foundations for all depths and removing the sheet piles after the work.

- 6) Providing & laying Reinforced cement concrete M35 grade using 20mm maximum nominal size aggregates, pile foundations with socketing in weathered rock, soft rock, hard rock of any type and any depth if arising. The piling with temporary liners / permanent liners & socketing in soft rock / hard rock are included. The initial load test, routine load test, dynamic load test, lateral load test, pile integrity test, cross hole sonic test (to be tested for 25% of piles or 1 pile per group), are included.
- 7) Scope also includes cutting / chipping of pile up to cut off level or up to good concrete and built up of pile up to required level. The scope also includes loading, unloading and disposal of surplus excavated material along

- with pile heads using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer. The contractor shall ensure that during transportation, the carried material does not spill out.
- 8) Elastomeric bearings based on detailed design including bearing pedestals, seismic restrainers, shear keys
  - 9) POT / PTFE / spherical bearings based on detailed design shall be provided. The type of bearing (POT/PTFE / Spherical or neoprene) will be approved by Engineer / Employer.
  - 10) MS railing over Parapet as per tender drawing including submerged galvanized painting as per the design approved by Engineer / Employer.
  - 11) Expansion joint, sealant in the expansion joints as per specification.
  - 12) Manholes with manhole covers made of Cast Iron on the deck with locking arrangement as per the drawing
  - 13) Earthing arrangement, drainage system, inserts for signaling masts in the parapets and other systems, as may be required
  - 14) Arrangements for ground water recharging / Rainwater harvesting systems in alternate spans of the entire corridor.
  - 15) Drainage arrangement will be as per detailed design.
  - 16) Pre-cast elements: Providing and laying M50/M55 reinforced cement concrete using 20 mm graded aggregates for precast parapet and M35/M40 for pre-cast drains, crash barriers etc., in the casting yard/site including provision of lifting the elements from the mould and shifting the same to the stacking yard.
    - i. The Scope includes all infrastructures in the casting yard/site, gantry cranes, moulds, shuttering, casting beds, mobile cranes, stores, concrete batching plant, testing labs, approved curing arrangements as required.
    - ii. The Scope includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, required dosage of admixture for concrete.
    - iii. The Scope shall also be inclusive of Loading, transporting precast parapets and other elements from the casting yard to work site, launching and erection in position using gantry or crane complete with cast in situ stitch concrete of same grade.
    - iv. The Scope is inclusive of providing bolts & inserts for fixing handrails.
    - v. The scope is also inclusive of providing Bi-RIDE logo in parapet.
  - 17) Providing & laying Reinforced cement concrete M35 grade using 20mm maximum nominal size aggregates, Reinforced cement concrete using Portland slag cement (Directly from manufacturer or blending of OPC+GGBS for the following concrete works:
    - i. Open Foundation / stepped foundation / Raft, Combined Footing, Columns, Grade beam, monopile pedestals, UG water tank and Structures of road widening works such as foundation, substructures and superstructures of culverts, retaining walls, RE Wall foundations, return walls, precast / cast-in-situ culvert deck slabs, road median, drains, RUB etc. including excavation for all depths from lowest ground level through existing water bound macadam road / bituminous road / concrete road / soil / moorum / hard rock / soft rock old structures below ground as encountered of all thicknesses, dismantling other structures, dead utilities, dewatering, pumping and bailing out water, strutting and shoring, formwork, backfilling in foundation with good earth / quarry dust / sand watering, compacting with a vibratory plate compactor complete as per specifications.
    - ii. The Scope includes loading, unloading and disposal of surplus excavated material using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer.
    - iii. The contractor shall ensure that during transportation, the carried material does not spill out.
    - iv. The scope shall include cost of using required dosage of admixture in concrete for obtaining required workability as per approval of Engineer, curing of concrete.
  - 18) Levelling Course: Providing & laying plain cement concrete M20 grade using 20mm maximum nominal size aggregates in pile foundation, open foundation, stepped foundation, combined footing, raft foundation, retaining walls, return walls, walls, UG water tank, culverts, drains, slab on grade, tie beams, basements,

levelling course or any other works as directed by the Engineer, etc. rate is inclusive of required dosage of admixture in concrete for obtaining required workability and as per specifications, approved drawings, laid in layers not exceeding 15 cm thick layers, as per drawing including cost of all material, form work / shuttering, dewatering during concreting, vibrating, compacting, curing, hire charges of machinery, all lead and lift, loading, unloading, transporting, stacking, finishing the exposed faces etc., complete. Skin reinforcement, if necessary, shall be provided.

- 19) Providing Boulder backing behind abutment, wing wall, return wall, retaining wall with hand packed boulders & cobbles with smaller size boulders toward the back including all lead, lift, labour & other incidental charges as complete work in all respects
- 20) Providing and laying of filter media consisting of granular materials of GW, GP, SW groups as per the approved specification in required profile behind Slab bridges, RCC boxes, Abutments, wing walls / return walls etc., above bed level with all labour and material complete job as per drawing and technical specification of RDSO.
- 21) Providing and laying Pitching with stone boulders weighing not less than 35 kg each with the voids filled with cement sand mortar 1:4 on slopes laid over prepared filter media including boulder apron laid dry in between bridge proper and curtain I drop wall of minor bridges complete as per technical specifications.
- 22) Drilling holes up to required diameter or 32 mm diameter, providing Weep Holes in stone masonry / Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm AC pipe extending through the full width of the structure with slope of 1V:20H towards drawing force.
- 23) Providing Granite plaques for bridge foundations details of size 45x45x8 cm in cement concrete 1:2:4 mix using 20mm hard stone aggregate embedded in 30mm deep notch over abutment & piers, engraving the letters smooth notching corners. Providing cast in situ bridge number plaques of size as per the IRBM using cement concrete of M25 grade with 20mm hard stone aggregate over the bridge parapet as directed by Engineer in Charge. Marking high flood level (HFL) and danger level (DL) to be marked on the abutment and piers of Minor, Major bridges as per IRBM.
- 24) Preparation and submission of detailed GAD, design and drawing for minor bridges for 25T Axle loading including all details such as new bridge location with respect to existing bridge, methodology of construction without disturbing the existing bridge structure, drawing and detailed design shall be based on hydraulic data, geotechnic investigations, etc., Drawing and design shall be as per IRS Specifications and SOD standard specifications and schedule of dimensions. (Design calculation for the bridges shall be submitted and approval obtained from Railway's competent authority).
- 25) Design, manufacture, supply & installation of the approved expansion joint at the site at formation level under the supervision of manufacturer's representative as per specification and expected movement (25 to 50 mm) as mentioned in relevant drawings..
- 26) Supplying to site and placing of Elastomeric bearings/ POT Cum PTFE Bearings / spherical bearings (Free POT bearing, Fixed POT bearing, Longitudinal guide POT bearing and Transverse guide POT bearings) and its components in position during casting of pier / pedestal and superstructure, including, grouting of holes for anchor bolts and underside of base plate with approved non-shrink cementitious grout as per specification. The forces and movements are as per the design.
- 27) Fabrication & Supply of drainage spout hot dip galvanized of dimension 300mmx180mm with MS Flat 50mmx6mmx100mm long with gratings of MS Flat 25mmx6mm with spacing of 50mm c / c and MS pipe 122mm dia. verticals as per drawing including installation of the spout with all tools, plants, leads and lifts and in position in complete and as directed by the Engineer.
- 28) Waterproofing for RCC Boxes of Minor Bridges & RUBs is in scope.
- 29) Supply, fabrication, transportation and erection of fabricated steel girder work of Grade E450BR conforming to IS 2062-2011 (with all latest amendments) including painting, fully killed and fully normalized at appropriate location using various structural steel sections including MS plates, etc. as per approved QAP and drawings for composite girders including cutting, bending, drilling holes with necessary field rivets welding HSFG bolts tightened by Torque wrench as per drawings supply of necessary templates, etc. complete for fixing accessories such as bolts and nuts, etc. complete duly providing necessary scaffoldings arrangements, temporary staging and metalizing the girders in accordance with Indian Railway bridge manual

and any other incidental work as required with all leads and lifts, etc. complete and as directed.

a. **Notes:**

- (i) In case of superstructure over flyover all steel girders with bracings together shall be launched using push and pull methodology / suitable launching schemes including Crib Crane method, etc.,
  - (ii) All labour, materials, tools and plants consumables such as welding rods, etc., by contractor.
    - a. Metalizing treatment of all steel surfaces shall be done by spraying aluminum having 99.5% purity with a coating of 150 microns by minimum 2 passes.
    - b. Painting of metalized steel sections shall be done as below.
    - c. First coat- Primer to IS: 5666
    - d. Second coat- Zinc chromium paint to IS: 104
    - e. Third & fourth coat- Aluminum paint to IS: 2339
  - (iii) The rates are inclusive of testing of all raw materials, shear connectors, HSFG bolts, nuts and welding, etc. including allowances for all types of wastages.
  - (iv) The scope is inclusive of surface preparation, sand blasting, etc. The scope shall also include supplying and providing of detailed fabrication drawing based on the GFC drawings, required for all permanent and temporary structure and their approval from Engineer-In-charge prior to execution.
  - (v) The Scope shall also include provision and installation of base plates, chequered plate for pathway, anchor bolts (measured in Tonnes, etc.) as per relevant drawings, specifications, and directions of the Engineer.
  - (vi) Using standard plate sections, rolled sections, tubular rolled sections, angles, channels, I- section, T sections, C sections, H sections, hollow round I square I rectangle sections etc., welded and built.
  - (vii) The launching scheme shall be submitted by the contractor using sufficient capacity cranes and get it approved by Engineer / Employer. When girder is to be erected over existing flyover then each girder is to be launched with proper care and with proper frame to avoid toppling during launching. The girders so placed will be temporarily braced with bolts and nuts before freeing from the frame.
  - (viii) The fabrication of the girder shall be done by RDSO approved agency / workshop.
- 30) Providing Boulder backing behind abutment, wing wall, return wall, retaining wall with hand packed boulders & cobbles with smaller size boulders toward the back including all lead, lift, labour & other incidental charges as complete work in all respect.
- 31) Providing and laying of filter media consisting of granular materials of GW, GP, SW groups as per IS 1498-1970 in required profile behind minor bridge RCC boxes, abutments, wing walls / return walls etc., above bed level with all labour and material complete job as per drawing and technical specification of RDSO.
- 32) Providing and laying Pitching with stone boulders weighing not less than 35 kg each with the voids filled with cement sand mortar 1:4 on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per technical specifications.
- 33) Drilling holes up to required diameter or 32 MM diameter, providing Weep Holes in stone masonry / Plain/ Reinforced concrete abutment, wing wall, return wall with 100 mm PVC pipe extending through the full width of the structure with slope of 1V;20H towards drawing force.
- 34) Providing cast in situ plaques for bridge foundations details of size 45x45x5 cm in cement concrete 1:2:4 mix using 20mm hard stone aggregate embedded in 30mm deep notch over abutment & piers, engraving the letters & figures with CM 1:3 and finished smooth.
- 35) Preparation and submission of Hydraulic/ Hydrologic calculations for bridges including Waterway and scour depth calculations as per RDSO guidelines and Railway Bridge Substructure Code with all calculations and details in three copies in CD and six sets of booklets, including collection of field details from the site with contractor's men, materials, and equipment etc. complete and as directed by the Engineer in-charge a) for Major bridges & Minor Bridges
- 36) Completion Drawing: Preparation and submission of GAD / Completion drawing for the Major bridge, RUBs based on soil exploration and water way calculation for fixing suitable span as per RDSO design and drawing in AutoCAD on 100micron film double mat finish as per Railway standard approved by the Engineer-in-charge to

specified scales including submission of check print for proof check to incorporate suggested corrections and modifications and supply final copy in compact disk and 6 copies in ammonia print in A0 size with all contractor's materials, labours, tools, plants etc., complete

- 37) Excavation along the alignment of signaling cable OFC / Power cable carefully and exposing the same without any damage and excavating new trench along the railway alignment or along the alignment as specified by Engineer-in-charge, laying of removed cable, filling up all complete with sand and laying a layer of brick with contractor's own material, tools, and plants etc., as directed by the Engineer-in-charge. In case the cable is damaged, the cost of restoration and the cost of cable will be recovered from the contractor. The decision of the Employer will be final.
- 35) Launching of precast RCC box segments of any size and barrel length for double line as per approved drawings to the correct alignment and position in electrified / non-electrified sections safeguarding all utilities ( S&T cable, power cable, OHE, pipelines etc.) including transportation of box segments from casting yard to site of launching, dismantling of the existing track, removing & stacking of ballast, removing surcharge, dismantling of existing bridge built with stone masonry / cement concrete, placing of Box segments in position either on base slab or prepared foundation, backfilling after launching of precast box segment and compaction of earth in surcharge, ballasting & relaying of track to correct alignment and geometry, packing and further maintenance till allowing non-stop 20 KMPH over the re-laid track, complete in all respect as per approved drawing to the satisfaction of Engineer-in-charge. The rate is all inclusive except the cost of RCC Box Segments, Base Slabs (if required) and backfill material which shall either be supplied by railway or paid extra under relevant item. Note: Unit of 'Each' here means bridge of span(s) with a total linear waterway up to 3m. Double Line Note: Minimum equipment required shall be (i) Crawler mounted Hydraulic excavator of min 200 HP and bucket capacity 2.5 cum - 3 numbers (ii) Cranes minimum 200 T capacity - 3 nos., (iii) Stone Breaker - 1 no., (iv) Road Trailer of 20 MT capacity - 1 no., (v) Tippers - 2 nos. and (vi) Tractors - 2 nos. (vii) Slope Vibratory compactor - 2 nos. and other required machineries etc. in good working condition at site of work. Loading, transportation and fixing of precast sacrificial retaining wall already cast panels to positions at site complete as per approved drawings and technical specifications.
- 38) Loading, transportation and fixing of precast RCC Box segments already cast to the positions at site complete as per approved drawings, as covered in Annexure A of volume 2 and technical specifications.
- 39) Casting and installation of single/twin RCC box of all sizes with or without common web section including design of pushing scheme, thrust bed, casting of all RCC components, with specified grade of controlled concrete, pushing it in correct position and alignment below Railway track/Road following all measures of track safety by "Box pushing technique" as per approved drawings/scheme, with or without surcharge in all types of soils with disposal of surplus earth away from vent up to 1 Km, fixing arrangement for all services & utilities including parapet walls on both sides, wearing course, foot paths, plaques, drainage arrangements etc. and all other incidental works to complete the RUB/Canal crossing in all respect as per specifications to the satisfaction of Engineer in-Charge. Note: 1. The rate includes all items of work/supplies for complete job in all respects except "cost of Reinforced cement concrete, cement, reinforcement & shuttering" of (i) main RCC Box; (ii) Thrust Bed; (iii) Footpath (iv) Parapet wall and (v) wearing Course only, which shall be paid extra under relevant items of USSOR. 2. In case Drag Sheet and/or Rail Cluster are to be used as per approved scheme and design, the same shall be paid extra under relevant item. 3. The payment for this item shall be made for the clear inner cross section area of the parent RCC Box/Boxes and barrel length i.e. clear inner volume of parent RCC Box/Boxes.
- 40) Supplying fabricating and erecting welded and/or bolted and/or riveted steel work in built up sections, trusses and framed work, staging, racks, Height Gauge etc. for Steel Structures other than bridge girders, using RSJ, tees, angles and channels/flats, plates, gussets, round or square bars, cleats, bolts etc., with contractors own steel including cutting, bending, straightening, drilling, riveting, hoisting, fixing, erecting, welding, bolting etc., with Providing stiffeners wherever required as per approved drawing including applying a priming coat of a approved steel primer with all contractor's materials, labour, tools & plants, lead & lift including crossing of tracks if required etc., complete as per specification and as directed by Engineer-in-charge. Note: The payment shall be made on the theoretical weight of main components and gusset plates only.
- 41) Supply, filling and stacking of sand bags layer by layer filled with Railway Sand/railway quarry dust in Contractor's empty polythene cement bags of 50 kg bags with all contractors labour, tools, plants, lead, lift etc., including stitching the same with machine using polythene thread complete as directed by Engineer-in charge at

site.

- 42) Painting the HFL mark and Danger level mark, year of HFL on bridge abutments and piers with ready mixed paint as per standard in two coats over one coat of primer with all materials, labour, tools, scaffolding, all lead and lift etc. including writing complete.
- 43) Providing cast in situ bridge number plaques as per Railway drawing in cement concrete 1:2:4 mix using 20mm hard stone aggregate embedded in 30mm notch in Bridge parapet coping duly engraving the letter and figures and an arrow indicating the direction of flow and finishing the top exposed surface with cement mortar 1:3, painting letters and figures with two coats of black enamel paint on two coats of white background with all labour, tools, cement, paint etc. with all leads and lifts.
- 44) Shoring with 'Z' section MS sheet piles side by side in all kinds of soil mechanically or manually as per approved drawing with contractor's own arrangement complete in all respects and removal of sheet piles after completion of the work as directed by engineer in- Roof sheet Structural steel columns on ERS wall in the approach road of RUBs.
- 45) Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05 %) total coated thickness with zinc coating 120 g/m<sup>2</sup> as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 m or as desired by Engineer in- charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.
- 46) Anchoring arrangement for cable tray purpose over the ERS wall/drain wherever required in the entire length of at-grade section.
- 47) Supplying and laying at site Factory made perforated hard HDPE subsoil drainage pipes pre-wrapped with 150 gsm Geotextile for subsoil drainage system including all necessary coupling/ fittings for joints & back filling with aggregates. The pipe shall be manufactured from High Density Polyethylene (HDPE). It shall be extruded into an open lattice wall structure, with > 60% of the circumference consisting of open area and a 30% solid area along the invert. The product should satisfy the following parameters as below
  1. Ring Stiffness as per ISO 9969: 2016 should be > 0.8 kN/m<sup>2</sup>
  2. Resistance to Acid with 3% HCl for 24 hrs without mass loss, change in colour, softening, cracking or spalling.
  3. Resistance to Alkali with 3% KOH for 24 hrs without without mass loss, change in colour, softening, cracking or spalling.
 160mm dia HDPE pipe
- 48) Earth work excavation by manual means for drains, canals, waste weir draft, approach channels, key trench, foundation of Buildings & Bridges and such similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. In all kinds Of Soil upto 1.5m
- 49) Providing Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) in Boundary wall work.
- 50) Providing and fixing of punched tape concertina coils of 600mm diameter over the boundary wall with "J" and "U" clips etc., complete as per manufactures specifications (Each coil to spread to 5.4 meter) with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/mm<sup>2</sup> with tape (0.52 mm thick) and weight 43.478 g/m barbed tapes / barbed wires for completing the work as per drawings and technical specifications.
- 51) Construction, loading, transportation and fixing of precast RCC Pannels of M30 Grade with cement wash along with Bi-RIDE logo @ every 4th panel , true to line and grade with c/c spacing between vertical post



not to exceed 3000 mm, leaving adequate space complete as per approved drawings and technical specifications.

**D. MISCELLANEOUS: INCLUDING ROADS, BARRICADING, QUALITY, INTERFACE WORK, CASTING YARD, SITE OFFICE AND EQUIPMENT, PERSONNEL ETC.**

- 1) Preliminary works such as site clearance, barricading, trial trenching etc., wherever required.
- 2) Designs and drawings of all the temporary structures
- 3) Road widening, side drains & other allied works, and construction of service roads at required locations
- 4) All temporary traffic diversion works, which will be required for the smooth flow of running traffic in order to carry out the works without any interruption including all safety precautions, signage, barricading, emergency lighting, traffic marshals, look-out men/ watchmen etc..
- 5) Tree cutting, preservation and disposal (or) translocation along the alignment for cutting / disposal / Translocation / afforestation in lieu of cutting / Translocation. Demolition of RCC framed structures, Brick masonry buildings including basement etc. as existing at site without making damage to adjacent structures, utilities and taking away and disposing all the debris and released materials etc.  
Geotechnical investigation bores as per the design requirement at every pier location of MJB to be carried out as directed by Engineer / Employer. ***No claim whatsoever will be entertained on account of any change encountered in strata while actual execution of the work on site as compared to geotechnical report enclosed in the tender document.***
- 6) Conducting survey and fixing benchmarks and alignment markers
- 7) Necessary permanent diversion of Utilities
- 8) Temporary barricading wherever required
- 9) Implementation of Project Quality Management Plan in accordance with ISO-9001:2015
- 10) Deployment of adequate manpower (Traffic marshals and watchmen) for management of traffic at intersection, junctions, traffic diversions etc.
- 11) Carrying out GPR survey to locate underground utilities up to 6m depth with a corridor width of 5mx5m grid as directed by Engineer.
- 12) Provision of sensors in structures for measurement of strain etc., as directed.
- 13) Demolition / dismantling of road, footpath, kerb stone, central verge, boundary wall, etc.as required.
- 14) Retrieved materials obtained from demolition / dismantling shall be the property of the owner. Acquiring and evacuation of the properties will be done by the concerned authorities.
- 15) Construction of temporary road as required for diversion / widening to facilitate the movement of traffic, dismantling of any existing roads / footpaths etc., for temporary diversion / widening and construction of temporary footpaths, diversion / widening for traffic diversion and its regular satisfactory maintenance as directed by Engineer / Employer.
- 16) Any other item of work as may be required to be carried out for completing the construction of at grade structure of specified length including all necessary interface works with station and system-wide Contractors in all respects in accordance with the provisions of the Contract and to ensure the structural stability and safety during and after construction works to be performed, including all general works preparatory to the construction and works of any kind necessary for the due and satisfactory construction, completion and maintenance of the works according to the intent and meaning of the drawings and technical specifications adopted, to best Engineering standards and orders that may be issued by the Engineer from time to time, compliance of all Conditions of Contract, supply of all materials, apparatus, plants, equipment, tools, fuel, water, strutting, timbering, transport, offices, stores, workshops, staff, labour and the provision of proper and sufficient protective works, diversion, temporary fencing, lighting and watching required for the safety of the public and protection of works on adjoining land; first -aid equipment, sanitary accommodation for the staff and workmen, effecting and maintenance of all insurances, the payment of all wages, salaries, fees, royalties, duties or the

other charges arising out of the execution of works and the regular clearance of rubbish, clearing of garbage /debris / pile heads from the embankment and premises of project, clearing up and leaving the site perfect and tidy on completion

- 17) Surveying by establishing DGPS control points and TBMs, True and proper setting out and layout of the works marking of alignment and pier locations, vertical & horizontal clearances for the elevated section including modifications, if any, as per drawings
- 18) No extra amount will be paid to re-do or to re-establish any of the survey points. The control points shall be fixed using DGPS double frequency and the accuracy of 1 in 50,000 or better shall be assured.
- 19) Providing temporary barricade as per the approved drawing, painting (including primer of approved quality) with synthetic enamel paint of approved colour, quality and brand, painting letters and logo of Bi- RIDE, including maintenance of the same duly cleaning the same on fortnightly basis and immediately repainting whenever required, arrangement for blinker lights on barricades during night as per requirement and as per the instruction of the Engineer.
- 20) Supply of caution watchmen at locations where caution orders is imposed and at all work sites near the IR track at the rate of one caution watchman per 8 hours shift round the clock with necessary three cell electrical torch, banner flags, hand flags etc. for continuous vigil and to exhibit necessary signals to the trains for their safe passage over the caution spot as directed by the engineer in charge.
- 21) Barricading should be rugged and fixed / anchored in ground firmly during the construction. It shall be maintained in position till completion of all works at the relevant location. Nothing extra will be paid for dismantling and re-erecting the barricades at a different location. The barricades shall be relocated as the work progresses and as directed by the Engineer.
- 22) Felling of trees of girth as directed (measured at a height of 1m above ground level) with lead and stacking of material including preservation.
- 23) Boring of 150 mm dia. (confirmatory bore holes), in all types of soil at each Pier locations (Locations to be decided by the Engineer) up to 3m in hard rock or 30m boring whichever is earlier and collecting core samples in rock for determination of core recovery, RQD and carrying out compressive strength test on rock samples.  
The scope shall include boring in soil, conducting SPT and collecting samples at 3m depth intervals and submitting bore log reports with soil classifications / SPT, Drilling 3m in hard rock with single/double barrel core for obtaining samples for testing of core recovery, RQD and compressive strength as per standard practice, Preparation and submission of report containing core recovery, RQD, Compressive strength at Hard Rock Locations with all lead and lifts and as per the directions of Engineer. The scope also includes refilling and reinstating surface and disposing off surplus materials.
- 24) Submitting colour photographs (soft copies and printouts of photos) of the works as directed by the Engineer at intervals as instructed by the Employer along with submission of MPR for every month.  
The photographs shall be submitted in 3 copies each of size not less than 225mm x 175mm each in album form, apart from 3 soft copies of all photographs. The photographs chosen should cover important activities of the work.
- 25) Submitting Drone digital video by showing the physical progress of works at an interval of every 3 months as per the Employer direction by suitable means of specified duration comprising one master copy and two extra copies duly editable version with BSTP Package 2 of corridor 2 alignment overlay with Geotagging in MP4 format and including Building infringement in respective to alignment, 3D Model – Auto Cad/sketch up compatible and Orthophoto – Geo ref JPG. Also, before VVIPs' inspection and high-level employer's meetings of the BSTP project.
- 26) Carrying out GPR survey to locate underground utilities up to 6m depth with a corridor width of 5 m x 5 m grid as directed by Engineer. The scope shall also include preparation of report and drawings both in soft and hard copy.
- 27) Diagonal Cross trenching works for identifying underground Utility at every Pier location to the required length, width and depth, which includes excavation in all types of soil, hard soil, rock, footpath, bitumen road, concrete

road, medians etc. cutting of all types road surfaces and backfilling the same with available excavated earth and reinstate road surface as per the authority requirement.

The scope also includes surveying and taking coordinates of the existing Utility and submitting the reports (hard & soft copy) of the same as per the directions of the Engineer.

- 28) Trenching for identification of utilities , temporary diversion and permanent diversion of if encountered during cross trenching.
- 29) Striking out of center line of alignment by using total station theodolite either before commencing work or after completion of earthwork on finished formation and fixing centre line stones of size 150x150x600 mm with CC 1:3:6 mix with 40mm metal in a pit of size 300x300x600 at every 100-meter interval on straight and at every 50m interval on curve etc.
- 30) Preparation of computer aided GAD / completion drawings in AO size in tracing film and 6 copies of ammonia paper print for each drawing by contractor with his own materials, manpower, tools and etc., complete with bridge details submitted by the railway and as directed by Engineer in charge. drawings in 7 copies, 1 tracing film, 6 ammonia paper print copies and soft copies should be handed over to Employer.
- 31) Dismantling of existing structures after ensuring necessary approval from the competent authority of the concerned department. The structures like culverts, bridges, buildings, retaining walls, Railway Platforms, Compound walls and other structure comprising of masonry, cement concrete, pre-stressed / reinforced cement concrete, brick / tile work in cement mortar, stone masonry rubble in cement mortar, stone pitching / dry stones spalls, removal of all types of Hume pipes, cement concrete pavements, kerb stones, BS slab / precast slabs of drain / footpath, paver blocks of footpaths, removal of silt or silt mixed with sand, etc. including T&P and scaffolding wherever necessary, including disposal of dismantled material with all lead and lifts including all labour, hire charges all machineries etc., complete by any mechanical means or any other means as direct by Engineer. Loading / Unloading G.I. sheets, rails, joists, built up sections, angles, C.I., Ductile pipes, A.C Pipes, or G.I. pipes RCC / PCC beams I slabs and other miscellaneous ironwork or woodwork.
- 32) The scrap materials will be the property of the contractor except the materials of local authorities (BDA, BBMP, BWSSB, BESCOM, BSNL, NHAI) and Railways.
- 33) Supplying and laying interlocking pre-cast CC block pavers of approved design factory manufactured of specified grade cement concrete on foot paths, circulating area, road junctions etc, including setting in position over 25mm thick bedding layer of fine sand, filling the joints with fine sand, levelling including compaction as per IS 15658, minimum of 80mm thick blocks of M35 grade for medium traffic
- 34) Supplying and laying of Hume pipes as directed by Engineer.
- 35) Supplying and fixing precast RCC gratings including cost of all materials, transportation, labour etc. complete (60x40 cm) with all lead and lifts
- 36) Tree cutting including uprooting of tree roots along the alignment of the corridor to facilitate the construction of corridor works.
- 37) Tree cutting, preservation and disposal (or) Translocation along the alignment for cutting / disposal / translocation / afforestation (as per the norms of Forest Department) in lieu of cutting / translocation
- 38) The applicable permits / permissions for felling of tress or Translocation shall be arranged by Employer, required assistance is lies with contractor for the same. The tree cutting and disposal is included in the scope of work. The cut trees will be the property of the contractor. However, the contractor shall deposit an amount not less than the Reserve Price of the trees (as fixed by Forest Department / BBMP) plus FDT (Forest Development Tax) to Bi-RIDE for onward transmission to Railways I BBMP / Forest Department, as the case may be.
- 39) Transportation for disposal of tree trunks, branches, roots, complete including loading and unloading as per BBMP / Forest and local authority guidelines.
- 40) Preparation of earth ball of tree roots of desired depth & diameters including necessary soil tests.
- 41) Dislodging, lifting, transportation and translocation tree from original place to the new place including all arrangements, labour etc. for successfully completing the work.
- 42) Translocation the marked trees of various species and specified girth to the place shown by the Engineer with

all lead and lift, tools, plant, men & machinery, and necessary preparation such as: Excavating pits of adequate size, arranging loose soil, mixing of manure, fertilizer, insecticides etc., to ensure survival of the trees being translocated

- 43) Maintenance of tree i.e., watering, soil heaping, spray of insecticides till the end of DLP or three years from the date of Translocation, whichever is earlier. All above operations shall be executed as per the specifications.
- 44) Providing & fixing hard drawn steel wire fabric reinforcement, straightening, cutting, cleaning, bending, tying, lap / butt welding placing including binding with mild steel annealed binding wire of 18 SWG in all structural concrete at all heights and depths, with all lead and lift. etc. complete as per drawing, specifications and directions of Engineer for fencing including vertical posts & RCC foundations for At- Grade Section.
- 45) Rain water harvesting: Providing and constructing the Rain water harvesting system in the median of the road / Embankments including boring / drilling of bore well of 300mm dia for casting / strainer pipes prescribed in the drawing, excavation in all type of soils / rock, constructing BW chamber, foundation, RCC top slab, plastering, CI manhole cover, filling / packing gravels in the chamber and the annular space in the bore, filling granules in the vertical pipe, laying HDPE pipe from piers to chamber, etc., complete as per the approved drawing
- 46) Transportation of all usable materials like B.S slabs / precast RCC slab, cement concrete blocks, interlocking paver blocks, kerb stones, steel items, telephone poles. Electric Poles to designated site as directed by Engineer by mechanical transportation including all lift, lead, loading, unloading, labour, machinery etc and handing over to the custodian instructed by Bi-RIDE.
- 47) Supplying and filling in foundations / backfilling in marshy / clayey foundation pits with granite / trap broken stones of 300mm and downsize with approved sand including hand packing, ramming, watering, including the Scope of all materials and labour with all lead and lifts etc., complete as directed by Engineer.
- 48) Design, build and maintain the Project & site offices fully furnished for the use of Employer/Engineer as per the layout drawing, specifications, & Employer Requirements-Scope of work. The contractor shall submit for approval of the Employer.
- 49) Providing Project Management Information System (PMIS) approved by the Employer, duly integrating the same with BIM software such that all documents generated by the contractor can be transmitted to the Employer and the Engineer by electronic means (and vice versa) and that all documents generated by either party are electronically captured at the point of origin and can be reproduced later, electronically and in hard copy. A similar link shall also be provided between the Employer's and Engineer's office at site (in Project offices and Site Offices to be provided by the contractor to Employer and Engineer) by the contractor.
- 50) Any other item of work as may be required to be carried out for completing the construction of At-grade structures as specified in drawings including all necessary interface works with infrastructure contractors, system contractors, etc. in all respects in accordance with the provisions of the Contract and / or to ensure the structural stability and safety during and after construction.

## **E. ROAD WORKS**

1. Direction and Place identification signs up to 0.9 sqm size board as per IRC:67
2. Portable barricades in construction Zone: Installation of steel portable barricade with horizontal rail 300mm wide, 2.5m in length fitted on a 'A' frame made with 45x45x5mm angle iron section, 1.5m in height, horizontal rail painted (2 coats) with yellow and white stripes, 150mm in width at an angle of 45 degree, 'A' frame painted with two coats of yellow paint, complete as per IRC: SP:55-2001 including cost of all materials, labour, loading, lead, lift, transporting etc., complete as per specification.
3. Traffic cones: Supplying of red fluorescent with white reflective sleeve traffic cones made of low-density polyethylene (LDPE) material with a square base of 390x390x35mm and a height of 770mm, 4Kg in weight, placed at 1.5m interval all as per BS-B73 including cost of all material, labour, loading, unloading, lead, lift, transporting, etc., complete
4. Retro-Reflectorized Road traffic signs: Supplying and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC: 67- 2001 made of high intensity grade micro prismatic HIP type-IV sheeting,

including lettering fixed over aluminum sheeting, 2 mm thick firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing

5. Manufacturing of Retro-reflective board - Caution Indicator / Stop indicator / Speed indicator / Whistle Board / any other board with 1.50 mm thick MS plate and MS plate stiffeners on M.S. T angles 75 mm x 75 mm x 6 mm and 4.75 m long approximately as per the specified drawing including cutting, drilling holes in the angles, providing hold fasts, bolts and nuts with washers of required size, bolting, welding.
6. Providing supplying and fixing in position, boundary pillars of standard design as per latest IRC with Bi- RIDE / Railway logo on it with reinforced cement concrete of M15 grade
7. Clearing and grubbing of land for roads, including uprooting of vegetation, grass, bushes, shrubs, saplings and trees of girth up to 300 mm.
8. Removal of earlier felled tree stumps and disposal of unserviceable materials and stacking of serviceable material (used or auctioned) with all lead and lifts including removal and disposal of top organic soil not exceeding 150 mm in thickness including all labour, hire charges of all machineries etc., complete with all lead & lifts by suitable machinery
9. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross section, and transportation with all & lift lead complete as per specifications, including scarifying the existing bituminous
10. Design and Construction of embankment for road work with approved materials gravel / Moorum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement complete as per specification, including cost of gravel / moorum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No.305
11. Design and Construction of sub grade and earthen shoulder with approved material Gravel / Moorum with all lifts & lead, transporting to site, Spreading, grading to required slope and compacted to meet requirement of table No.300-2 complete as per specification, including cost of earth, watering charges & compaction by vibratory roller to 97% of modified proctors density MORTH Specification No.305 including compaction
12. Design & Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite / trap / basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V revision
13. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to Wet Mix Macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications, MORTH specification No.406
14. Providing and applying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60kg per sqm using mechanical means complete as per specifications. Clause 502 of MORTH V revision.
15. Providing and applying tack Coat using 80 / 100 grade bitumen (VG10) on the bituminous surface at the rate of 0.25Kg per Sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of Road Surface) as per Specifications. Clause 503 of MORTH V revision.
16. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 505 of MORTH V revision. Using 40 I 60 TPH capacity H.M.P with sensor paver Gr-II with 4.5% VG-30 Bitumen.
17. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade,

level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects as per specifications. Clause 507 of MORTH V revision. Using 40 I 60 TPH capacity H.M.P with sensor paver Gr-II with 5.4% VG-30 Bitumen.

18. Filling potholes and patch repairs with bituminous concrete.
19. Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface I Concrete Surface. Painting lines, dashes, arrows etc., on roads in two coats on new work with ready mixed road marking paint conforming to IS: 164 on bituminous surface.
20. Painting two coats on new concrete surfaces: Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces including cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete as per specification
21. Road delineators: Supplying and installation of delineators (Roadway indicators, hazard markers, object markers), 80-100cm high above ground level, painted black and white in 15cm wide strips, fitted with 80x100mm rectangular or 75mm circular reflectorized panels at the top, buried or pressed into the ground and conforming to IRC-79 as per drawings including cost of all materials, labour, loading, unloading, lead, lift, transporting, etc., complete as per specification.
22. Supplying and fixing pre cast solid concrete kerb stones made out of M15 I 20 (CC 1:2:4) and finished with CM 1:3 Plastering and finishing, cutting, with all lead and lifts etc., complete of size 450 x 200x 400mm.
23. Construction of Public Roads in At Grade location with the approval of local authorities in all terms, wherever required as directed by Engineer/Employer.

## **1.2 Clearances, Investigations and Reinstatement**

- 1.2.1 The Permanent Works shall not infringe the IR / Metro railway Structure Gauge as confirmed by the project Schedule of Dimensions (SOD).
- 1.2.2 The Permanent Works shall allow for provisions for the installation of IR / Metro railway operating equipment without infringement of the structural gauge as confirmed by the project Schedule of Dimensions (SOD).
- 1.2.3 The Contractor shall request the Engineer's approval prior to demolishing any building or structure.
- 1.2.4 The Contractor at all times shall minimise the impact of the Works on traffic flows. All traffic diversions, height clearances, road narrowing, and any other restrictions shall be approved by the appropriate Authorities and the Engineer before work commences.
- 1.2.5 The Contractor is responsible to obtain No Objection Certificates (NOC) & Completion Approval for all utility and traffic diversions from the concerned Statutory Authority or utility Owner
- 1.2.6 The Contractor shall carry out all reinstatement works to the satisfaction of all Stakeholders, Statutory Authorities and the Engineer.
- 1.2.7 The Contractor shall verify the survey information provided by the Employer/Project Partner. The Contractor's survey shall only be used for the basis of the design of the works. Any discrepancy found needs to be resolved before the commencement of work. The survey information shall be shared, verified and confirmed with other Project Partners.
- 1.2.8 The Contractor is advised to conduct further investigations considered necessary by them at their own cost. Any error or discrepancy found in the Employer's / Project Partners data at any stage will not constitute grounds for any claim for an extension of time or cost.
- 1.2.9 Contractor shall take necessary approvals from Statutory department like IR, BBMP, BMRCL, BESCO, BWSSB, Pollution control board, KPTCL, Gas pipe, Traffic etc.,

## **1.3 Detailed Scope of Works**

- 1.3.1 The Contractor shall carry out subsurface trial trenches to locate underground utilities for the foundations.
- 1.3.2 The Contractor shall carry out geotechnical borehole soil investigation for foundation design at every alternate pier location.
- 1.3.3 Deleted

- 1.3.4 The Contractor shall fully coordinate and interface their design and construction work with those prepared by Project Partners.
- 1.3.5 Logistics Areas  
The Employer will not provide any land for logistics areas, casting yards or offices. The Contractor shall identify the land they require and procure the same at their own cost.
- 1.3.6 The Permanent Works shall be constructed in such a way that, when maintained in accordance with the Contractor's Operations and Maintenance manuals, the structures will remain serviceable for a minimum 100-year design life.
- 1.3.7 The Contractor shall develop their construction methodology to suit the areas provided for the Works including but not limited to the special design wherever needed on the stations, ramps and other locations.
- 1.3.8 Deleted.

#### 1.4 Design

- 1.4.1 A Designer or Designers shall be employed by the Contractor. The Designer(s) shall have relevant experience as defined in Qualification of Tenderer of **Section-II** for designing of BSTP/IR/Metro. The Contractor shall provide full details of the Designer(s) past experience and details of the proposed design discipline leads for the Engineer's/Employer approval.  
The Contractor may propose to carry out the design work in-house if they have a design office with an experienced design team capable of carrying out the design work for this Contract. The in-house design team should have the relevant experience as prescribed above for the Designer. The Contractor shall provide full details of his design team's past experience and details of the proposed design discipline leads which he intends to deploy for the Engineer's approval.  
To ensure progressive design assurance is achieved the Designer(s) discipline leads (including Key Personnel) shall be available at all times for design meetings and workshops with the Engineer and shall be located in Bengaluru.

The Permanent Works shall be designed and constructed in such a way that, when maintained in accordance with the Contractor's Operations and Maintenance manuals, the structures will remain serviceable for a minimum 100-year design life.

- 1.4.2 The Contractor shall develop their design and construction methodology to suit the areas provided for the Works including but not limited to the special design wherever needed on the stations, ramps and other locations.
- 1.4.3 The Works shall be designed to the Employer's requirements and all relevant current codes, specifications and drawings or as otherwise directed by the Engineer.
- 1.4.4 The design shall be fully coordinated for all disciplines including systems installations. The Contractor shall design all disciplines in a fully coordinated BIM 3D model to minimise clashes, which shall be shared with other Project Partner Contractors and Stakeholders, and this shall be carried out on a common digital platform to which the Engineer and other Project Partner Contractors will be provided access.
- 1.4.5 The **Contractor shall appoint a proof check consulting agency (the "Proof Consultant") after proposing to the Engineer & Employer a panel of 3 (three) names of qualified and experienced firms and Engineer will the approval of Employer will select 1 Proof Consultant from panel.** The Parties agree that no firm or person having any conflict of interest shall be engaged hereunder.

#### 1.5 Interface and Coordination

- 1.5.1 The Contractor shall to the satisfaction of the Engineer, coordinate, interface and cooperate with all Stakeholders and Project Partners including all external Agencies and Authorities.
- 1.5.2 The Contractor shall fully co-ordinate the design and construction of his Works with Project Partners, but not limited to Viaduct, Track, Solar Panel, Depot, Rolling Stock, Signalling and Telecommunication, Automatic Fare Collection (AFC), Passenger Screen Doors (PSD) and Vertical and Horizontal Transportation Systems (VHTS).
- 1.5.3 The Contractor shall include and cooperate and coordinate by provision for the Project Partners equipment movement and installation by providing suitable access routes, staircases, cut/box outs, sumps, service

corridors, cable troughs on the station area, raceways, conduits, fixtures, inserts, clearances etc.

- 1.5.4 Earthing and lightning protection shall be provided and fully coordinated with Project Partners.
- 1.5.5 Prior to the Taking-Over Dates, early agreed access shall be provided to other Project Partners appointed by the Employer, to carry out their works. Material and equipment supply delivery routes shall be coordinated and provided to the Project Partners. The security of materials and equipment brought to the site by other Project Partners shall be their responsibility.
- 1.5.6 The Contractor shall conduct, and coordinate interface meetings intimated to the Engineer, and adhere to the decisions taken at the meeting approved by the Engineer.
- 1.5.7 Any coordination or interface disagreements with other Project Partners shall be informed to the Engineer. If the Contractor despite having taken all reasonable efforts cannot resolve such disagreements, then the decision of the Engineer shall be final and binding on the Contractor.
- 1.5.8 Access shall be provided to the staff and labour of the other Contractor appointed by the Employer for carrying out their works and bringing materials and equipment at the site. However, the security of materials and Equipment brought at the site will be the responsibility of the respective Contractors.

## 1.6 Utility Diversions

- 1.6.1 Utility identification at foundation locations shall be carried out by the Contractor in advance. The Contractor shall modify the reference structural design confirmed in the Tender Drawings to save the utilities as directed by the Statutory Authority within the accepted Lumpsum price.. The relocation/diversion of the utility shall be undertaken by the contractor. The removal/diversion plan shall be approved by the Utility owning agency.
- 1.6.2 The Contractor shall be responsible for design, diversion plan, getting approval, co-ordination and supervision of execution of works pertaining to relocation/shifting/removal of above and below ground utilities, through respective Utility agencies. The payment for these Items will be made under **Schedule C of Price Schedule**'. Any delay in completion of these works shall not relieve the Contractor's obligation and it shall be at Contractor's own risk and cost.
- 1.6.3 Utility services that may require removal/diversion or protection while carrying out the scope of work under this Contract may include, but are not be limited to water supply, sewerage, storm water pipes, gas, electricity, telecommunication cables (including fibre optic), military and security, police utilities, medical utilities, sewage and storm water etc.
- 1.6.4 The diversion of overhead and underground electric transmission lines above 33kv shall be arranged by the Employer directly through the utility owning Agencies/ statutory authorities and shall be paid directly by the Employer.
- 1.6.5 Tree cutting, relocation, Afforestation and plantation shall be carried out as per **SCHEDULES -SITE OF THE PROJECT Annexure-1 of Section VIII-Employer's Requirements –Vol 2**. However, grass, lawn, herbs, shrubs, plants, and others which are not to be transplanted/removed by the owning agencies shall be removed by Contractor.
- 1.6.6 The Contractor shall ensure that any salvage materials are returned to the utility owning agencies.
- 1.6.7 The demolition, dismantling and disposal of building structures such details will be advised progressively during the progress of the Contract work and the cost towards the same shall be paid under relevant items of **Schedule C** of Price Schedule.
- 1.6.8 The Contractor shall remain responsible for any works carried out by his Subcontractor, Vendors, Utility owning agencies within the right-of-way and/or the construction site boundaries.
- 1.6.9 Utility Diversions include but are not limited to the following scope of work: and the cost is included in the lumpsum price
  - a. Verify the correctness of all drawings showing utilities provided by the Employer, Engineer and Statutory Authorities;
  - b. Relocation/diversion of utilities as deemed necessary, and agreed by the Engineer, to enable the execution of the Works;



- c. Construction of temporary traffic diversions where the construction of the works for the utility diversion interrupts existing public or private roads or right of way;
- d. Provision and submission to the Engineer/Employer and Statutory Authorities of AutoCAD drawings and diversion construction methodology showing details of the utility locations and depth before and after relocation, supported by photographs; and
- e. Protection of utilities that are not to be diverted during the execution of the Works as per the Employer's Requirements.

1.6.10 In the process of either identifying, relocating or protecting the public utility services located within the right-of-way and/or the construction site the Contractor shall:

- a. Obtain all necessary approvals/ NOC if necessary, from the relevant authorities to carry out the investigations to identify the location of all existing public utilities within the right-of-way and/or the construction site boundaries;
- b. Provide accurate records of existing public utilities identified to the Engineer, prior to commencement of the Works;
- c. Provide accurate records of any additional public utilities encountered and take all necessary steps to prevent damage to and to safeguard such services;
- d. Draft any utility diversion design plan in accordance with the applicable standards as approved by the relevant Statutory Authorities;
- e. Cooperate with any other Stakeholders involved so as to avoid interference with other Project Partner Contractor operations e.g. an independently appointed Enabling Works Contractor;
- f. Cooperate with the public utility authorities to safeguard and minimise the disruption of service;
- g. Erect suitable barricades around all trenches dug during utility identification or diversion
- h. Construct temporary traffic diversions where the construction of the works interrupts existing public or private roads or right of way but only after first obtaining approval from the relevant authorities;
- i. Prepare shop drawings, approved by the relevant authorities and the Engineer, before commencing any diversion of utilities;
- j. Construct support and/or protection, as approved by the Utility Authority and Engineer, for those utilities that do not require diversion during construction;
- k. In the event of a service being interrupted as a result of damage caused by the Contractor or Subcontractor, promptly notify the authority concerned and inform the Engineer of the incident. The Contractor shall be responsible for all costs for damage repairs that are required to restore the services and any consequential damages;
- l. Ensure that adequate insurance cover is in place at all times, as approved by the Engineer, to cover all liabilities that may result as a consequence of accidental disruption of any utility service;
- m. Make substitute arrangements, as directed by the concerned Utility Authority, until such time that any damage caused to utility services by the Contractor or Subcontractor has been repaired at the Contractors own expense; and
- n. Submit a copy of all 'As-Built Drawings' to the relevant authorities and Engineer and obtain a completion certificate from the relevant service authority once of the awarded works related to removal, utility diversion, relocation and protection have been completed.

1.6.11 The Employer retains the right to select and appoint the party responsible for carrying out the Utility Diversions scope of work, either in its entirety or to allocate certain parts of the scope of work.

#### **F Deleted**

#### **G. SALIENT FEATURES OF DESIGN & CONSTRUCTION AND OTHER INSTRUCTIONS**

- 1) Preliminary works such as site clearance, barricading, trial trenching etc., wherever required, shall be taken up simultaneously along with mobilization activities.

- 2) All the concerned structures shall be designed for the gauge and the loading standard given in the SOD & DBR of BSTP.
- 3) The contractor shall design all the structures, ensuring 5.5 m vertical clearance above the existing road level & adequate vertical clearance at Railway crossings as per the SOD.
- 4) Any new design or span arrangement being proposed by the tenderer shall be in conformity with the contemporary best practice. The alignment crosses the existing railway lines at some locations. Some spans shall have to be designed as special spans / obligatory spans for crossing the existing railway tracks.
- 5) Design and Construction of pile foundations / Open foundation including pier/pier cap abutment , bearing pedestals, bearings, shear keys, seismic restrainers, hold down devices etc. complete if required . Provision of Seismic restrainer is mandatory.
- 6) If at any location, if permanent liners are required, they shall be provided and no additional cost shall be paid against to the item.
- 7) Stray current corrosion prevention measures (including extra rebars in various RCC / PSC structural members) for earthing shall be adopted wherever necessary.
- 8) Preparing detailed designs, general drawings and working drawings for various components of the works and obtaining approval in respect thereof from the Engineer, inclusive of incorporation of all modifications, alterations, changes, etc. shall be carried out as per the direction of Engineer & Employer
- 9) The shape and appearance of piers shall be decided by Employer from Aesthetics and economy point of view. The maximum eccentricity of alignment center line from the center line of pier is given in the GAD for reference.
- 10) All spans shall have similar GI brackets for cables, walkways, parapets and railing arrangements Approval of Engineer / Employer will be after checking of the same by the Engineer. Suitable sleeves for PVC pipes along with insert plate will be in the scope of contractor
- 11) Rapid construction is essential for the project, due to strict requirements on work zone safety, traffic control during construction and working adjacent to railway track with OHE lines.
- 12) All necessary safety precautions shall be taken at casting yard during transportation and erection adjacent to railway tracks. The contractor is solely responsible for any untoward incident due to unsafe practices. Suitable capacity cranes of adequate numbers required shall be mobilized. Suitable supporting system shall be provided for pre-stressing activity and its equipment. A suitable supporting system for stability of erected pier segments shall be provided at site as directed by Engineer, if required.
- 13) Doglegged staircases of adequate numbers shall be provided for accessibility and inspection. The price quoted shall be inclusive for the above work.
- 14) For all spans, the design shall be done by the contractor and shall be approved by Engineer / Employer. The design of bearings, shear keys of seismic restrainers, hold down devices, if required, shall also be done by the contractor, which shall be approved by Engineer / Employer.
- 15) Solar panels are planned to be fixed over ERS wall. all fixtures required to mount the panels shall be fixed by the contractor at his own cost.
- 16) Filling of pile cap/Raft foundation/Open foundation etc area shall be done with good earth, GW/SW Good earth means gravel, moorum, (excluding clay and silt) & similar to the soil which is used for earth work in embankment. Further details are in the technical details of the tender document.
- 17) The girders may be tapering in plan and shall be cast true to the profile by suitable formwork system.
- 18) The location of piers/abutments shall be proposed by the contractor and before proposing those locations for the approval of the Employer through the Engineer, the feasibility of providing the same shall be verified at site by the contractor involving all the stakeholders. The locations should be in such a way that

they do not disturb the road layout or any other obligatory point such as structures, Utilities etc., and do not obstruct water flow, if any. The decision of Employer is final in this regard

- 19) Some of the major Utilities cannot be diverted. The contractor shall take into consideration the existence of these Utilities and propose the foundations of piers of BSTP with strengthening the utilities at these locations accordingly.
- 20) Before carrying out the work at site, necessary permissions from various local agencies like BWSSB / GAIL / BSNL / BESCOM and Railway authorities / Road authorities such as SWR, NHAI, BBMP, PWD, Traffic Police etc., shall be required to be obtained by the contractor. The Employer will assist only by way of issue of necessary support letters.
- 21) The levels, measurements and other information concerning the existing site as shown on the drawings are believed to be correct and indicative, but the contractor shall verify them himself and also examine the nature of the ground as no claim or allowance whatsoever will be entertained on account of any error or omission in the levels or strata turning out different during execution from what is shown on the drawings. The contractor should validate the L- Section and horizontal / vertical by ensuring best fit alignment without any speed reductions in the design speed using applicable latest software.
- 22) The permanent traffic diversions shall be carried out in consultation with traffic police. Contractors shall provide traffic diversion proposals, traffic marshals, cones, traffic diversion boards etc., as desired by Traffic Police. The text for painting will be given by Engineer / Employer.
- 23) Maximum width of median including crash barrier shall be limited to 3m (if median is required).
- 24) The road works and allied works shall be carried out in co-ordination with BBMP as per MORTH specifications. On award of work, the contractor shall start the road work along and complete the same.
- 25) The applicable permits for felling of trees , translocation shall be arranged by the Employer. However, required assistance will be provided by the contractor. The tree cutting and disposal shall be arranged by the contractor and the scope is inclusive of the same. The cut trees will be the property of the respective owning agency. However, the contractor shall deposit an amount not less than Reserve Price of the trees (as fixed by Forest Department / BBMP/Railways) plus FDT (Forest Development Tax) to Bi-RIDE for onward communication to Railways / BBMP / Forest Department, as
- 26) The GTI report of tender document is based on preliminary investigation, and it is tentative and for reference only. In case of any variation in Geotechnical details during construction, no claim (Financial or otherwise) shall be entertained by Employer
- 27) The contractor to fix alignment reference points at regular intervals all along the alignment. The contractor along with the Engineer should verify the details of these alignment pillars.
- 28) GFC drawing requirement shall be planned by the contractor based on his three-month rolling programme and the GFC drawings shall be issued accordingly.
- 29) The contractor shall make the detailed traffic diversion plans in consultation with Bengaluru Traffic Police. The work is to be executed with proper liaison with Bengaluru Traffic Police. Necessary assistance will be given by Employer. The scheme should be such that a minimum of two lane of traffic on each direction of the road should be available for the smooth flow of traffic. The contractor shall inspect the site and submit the traffic diversion plan to concerned traffic police authorities for approval..
- 30) The contractor shall liaise with the Utility Authorities for carrying out the work expeditiously, wherever required, so that works at particular locations are not delayed. In case he comes across any uncharted utilities also he shall liaise with the agency concerned for necessary diversion; the cost of diversion shall be paid by Employer under the relevant item of Price schedule, Contractors shall provide any temporary support for the utilities, if needed, but at no extra cost. If temporary diversion is necessary, it shall be taken up by the contractor in consultation with concerned utility owner, and necessary payment will be made for such diversion one time only under relevant items of price schedule.
- 31) The contractor shall provide temporary barricading during construction at site, work areas (i.e., Construction

Depot, store, site office, casting yard etc.) and locations where road vehicles / pedestrians are moving, along the At-Grade section / Construction sites as directed by Engineer. The temporary barricade of 2m height along the alignment near to railway boundary / acquisition line and road footpath and the railway standard barricade along the alignment in between IR tracks and BSTP tracks are included in the scope of work for At-grade section. In elevated section, the temporary barricade of 2m height along the alignment near to railway boundary / acquisition line, road footpath and in between IR and BSTP tracks are included in the scope of work. The work shall be executed as per the technical specifications. The contractor shall provide & maintain barricading as per the drawings.

- 32) Any untoward incident due to any gaps in barricading will be the sole responsibility of the contractor. The barricade and its efficiency shall be monitored by dedicated staff of the contractor all the 24 hours till completion of the work.
- 33) Adequate blinking lights on barricade during night time must be ensured. The cost of this item should include provision for power pack / Generator set/solar etc. so as to ensure the blinking of lights in night time as long as barricades are in position at the work spot.
- 34) After completion of the entire work, the barricades shall be removed by the contractor and transported away from the Right of Way.
- 35) In case the Railway land / Govt. land is arranged near the railway track for casting of Girders & for initial erection and launching activity temporarily, the necessary land rent / lease charges shall be levied as per Railway guidelines / Govt. norms / Bi-RIDE norms and the same will be deducted from RA bills of the contractor.
- 36) In addition, the contractor shall be required to carry out various interface works as per interfacing requirements.
- 37) The necessary interfacing, / liaison and arrangements with systems contractors shall be done by the contractor and shall form part of the work. Inserts for Electrical, OHE, signaling etc., shall be provided as per drawing and the amount is included in scope.
- 38) The land for setting up casting yards, stacking yards, offices etc., as required, shall be arranged by the contractor at his own cost. No land for casting yards / stacking yards / project offices / site offices / laboratories / contractor's offices / camps etc., will be provided by the Employer. The Employer also does not guarantee any vacant railway land for these purposes. However, assistance can be provided by the Employer by giving recommendation letters etc., to the concerned authorities and it is the responsibility of the contractor to find out and arrange lands etc. for the above.
- 39) The contractor shall carry out as soon as possible, but not later than the deadlines specified,
  - a. Setting up of fully fledged site laboratories, as per the requirements.
  - b. Setting up concrete batching & mixing plants.
  - c. Setting up of Contractor's site offices.
  - d. Casting yards with complete facilities
- 40) The contractor shall implement a Project Quality Management Plan in accordance with ISO-9001:2015 "Quality System – Model for Quality Assurance in Design / Development, Production, Installation and Servicing" or any other system as approved by Engineer to ensure that all materials, workmanship, plant and equipment supplied, and work done under the contract meets the requirements of the contract.
- 41) The contractor shall provide the Key Personnel as per **Appendix-04 of Employer Requirement Annexure-1.**
- 42) The contractor shall provide the Key Plant and Equipment as per **Appendix-05 of Employer Requirement Annexure-1.**
- 43) The contractor shall provide and maintain Office accommodation, equipment, appliances, personnel etc. as per **Appendix 13 of Employer Requirement Annexure-1.**

- 44) Formation grade of Siding line, stabling lines, pocket tracks and cross overs as shown in the drawings and are in the scope of work.
- 45) GADs attached with this tender are for the tentative location of piers. However, they should be verified at site for feasibility. Contractor's Design team shall explore alternate proposals for Engineer / Employee approval if required as per site condition.
- 46) Providing concrete for all works deemed to be inclusive of the cost towards design mix production of concrete by batching plant, transit mixer, transportation of concrete with all leads and lifts, form work, shuttering including staging as required, pouring of concrete by pump/ tower crane to all heights / depths, tremie or other approved means, compaction by vibrators, curing by approved means such as water, and all labour, tools, plants, machinery required for execution of work complete in all respects including de-shuttering after completion of work and rendering & finishing etc.
- 47) Shuttering required for concrete work shall be of steel except wherever there are site constraints as decided by the Engineer.
- 48) It is also informed that the area available for launching of girders full span is limited in certain stretches in the at grade construction and there may be difficulties in keeping girders directly below the span within the base width of overhead launching assembly. The tenderer shall inspect and conduct a survey for studying the field constraints and quote their rate / amount accordingly to perform the contract.
- 49) Boring of 150 mm dia. (confirmatory borehole shall be done at at location as decided by engineer), in hard rock or 30m boring whichever is earlier and collecting core samples in rock for determination of core recovery, RQD and carrying out compressive strength test on rock samples.
- 50) Diagonal Cross trenching works for identifying underground utility , Retaining Wall location, sacrificial wall and wherever required as directed by engineer etc., to the required length, width and 2.5 mtr depth, which includes excavation in all types of soil, hard soil, rock, footpath, bitumen road, concrete road, medians etc. cutting of all types road surfaces and backfilling the same with available excavated earth.
- 51) Design and Drawings shall be developed in conformity with the Specifications and Standards set forth in Schedules and Employers Requirement and scope of work. The contractor shall appoint a proof check consultant (the "Proof Consultant"). If demanded by "Client" or "The Engineer", third party proof check shall be done without any financial implication. Contractor shall submit detailed designer's organization chart to the Employer.
- 52) Wherever night working is carried out by the contractor, temporary lighting arrangements as per approved layout shall be provided, installed, maintained for the duration of the contract.
- 53) The contractor shall at all-time carryout the work on either side of existing IR tracks / highway / road service road in a manner creating least interference to the flow of traffic. The contractor shall take prior approval of the Engineer, Railways and traffic police regarding traffic arrangements and diversion of traffic during construction.
- 54) The contractor shall take suitable and sufficient measures as per SHE manual for working at night.
- 55) The bridges have unique design and therefore their actual performance in field is required to be monitored with respect to the design parameters. The settlement of foundation, deflection of super structure, deformations, loss of camber etc., to be monitored by the contractor and the cost is included in the Scope
- 56) The debris and waste materials of the median shall be cleared and disposed properly.
- 57) The scope of work shall include detailed survey of the alignment for the at grade section, soil investigation where ever, fixing an optimized span configuration avoiding shifting of utilities. The contractor is advised to carry out his own investigation and collect necessary site details while quoting his rates. Bi-RIDE will not be responsible for any cost implications due to any hindrance due to Utilities falling in the alignment. The chainage / drawings of major utilities which may not be possible to be shifted shall be identified by the contractor in advance, and the contractor is advised to consider the same while planning / locating the foundation. Utilities may be verified by contractor physically at site. The contractor shall

ensure that no foundation of pier is located throughout the length in such locations. If at all, the contractor is required to take up diversion of uncharted utilities, payment towards the same shall be made as per **Schedule C Price Schedule**.

- 58) Demolition / dismantling of RCC framed / steel structures /bridges, buildings, masonry buildings, station platforms, compound walls, drains, Toe walls & retaining walls including basement, ground and above floors as existing at site on the alignment without making damages to the adjacent structures, Utilities, etc. including disposing off retrieved materials out of the site of work.
- 59) Contractor shall get necessary permission / NOC from the Railway, Road, Police and other concerned regulatory authorities for blocking services and working in such locations Bi-RIDE will provide assistance like issue of letter and coordination for meeting concerned officials.
- 60) Contractor shall study traffic pattern all along the Corridor & ensure optimized at the detailed design stage taking into consideration of traffic requirement and width of road.
- 61) Disposal of surplus materials including excavation spoils etc., to the dumping site approved by the Employer / Engineer.
- 62) Nallah diversions and drain diversions are in the scope of work.
- 63) True and proper setting out of the layout, benchmarks and provision of all necessary labour, instruments and appliances for survey as specified or as directed.
- 64) The cost of final carpeting of the roads or new road construction before handing over the roads to road owning agency is included in the scope.
- 65) Also, final restoration of footpaths as per modified specifications and drawings, as per requirements of the road owning agency, is also included in the scope.
- 66) Deployment of adequate traffic marshals and provision of traffic signboards, hand delineators, portable signals etc., and as accepted by Employer & the cost is included in the Lumpsum Price/ Price schedule..
- 67) All aspects of quality assurance, including testing of materials and other components of the work, as specified, or as directed are in scope. Nothing extra payable on this account.
- 68) The contractor shall ensure cleanliness of the roads and footpaths by deploying manpower for the same. The contractor shall ensure proper brooming, cleaning and washing of roads and footpaths at regular intervals or as and when required or directed throughout the entire stretch till the currency of the contract including disposal of sewage. Regular interval implies that Roads and Foot-paths should be maintained in clean condition throughout. Nothing extra is payable on this account.
- 69) Results of sub-surface investigations conducted at the project site are enclosed with the tender document. This information about the soil and sub-soil water conditions is being made to the contractor in good faith and the contractor shall obtain the details of investigation independently. No claim whatsoever on account of any discrepancy in the sub surface conditions that may be actually encountered at the time of execution work and those given in these tender documents shall be admissible to the contractor under any circumstances.
- 70) The contractor should find out the capacity of the quarries and accordingly plan procurement of coarse / fine aggregates either from the existing quarries or establish their own quarries and crushing arrangements.
- 71) It is the responsibility of the contractor to thoroughly examine the site of work and all constraints before submitting the bid.
- 72) Any services affected by the works must be temporarily supported by the contractor. The work of temporarily supporting and protecting the public utility, services during execution of the works shall be deemed to be part of the contract. the amounts are included in scope of schedule Nothing extra shall be payable on this account.
- 73) The contractor shall take all precautions for safeguarding the environment during the course of the

construction of the works. He shall abide by all laws, bye-laws, rules and regulations in force governing pollution and environmental protection that are applicable in the area where the works are situated. The contractor must take all necessary steps, especially to avoid dust nuisance during construction of the works.

- 74) Levels, measurements and other information concerning the existing site as shown on the drawings are believed to be correct and indicative, but contractors should verify them for themselves and also examine the nature of the ground as no claim or allowance whatsoever will be entertained on account of any error or omission in the levels or strata turning out different during execution from what is shown on the drawings. The contractor should validate the L- Section and horizontal alignment using applicable latest software.
- 75) Any incidental works required to be carried out in this regard shall be the responsibility of the contractor and the amounts are included in the scope of schedule. Nothing extra shall be payable on this account. In case any new items are required for such work, the same will be processed as per the need on mutual consent.
- 76) Preliminary works such as site clearance, barricading, trail trenching etc., wherever required, shall be taken up simultaneously along with mobilization activities.
- 77) The contractor shall at all-time carry out the work on either side of existing IR tracks I highway / road / service road in a manner creating least interference to the flow of traffic. The contractor shall take prior approval of the Engineer and traffic police regarding traffic arrangements and diversion of traffic during construction.
- 78) Works to be performed shall also include all general works, including Road widening and allied works of any kind necessary for the due and satisfactory construction, completion and maintenance of the works to the intent and meaning of the drawings adopted and technical specifications, to best Engineering standards and orders that may be issued by the Engineer from time to time.
- 79) Road works and allied works shall be carried out as per BBMP as per MoRTH specifications.
- 80) Road widening works, wherever required, are in the scope of contract. Further if diversions of roads need any upgradation, as desired by the Employer I Engineer, the contractor shall carry out the works. Road widening and drainage work shall be completed before the commencement of At-grade/Bridges section work at any particular location.
- 81) Restoration of Road and allied works shall be done immediately after completion of work up to road level or as per instructions of Employer / Engineer.
- 82) Tree cutting and (or) translocation along the alignment shall be arranged by the Contractor at her / his own cost. The applicable permits / permissions for felling of trees or translocation will be arranged by Employer. However, no clear time limits can be specified for the same.
- 83) Demolition of RCC framed structures, Brick masonry buildings including basement etc. as existing at site without making damage to adjacent structures, utilities and taking away and disposing all the debris and released materials etc., shall be done by contractor, the amount of the same is included in the price schedule.
- 84) All disposable excavated material shall be collected and transported for disposal at contractor's dumping yard, which shall be approved by the relevant authorities. The dumping yard area cannot be provided by the Employer
- 85) The tyres of the vehicles leaving site shall be cleaned with Jet Wash to avoid spillage of earth / mud on public roads. The contractor shall ensure cleanliness of public roads and footpaths, through which contractor's vehicles / personnel move, by deploying manpower for the same. The contractor shall ensure proper cleaning and washing of roads and footpaths on all the times throughout the entire stretch till the currency of the contract including disposal of sweep age. Nothing extra shall be payable on this account.
- 86) While planning for the work of transportation of bridge construction materials to the bridge site, the finished

formation of earth work in banks and cuttings with or without blanket layer should not be used for plying of trucks or other vehicles used for transportation. This restriction has specially been imposed to save the top surface of the formed formation from forming pits and ruts, which later are likely to accumulate water and pose problems for maintenance.

- 87) Contractor shall be required to mobilize resources for taking up work at a number of locations simultaneously. Planning of resources may be done at least to meet these requirements.
- 88) The bidder may ascertain availability of suitable/ preferred type of soil for embankment and lead / lift involved before quoting his rates / price.
- 89) Maintaining and keeping the Existing Railway banks, structures and adjacent roads clean in the area of work and where construction machineries ply is the responsibility of the contractor.
- 90) Sufficient measures to minimize water, air and noise pollution at / near the area of the work shall be undertaken by the contractor.
- 91) Clearing of site and handing over of all the Works, as specified or as directed by Employer shall be ensured.
- 92) Maintenance of the completed Work during the maintenance period as directed by Employer shall be ensured.
- 93) Submission of completion (i.e., 'As Built') drawings and other related documents as specified shall be ensured.
- 94) Contractor shall not display any name-board for the works without the written permission of the Employer.
- 95) No labor camp shall be allowed at work sites or any unauthorized place. The proposed sites for labour camps shall be approved by the Engineer / Employer.
- 96) All goods and materials to be incorporated in the works shall be new, unused, and of the most recent or current models, and they shall incorporate all recent improvements in design and materials, unless provided for otherwise in the contract.
- 97) If Employer wishes to engage third party consultants for quality control assessment, apart from the quality control and field tests by the Employer, the contractor shall co-operate with both Quality control authorities and the third party.
- 98) The above list is not exhaustive. Any other minor requirement inadvertently missed out in the above list, shall be complied with. The contractor shall execute the work as per the requirement of BSTP and as per the latest and best engineering practices. In case of any dispute, the decision of Employer is final in this regard and with regard to whether the requirement is minor or not.
- 99) Supplying & laying of drainage composite for use behind abutments, wing walls, return walls and Retaining walls Geo-composite drain (Vertical) as per RDSO Specification No. RDSO/2018/GE:IRS-0006 latest version with all material, labour, equipment, tools and plants, lead, lift etc. complete in all respects as per the direction of Engineer-in-Charge.
- 100) Supply, installation of factory fabricated, perforated, hot dip galvanized, double bended cable trays from 2 mm thick sheet steel continuously connected including inward, outward, horizontal & vertical bends, reducers, tees, flexible earth connector and other accessories. Trays shall be dully supported with suitable approved make anchor fasteners, vertical GI rods of 12 mm dia / GI rigid angle supports, etc. or installed on suitable wall supported brackets as required complete as per specifications. All the cable tray accessories shall be factory pre-fabricated, until otherwise specific approval is obtained to fabricate at site

Note: Trays shall be supported adequately using galvanized structural members. This support should be capable of withstanding the weight of the cables laid over it. Rigid ISA / ISMC / ISMB / flats support should be provided at every 3m length and also at diversions, crossings, bends and multi layered locations. Cost for additional supports shall be paid separately. 300 mm wide & 50 mm depth.



- 101) Supply, installation of factory fabricated, perforated, hot dip galvanized, double bended cable trays from 2 mm thick sheet steel continuously connected including inward, outward, horizontal & vertical bends, reducers, tees, flexible earth connector and other accessories. Trays shall be dully suspended from the ceiling with suitable approved make anchor fasteners, vertical GI rods of 12 mm dia / GI rigid angle supports, etc. or installed on suitable wall supported brackets as required complete as per specifications. All the cable tray accessories shall be factory pre-fabricated, until otherwise specific approval is obtained to fabricate at site  
Note: Trays shall be supported adequately using galvanized structural members. This support should be capable of withstanding the weight of the cables laid over it. Rigid ISA / ISMC / ISMB / flats support should be provided at every 3m length and also at diversions, crossings, bends and multi layered locations. Cost for additional supports shall be paid separately 100 mm wide & 50 mm depth.
- 102) Providing and applying two coats of coal tar or bitumen conforming to IS:3117– latest version on the top and sides of RCC box/slabs @ 1.70 kg/sqm after cleaning the surface with all labour and materials complete job as directed by the Engineer.
- 103) Supplying and laying at site Factory made perforated hard HDPE subsoil drainage pipes pre-wrapped with 150 gsm Geotextile for subsoil drainage system including all necessary coupling/ fittings for joints & back filling with aggregates. The pipe shall be manufactured from High Density Polyethylene (HDPE). It shall be extruded into an open lattice wall structure, with > 60% of the circumference consisting of open area and a 30% solid area along the invert. The product should satisfy the following parameters as below  
1. Ring Stiffness as per ISO 9969: 2016 should be > 0.8 kN/m<sup>2</sup>  
2. Resistance to Acid with 3% HCl for 24 hrs without mass loss, change in colour, softening, cracking or spalling.  
3. Resistance to Alkali with 3% KOH for 24 hrs without without mass loss, change in colour, softening, cracking or spalling.  
(Excavated material to be utilised in roadway at site)160mm dia HDPE pipe.
- 104) Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & Technical Specification.
- 105) Manufacture and supply of Precast Hectometer/TP Repeater posts of size 0.90Mx0.30 mx0.30Mx0.30M Triangular size in RCC 1:2:4 mix, engraving letters, leading to work spot, and fixing in position with CC 1:3:6 concrete, duly making pits of size as required, painting the post with two coats, letters on the both sides of posts with enamel paint of approved quality as per IRPWM/Railways drawings complete with contractor's materials, cement, steel, labour, tools, plant, with all lead and lifts etc., complete as per specifications and as directed by the Engineer-in-charge.
- 106) Manufacture and supply of Precast Kilometer Posts of size 1.15 x 0.50 x 0.075 m in RCC 1:2:4 mix, engraving letters and leading to work spot, fixing in position with CC 1:3:6 concrete duly making pits of size as required, painting the post, writing the letters on both sides of the post with 2 coats of enamel paint of approved quality to the Railways drawings/IRPWM with contractor's materials, cement, steel, labour, tools, plant, with all lead and lifts etc., complete as per specifications and as directed by the Engineer-in-charge.
- 107) Manufacture and supply of Precast gradient Posts of size 1.65 x 0.60 x 0.075 m in RCC 1:2:4 mix, engraving letters and leading to work spot, fixing in position with CC 1:3:6 concrete duly making pits of size as required, painting the post, writing the letters on both sides of posts in 2 coats with enamel paint of approved quality to the Railways drawings/IRPWM with contractor's materials, cement, steel, labour, tools, plant, with all lead and lifts etc., complete as per specifications and as directed by the Engineer-in-charge

## **V) GENERAL INFORMATION, INSTRUCTIONS AND MISCELLANEOUS ISSUES**

### **1. ITEMS PAYABLE UNDER LUMP SUM COMPONENT OF THE WORK IN SCHEDULE - C**

The items against the scope of the work include (but not limited to) the following:

- a) Shifting of Utilities required, if any
- b) Any other items not covered in the scope of the work of Price **Schedule 'A' & Schedule 'B'**,

### **2. DESIGN PHASES OF PERMANENT WORK**

The contractor shall execute the work in two phases:

- a) Design Phase
- b) Construction Phase

The Design Phase shall commence on the date of issue of Letter of Acceptance. There is no relation of Design Phase with the Notice to Proceed. This phase shall include the preparation and submission of:

- c) The Preliminary Design
- d) The Definitive Design; and
- e) The GFC Drawings.

The design for all temporary structures shall also be submitted during the stage of the Preliminary Design / Definitive Design, as directed by the Engineer.

The Design Phase will be complete upon the issue of a Notice in respect of the comprehensive and complete GFC Drawings submission for the whole of the Permanent Works.

The Design and Good for Construction (GFC) drawings shall be submitted by the Contractor. After due scrutiny by the Engineer and the Employer, the Engineer shall, with the approval of the Employer, issue the approved GFC drawings to the Contractor for execution of the works in accordance with the terms and conditions of the Contract Agreement.

**The drawings approved by KRIDE are enclosed with the tender documents and may be used directly for the execution of the works. For drawings that have not been approved by KRIDE, the bidder shall prepare and submit the required designs and drawings (such as General Arrangement Drawings and structural designs) for approval by the Employer through the General Consultant (GC) prior to execution.**

### 3. REFERENCE DOCUMENTS

The following Documents shall be referred in conjunction with each other (not necessarily in the same order) by the contractor for construction work as these are mutually complementary to each other:

- a) Good for Construction Drawings will be issued by the Engineer with the approval of Employer
- b) Employer's Requirements
- c) Instructions
- d) Technical Specifications and explanatory notes
- e) Contract Conditions
- f) Particular Conditions of Contract
- g) Bill of Quantities
- h) Indian and International Standards referenced in the bid document
- i) The schedules and any other documents forming part of the Contract
- j) Any other related section in the bid document

The contractor shall always promptly seek advice from the Employer/Engineer in the event of conflicts among above cited documents, before taking any action in respect of any item of work, where such a conflict has a potential to affect any aspect of the work. In case of conflict, the Employer's decision will be final and binding.

### 4. GENERAL PROJECT INFORMATION

The project site is located in and around Bengaluru City. The tendered work is BSTP project for Package 2 of Corridor-2 / BSTP between Benniganahalli to Hebbal. At-grade section is proposed parallel to the existing Railway track alignment on the left / right side and over existing electrified railway line as per tentative alignment drawing.

### 5. AVAILABILITY OF LAND

A major portion of the required land for the execution of works is available along the alignment. The remaining land will be acquired and handed over to the contractor progressively. The contractor shall take additional land on a lease / rent basis temporarily for installation of his facilities like batching plant / Casting Yard / Site Work Shops / Project offices / Site offices etc. The tenderers are advised to conduct a detailed study and cater for all such expenditure in the bid.

## **6. APPROACHES TO THE PROJECT SITE**

Land acquired for the project caters for construction and operation of the proposed line. The contractor shall plan for approach roads to various sites of work conducting detailed survey and should include the cost of inputs for any such approach roads in his bid for the work.

However, in case any existing road outside railway land needs to be utilized for transportation of materials to the site of work and in the process the road gets damaged or needs to be strengthened and the authority owning the said road submits demand to Bi-RIDE to carry out some specific works in order to strengthen / repair the road, Engineer / Employer is authorized to get such works executed through this contract

## **7. INTER COMMUNICATION FACILITIES**

Telephone and fax services are available at Bengaluru. Should the contractor wish to use Radio communication on the site, the Employer will recommend to the appropriate authority the application for allocation of radio frequencies to the contractor.

## **8. SITE INFORMATION**

The project site is located in and around Bengaluru City. Bengaluru is well connected to other parts of the country by Road, Rail and Air. It has an International Airport. The location of the work and the general particulars are shown in the drawings enclosed with the bid documents.

## **9. GENERAL CLIMATIC CONDITIONS**

Bengaluru is located in meridians of 12° N latitude and 77°3' E Longitude, spread over an area of 531 sqm km. located at an altitude of 900m, Bengaluru boasts of delightful weather around the year registering a maximum temperature of around 34° centigrade in summer and a minimum temperature of around 14° centigrade in winter. However, there have been instances of break of these maximum and minimum. Bengaluru receives both the Southwest and Northeast Monsoons, getting an annual average rainfall of 760 mm, generally during the months of May to September I October. Bengaluru falls in Seismic Zone II.

## **10. OBTAINING CLEARANCES / CERTIFICATES FROM AUTHORITIES**

Contractor shall arrange well in advance, stage-wise (if required), submission of all the required documents and drawings for approval of other concerned authorities and arrange for their inspection and obtain approval / completion certificates with respect to the work, as required. All clearances from the Statutory Authorities is the responsibility of the contractor. The contractor shall obtain and deliver to the Employer and the Engineer, on completion of the works, the final Inspection Report from the Authorities.

## **11. RESTRICTIONS IN WORKING**

- i. The various items of construction work shall have to be carried out in / along narrow roads / streets of Bengaluru city besides / across / parallel to the existing railway lines where there are buildings adjacent to the road / track and where there may be heavy railway traffic.
- ii. There are restrictions for movement of trucks and heavy vehicles (ex: trailers) carrying construction materials, cleaning during the day hours on some roads.
- iii. There are some one-way roads where traffic can't move in both directions.
- iv. Generally, at least two lanes of traffic in both directions shall be kept while the works are on, including foundation works.
- v. The construction of structures shall be planned in such a manner that they do not obstruct or

interfere with the existing roads, railways tracks and other Utilities. Since the entire alignment is parallel to the existing IR track / road, continuous movement of trains / heavy vehicles is expected. Wherever the works are near stations / approaches to the stations / at the middle / besides IR Track / road / across the railway tracks / roads, erection of pre-cast members shall be planned in such a way that the erection is done from one end with Back Feeding.

- vi. Unless the competent authorities permit to execute such works during daytime using cranes and restricting the movement of the vehicles / trains, they shall be ordinarily planned in such a way that they do not cause any hindrance to the movement of vehicles / trains and the same shall be planned to be carried out during night. While working in the night hours, the noise pollution shall be restricted to an acceptable level. Special care shall be taken to restrict the noise pollution further, to the minimum levels, in the vicinity of hospitals, educational institutions etc. The bidder should take all these facts into account while quoting rates and devise his methodology of working accordingly.
- vii. Where work is required to be carried out at locations adjacent to such Existing IR tracks, roads, Utilities, structures, monuments, religious structures, etc., suitable safety and protection arrangements shall be ensured. Nothing extra will be payable on these accounts. It shall also be ensured that no damage is caused to any such element and Engineer / Employer shall be indemnified against such damage at no extra cost.

## 12. POWER & TRAFFIC BLOCK

- (i) Track occupation may be granted at any time during day or night to suit convenience of traffic operations and will ordinarily be granted over a distance covered by one or two consecutive block sections. Work trains will normally be allowed to take advantage of block shadows. Normally the total duration of block on any section will be maximum of 1.5 to 2.5 hours at a stretch in a day or 2.5 to 5hrs in night depending upon nature of work. Block provided may be utilized for one or more work trains or track Lorries or ladder trolleys to suit convenience of work.
- (ii) Blocks will not ordinarily be given for laying the feeders except where crossing of track is involved, which shall be laid manually in general.
- (iii) Any traffic / power blocks, temporary speed restrictions and caution orders required in connection with execution of works by the contractor, shall be got sanctioned from the Railway authorities well in advance by the contractor through the Engineer. The Railways may sanction the same for specific sites within the overall recovery time available in the Railway timetable. The contractor shall schedule his Programme according to the convenience of the Railways. No claim from the contractor for any delay / inconvenience / loss on this account shall be entertained by the Employer / Engineer.
- (iv) In order to minimize blocking of the track for work / material trains, the contractor shall consider the working conditions on the section and assess the use of alternative method of construction on a part or whole of the work. He should submit a clear proposal along with financial implication if any to the purchaser for such special method of saving of blocks that could be obtained along with reduction / redundancy of the facilities being provided by the Railway / Bi-RIDE.
- (v) The protection required for block working i.e., flagmen, flags etc. shall be provided by the contractor. Competency for the above shall, however, be given by the Railway authority. Protection of track by banner flags etc. shall be done in accordance with General Rules of Indian Railway and Subsidiary Rules of the concerned zonal Railway where work is being carried out. The contractor shall provide a Safety helmet, Safety belt and Safety Shoes to their staff while working at site.
- (vi) In case of theft / breakdown, the contractor shall restore the traffic in the minimum possible time. Failure to do so shall attract suitable penalties.

## 13. PROVISIONAL ACCEPTANCE

- i) Immediately after completion of works / such part of works, the contractor shall certify and advise

the Engineer in writing that the works are (i) complete (ii) ready for satisfactory commercial service and (iii) ready to be handed over. He will also place at the disposal of the Engineer the required staff for checking it and putting it into operation.

- ii) The test or tests as stipulated in approved Technical Specifications shall be carried out jointly by the Engineer and the contractor within a month after the receipt of the contractor's notification as stated in sub-Para above.
- iii) The provisions contained in the relevant CC/PCC clause shall be followed for taking over the installations.

#### Use of Rejected / Sub Standard Items / Equipment.

In the event of such rejection as aforesaid, the Engineer shall, without prejudice to his other rights and remedies and in particular without prejudice to his rights under the clause just preceding, be entitled to the use of the rejected / substandard equipment / item for a time reasonably sufficient to enable him to obtain other replacement. During such period, if the rejected / substandard equipment / item is used commercially the contractor shall not be entitled to the payment on energization until such rejected equipment is rectified and / or replaced, but the Engineer shall not be entitled to claim any damages arising out of rejected / substandard equipment / item in respect of such period.

### 14. GUARANTEE

- (i) The contractor shall guarantee satisfactory working of the installations erected by him, for a period of 24 (Twenty -Four) months from the date of issue of completion certificate or from the date of Provisional Acceptance by the Engineer, whichever is earlier. The guarantee for spares (if any) should be coincident with the guarantee for erected equipment. The provisions contained in the relevant clause shall be followed for rectification of defects.
- (ii) During the defect liability period the contractor shall keep available an experienced engineer and necessary equipment to attend to any defective installations / work resulting from defective erection and / or defects in the equipment supplied by the contractor. The contractor shall bear the cost of all modifications, additions or substitutions that may be considered necessary due to faulty materials, design or workmanship for the satisfactory working of the equipment. The final decision shall rest with the Engineer / Employer.
- (iii) During the defect liability period the contractor shall be liable for the replacement at site of any parts which may be found defective in the equipment whether such equipment be of his own manufacture or those of his sub-contractor whether arising from faulty design, materials, workmanship or negligence in any manner on the part of the contractor provided always that such defective parts as are not repairable at site are promptly returned to the contractor if so required by him at his (Contractor's) own expenses. In case of type defects in Contractor's equipment and components detected during guarantee period, contractor shall replace all such items irrespective of the fact whether all such items have failed or not. The contractor shall bear the cost of repairs carried out on his behalf by the Engineer at site. In such a case, the contractor shall be informed about the works proposed to be carried out by the Engineer / Employer.
- (iv) If it becomes necessary for the contractor to replace or renew any defective portion of the equipment under the Para aforesaid then the provision of the said Para shall also apply to the portions of the equipment so replaced or renewed until the expiration of six months from the date of such replacement or renewal or until the end of the above-mentioned period whichever is later. Such an extension shall not apply in case of defects of a minor nature, the decision of the Engineer or his nominee being final in the matter. If any defect be not remedied within a reasonable time during the aforesaid period, the Engineer may proceed to do work at the contractor's risk and expense, but without prejudice to any other rights and remedies which the Engineer may have against the contractor in respect of such defects or faults.
- (v) The repaired or renewed parts shall be delivered and erected on site free of charge to the satisfaction of the Engineer / Employer.

**15. ACCOUNTABILITY AND DISPOSAL OF RELEASED MATERIALS**

- (i) The contractor shall liaison with the Engineer to finalize the procedure for taking over the whole or part of the section and for disposal of the released materials.
- (ii) All released materials shall be handed over to the authorized representative of the Engineer / Employer at the specified depot / location.
- (iii) The material released on account of modifications / alterations shall be accounted by the contractor in the presence of the Engineer and the Employer's Representative, except for the material permitted by the Engineer to be re-used.
- (iv) If any shortfall of released material is noticed at the time of completion of the work, the contractor shall be liable to pay for the shortfall as per the prevailing rates. Else, the same will be recovered from the final bill of the contractor as per the extant policy of Bi-RIDE.

**16. CODES AND SPECIFICATIONS**

The work shall be carried out as per Specifications. Wherever reference is made in the Contract to specific standards and codes to be met by the goods and materials to be furnished and work performed or tested the provisions of the latest current edition or revision of the relevant standards and codes in effect shall apply, unless otherwise expressly stated in the Contract. Where such standards and codes are national or relate to a particular country or region, other authoritative standards which ensure an equal or higher quality than the standards and codes specified will be accepted subject to the Engineer's prior review and written approval. Differences between the standards specified and the proposed alternative standards must be fully described in writing by the contractor and submitted to the Engineer at least 28 days prior to the date when the contractor desires the Engineer's approval. In the event the Engineer determines that such proposed deviations do not ensure equal or higher quality, the contractor shall comply with the standards specified in the documents.

- (a) The Standard Specifications of Railways / IS / IRC and the list of codes and manuals given in the annexure thereof shall be prime governing (IRPWM, IR Bride Manual, the relevant IR specifications, Specifications of works of concerned zonal Railway, SOD, DBR, IRS codal provisions / IRC codal provisions / IS codal provisions / MORTH / CPWD.
- (b) Where there is conflict between provisions in IRS & IS specifications, provisions in IRS specifications shall prevail.
- (c) Where there is no provision of specifications in IRS, provisions in IS specifications should be adopted. Where there are no provisions in IRS and IS Specifications, in IRC Specifications should be followed.
- (d) For items not covered in IRS / IS / IRC specifications, BS-5400 Part 1 to 10 / FIP / AASHTO / ASTM may also be considered.
- (e) The decision of Employer is final and binding in the interpretation of the clause of the codes of practice and specifications of this tender and no claim whatsoever shall be entertained on this account from the contractor.

**17. SURVEY AND FIXING WORKING BENCH MARKS AND ALIGNMENT MARKERS**

The work of conducting survey and fixing bench marks and alignment markers before the start of any work on this tender is included in the works covered by the present Tender.

**17.1 Bench Marks**

- 1. All along the length of the corridor, the contractor shall establish bench marks with reference to the permanent bench marks available with the Survey of India. The details of these bench marks along with their reduced levels shall be marked on the alignment drawings indicating the plan and 'L' section which forms a part of the tender. The contractor along with the Engineer shall verify the details in the first instance, soon after getting access to the site. If any mistakes are detected in these details of these bench marks, the same shall be indicated to the Engineer. The mistakes

detected shall be corrected in consultation with the Engineer. These corrections should be got approved by the Engineer before starting of any other work.

2. The contractor shall then, in the presence of the Engineer, establish working bench marks at short intervals, adequately connecting them to the reference bench marks set up by the Employer in the Project length. The working bench mark levels should be got approved from the Engineer. An up-to-date record of all bench marks including approved corrections, if any, shall be maintained by the contractor and also by the Engineer.
3. All levels taken for making out the longitudinal section and cross section should be related only to these working bench marks.

### **17.2 Alignment**

1. The contractor shall fix alignment reference points on pillars, cast and erected as per the specifications, at regular intervals all along the alignment. The contractor along with the Engineer shall verify the details of these alignment pillars. If any mistakes are detected in these details, the same should be indicated to the Engineer before starting any work. These detected mistakes should be corrected by the contractor in consultation with the Engineer. These corrections should be got approved from the Engineer.
2. The contractor shall then, in the presence of the Engineer, establish working alignment reference markers at shorter intervals, adequately connecting them to the reference pillars set up by the Employer in the Project length. The location of these pillars and subsidiary alignment markers, if any, should be got approved from the Engineer. An up-to-date record of all alignment pillars, and corrections, if any done, shall be maintained by the contractor and also the Engineer.
3. The alignment should be related only to these working bench marks.
4. The Engineer, when necessary, will provide the contractor with the data necessary for setting out of the centerline. All dimensions and levels shown on the drawing or mentioned in the documents forming part of or issued under the contract shall be verified by the contractor on the site; he shall immediately inform the Engineer of any apparent errors or discrepancies noticed in such dimensions or levels. The noticed mistakes shall be corrected in consultation with the Engineer. These corrections shall have the approval of the Engineer.
5. The contractor will be entirely responsible for accurate setting out of the works and safeguarding all survey monuments, bench marks, alignment references etc. The work of setting out shall be deemed to be a part of the general works preparatory to the execution of work and no separate payment shall be made for the same.
6. For the entire duration of the contract, the work of setting out shall be deemed to be a part of the general works preparatory to the execution of the work and no separate payment shall be made for the same.

### **17.3 Interfacing and Integrations of Works**

1. The contractor shall take full responsibility in terms of organizing, managing, coordinating and administrating the interfacing of all components of work including all issues related to and arising out of such tasks. The contractor shall interface with all concerned authorities and other contractors as required to complete the work satisfactorily within the stipulated period.
2. Under consideration and application of the above clause, the contractor shall have the obligation to liaise with the other contractors and Authorities to obtain all necessary technical information, all necessary information concerning organization of works, coordinating the works etc. which are necessary to assess, mitigate, take care of contractual obligations, risks, liabilities and whatsoever arising out of interfacing, engineering issues, organization of the works etc. The Employer / Engineer shall not be held liable in any way, throughout the preparation of the offer and / or execution of the works and / or maintenance period and / or defects liability period for any omissions, misunderstanding, negligence etc. arising out of interfacing, coordinating, organizing etc. of the works. The Employer will not entertain any claim arising out of misunderstanding,

miscommunication, omission, withholding of necessary / required information or whatsoever between the concerned contractors / Authorities concerning interfacing, organizing etc. of works. In case of any claim arising from any of the contractors, as aforesaid, referring to interfacing and / or interfacing related issues, the Employer will hold the concerned contractors liable for not taking care of their contractual obligation concerning interfacing, organizing, co- ordination etc. of the related works.

3. Needless to say, that commissioning of this project requires close coordination among various agencies executing the works in this section, the Engineer, the Employer and the Railway authorities, wherever applicable. The contractor shall therefore plan all his works requiring interfacing with other agencies, meticulously, in consultation and coordination with all concerned parties, in advance, for expeditious execution, without causing any delay either to his works or those of others.
4. If, in the opinion of Employer / Engineer, any delay in execution of any part of the Project requiring interfacing is attributable to the failures of the contractor to take adequate steps for smooth execution of such works, then the Employer will have the right to take necessary steps to organize and streamline such works, including excluding the requisite portion of work from the scope of the contractor and getting the same executed by other agencies, at the risk and cost of the contractor.

#### **17.4 SURVEY EQUIPMENT**

1. The contractor shall provide the survey equipment and other accessories as per the instructions of the Engineer as and when required. He should also provide all necessary help as required by the Employer / Engineer for inspecting and checking the works, whenever required.
2. All power requirements for execution of works shall be arranged by the contractor from his own resources. Subject to availability of power, the Employer / Engineer may recommend to the Railway Authorities for providing power connection. No guarantee whatsoever is given by the Employer in this regard. The contractor shall bear the cost of installation and payment of necessary charges for providing such power connections as per the Terms and Conditions of the Railways. However, in the event of non-availability of Power from Railways, the contractor shall make necessary arrangements to tie up with the local Electricity Authorities etc. for supply of Power, till all the works are over.

#### **18. DAMAGE TO PROPERTY**

The contractor shall organize all his activities so as not to cause any damage to the property of Railway or that of other agencies or any third party. In spite of taking all precautions, in the unfortunate event of any damage to any property, there could be claims by the affected parties. The contractor shall not only indemnify the Employer / Engineer against the claims made by the affected parties but also settle the matters with the affected parties as per the law. If the nature of damage is one of that affecting the train movements or causing a safety hazard to the public, then the situation will be treated as an emergency and the Employer reserves the right to take all necessary steps as deemed necessary to restore train operations or to remove the hazardous situation or to mitigate the damage, at the risk and cost of the contractor.

#### **19. STRUCTURAL ELEMENTS, SHAPE AND FORM**

The bidder shall note different structural elements in shape, form and structural configuration in plain. The structural elements may be skew, tapered, curved etc. The bidder shall include these factors while quoting his rates. All the above shall be covered in the quoted rates and nothing extra shall be payable towards this.

##### **19.1 Stability of the elements**

During construction, the stability of each element must be ensured until the connections through which the stability is achieved are fully operative. This might require temporary supporting, bracing etc. This



is the contractor's responsibility, and no extra payment will be made.

### **19.2 Stability of the Structure**

The overall stability of the structure must be ensured during each phase of construction. This might require special provisions. This is also the contractor's responsibility, and no extra payment will be made.

### **19.3 Temporary Works**

Traffic barricade with reflective tapes and other necessary traffic signages should be provided wherever required so that safety is ensured during day and night continuously. Temporary traffic diversion for smooth flow of traffic during construction including necessary traffic signs, repairs to the diverted route I service lanes, if required, restoration of diverted route to original condition etc. shall be done by contractor at his cost...

The contractor shall also provide any temporary support for the utilities (charted or uncharted), wherever required, at no extra cost to Employer.

### **19.4 Design for Temporary Works**

The Design should cover all the items pertaining to all temporary works, traffic diversion scheme, form work, casting and stacking yard, staging, launching scheme for girders / beams and / or transportation scheme for various structural elements and materials to be transported to and from site during construction period.

Contractor shall formulate a practical and viable scheme for design / fabrication of shuttering, scaffolding / staging, casting, curing, testing and launching / erection of girders / beams / and all other structures. The contractor should, along with the bid, specify the scheme that he proposes to adopt for carrying out all the works including fabrication, transportation, stacking and erection of steel structure and casting, curing, stressing, testing and launching I erection of girders I beams.

Contractor shall formulate the erection scheme, design the staging, including all necessary temporary structures, prepare fabrication drawings in accordance with relevant provision of applicable IRC standards and submit the same to the Engineer for approval with third party certificates. These works will be executed only after the approval has been obtained from the Engineer.

## **20. DRAWINGS**

1. The Drawings furnished with the Bid documents are indicative and approximate and may require changes at the time of actual execution of works based on actual site conditions. Drawings furnished with the Bid Documents show the level of work based on available soil investigation data. These may change at the time of actual execution of works based on actual site conditions without additional cost.
2. Tender drawings represent Employer's proposal based on preliminary design and conceptual plans, which are indicative.

### **20.1 - GFC Drawings:**

The Design and drawings are the responsibility of contractor. GFC drawing requirement shall be planned by the contractor based on his three-month rolling Programme and the GFC drawings shall be submitted accordingly.

Errors, Omissions and Discrepancies in Specifications and Drawings:

- a. It shall be the responsibility of the contractor to promptly bring to the notice of Engineer any error, omission fault, defects or discrepancy in the contract documents, specifications and drawings for the work which are discovered while reviewing the contract documents or in the process of execution of the works and obtain his orders thereon.
- b. Only stated dimensions shall be taken and not those obtained from scaling the drawings.

- c. . In case of errors, omissions, faults, defects and / or disagreement on the drawings or between the drawings and specifications the following principles shall be followed
  - i. As between the written description or written dimensions on the drawing and the corresponding one in the specifications, the former shall apply.
  - ii. As between the written description of the item in the Bill of Quantities and the detailed description in the specification of the same item, the former shall prevail.
  - iii. The drawings on a large scale shall take precedence over those on a smaller scale; and
  - iv. Drawings approved as construction drawings from time to time shall supersede corresponding drawings previously approved. The decision of Engineer / The employer will be final on this matter.

## **20.2 Meaning and intent of specifications and Drawings.**

If any ambiguity arises as to the meaning and intent of any portion of the specifications and drawing or as to execution or quality of any work or material, or as to the measurement of the works, the decision of the Engineer thereon shall be final subject to the appeal (within 7 days of such decision being intimated to the contractor) to Employer, who shall have the power to correct any errors, omissions, or discrepancies in the specifications, drawings, classifications of works or materials and whose decision in the matter in dispute or doubt shall be final and conclusive.

## **20.3 Responsibility for Specifications, Design and Drawings Specifications**

RDSO / MORTH / CPWD, KPWD specification / other Specifications / Codes viz. IS, IRS, IRC DSR etc. shall be procured by the contractor from the market. One set of these specifications shall always be kept at contractor's site office for reference. Standards guaranteeing a level of quality or performance equivalent or superior to those indicated will also be accepted. Reference to trademarks or other specific designations that are necessary to explain the nature of the products required does not necessarily mean that the same specific product / brand has to be used, but it means that any other product of equal or superior quality or performance is also acceptable, subject to prior approval of the Employer / Engineer to be obtained in writing for adopting the new standards which are not provided in the contract.

## **20.4 Drawings for Permanent Works**

- i. Preliminary Drawings as listed showing general dimensions & details elaborating the scope of work (not based on detailed design) are supplied along with the bid documents. These drawings are broadly indicative of the work to be carried out. These drawings are not "Construction Drawings" and details indicated therein are for general guidance only and shall be modified by the contractor, to incorporate additional details as per design, and as described in the Specifications.
- ii. The Permanent Work shall be carried out in accordance with the "Good for Construction" (GFC) drawings as would be issued to the contractor by the Engineer duly signed and stamped. The contractor shall not take cognizance of any drawings, designs, specifications, etc. not bearing the Engineer's signature and stamp. Similarly, the contractor shall not take cognizance of instructions given by any other Authority except the instructions given by the tender calling authority / competent authority or the nominated official of the Employer / the nominated official of Engineer, in writing. Construction drawings shall be supplied progressively by the contractor during execution of work, well in time (giving sufficient margin of time, as decided by the Employer / Engineer, for their scrutiny and issue), for each activity.
- iii. GFC drawings / Advance copies required for the next three months' work shall ordinarily be submitted by the contractor to Employer / Engineer for his planning, procuring etc.
- iv. The "Good for Construction" drawings shall be prepared by the contractor after the award of the work.
- v. No deviation shall be made from GFC drawings by the contractor without written permission of

Engineer. For such portion of deviations which are approved by Engineer, as built drawings shall be submitted by contractor for approval as soon as the work is completed at site.

#### **20.5. Design, Drawings and Specifications for Temporary / Ancillary works.**

- i. Contractor's proposal for erection of all Ancillary and Temporary works shall be in conformity with the proposals submitted along with the bid and / or as approved by Employer / Engineer.
- ii. The contractor would design all the Ancillary and Temporary works including temporary supports, false work, formwork, staging scheme etc. and will submit the same and related working drawings to the Engineer for approval, after getting check by an independent third-party designer. Bar Cutting and bending schedule for the reinforcement including bend corrections, shop drawings for fabrication work etc. shall also be prepared by the contractor and submitted for Engineer's approval.
- iii. Shop drawings
  - (a) Based on "Good for Construction" drawings issued by the contractor, the contractor shall prepare shop / fabrication drawings to scale as specified, indicating the required details. The shop drawings shall be prepared before execution of work, after taking actual site dimensions and all existing and proposed services / structures etc.
  - (b) Shop / Fabrication drawings submitted by the contractor shall be in sufficient detail to indicate the type, size, arrangement, breakdown for packing and shipment, the external connections, fixing arrangements required, the dimensions required for installation and interconnections with other equipment and materials, clearances and spaces required between various portions and any other information specifically called for.
  - (c) All reference points shall be in relation to the levels and locations, given in the Architectural and Services drawings duly cross-checked on site and confirmed. All locations and levels should be indicated with respect to grid and reduced levels with respect to the Bench Mark adopted for the Project and indicated in the drawings issued by the Engineer.
  - (d) The contractor shall verify the dimensions of all the necessary structural, architectural, Mechanical, Electrical & Plumbing (MEP) Services and other elements, relevant to the system being done, before proceeding with the preparation of the shop drawings and proceeding with the physical work at site and make suitable adjustments to accommodate within the spaces available.
- iv. Approval of Engineer of any such proposal / drawings or delay in approval shall not relieve the contractor of his responsibility of sufficiency of such works.

#### **20.6 Drawing Management**

1. The contractor shall submit all such drawings for Temporary / Ancillary works and shop drawings to the Engineer well in advance before he desires to commence the works and get the same approved from the Engineer. These drawings should be submitted only after they have been duly detailed, checked and verified within the contractor's organization ensuring that the details and data shown / furnished on the drawings are correct and that the requirements of other disciplines have been taken care of. The names and complete signatures of the contractor's personnel responsible for the drawings shall be contained on each drawing. Any drawing which does not contain the above names and signatures shall be summarily returned to the contractor and treated as not having been submitted.
2. The drawings submitted for approval shall be in any one of the standard sizes - AO, A1, A2, A3 or A4, in accordance with Indian standards and as specified.
3. All drawings shall show the following particulars in the lower right-hand corner in addition to the contractor's name.
  - i. Project Title
  - ii. Name of the Employer
  - iii. Name of Consultant

- iv. Contract No.
  - v. Title of Drawing
  - vi. Scale
  - vii. Date of Drawing
  - viii. Contractor's Drawing Number
  - ix. Space for the Engineer's drawing number
  - x. Name of the Engineer
  - xi. Name of Review Consultant
  - xii. This drawing is based on Drawing No.(s.)
  - xiii. Further detail is given on Drawing No.(s.)
4. Each drawing shall carry a revision number, date of revision and brief details of revisions carried out. Whenever any revision is carried out, the revision number must be updated. The revisions carried out on the drawing shall be clearly marked by clouding and each cloud revision shall be numbered by marking the revision number in triangle.
5. All dimensions on drawings shall be in metric units, unless otherwise specified. However, all levels shall be in metres.
6. A template with the above information shall be got approved from Engineer / Employer before start of the work.
7. All shop drawings shall be prepared on CAD using AUTO-CAD Version 2020 or higher.

**20.7 Shop drawings shall be prepared for the following works:**

- i. Reinforcing bar bending schedules
- ii. Precast yard development and its assets
- iii. All form works, Shuttering and Scaffoldings
- iv. Shop / Fabrication drawings for structural steel for PEB
- v. Metal work (ferrous and non-ferrous) for inserts, structural work in built up sections etc.
- vi. Seismic joints
- vii. Expansion joints
- viii. Construction joints
- ix. Waterproofing

**20.8 Drawing Management at Site**

- (i) The contractors shall ensure that all drawings (to be laminated at contractors' cost) meant for further engineering, fabrication, erection and field work are issued to their personnel in a controlled manner. A proper record shall be maintained to show to whom the drawing is issued and to ensure that the latest revision of the drawing is being followed for further work.
- (ii) All superseded drawings shall be promptly withdrawn from the personnel to whom they are issued and stamped "SUPERSEDED" in RED. The contractor shall maintain a register of drawings, with their revision I issue number, as received from the Engineer and a record of their distribution to the designated personnel within their organization. A certificate to that effect along with list of drawings withdrawn during the month shall be incorporated in the monthly progress report.
- (iii) In case of revision of Approved Drawings for Temporary I Ancillary and Shop Drawings, if any, at any time before the completion of the work, the contractor shall make such revisions and proceed in the same manner and observe procedure for obtaining approval of the Engineer as for the approval of the original drawings.
- (iv) The contractor shall maintain at Site a set of the drawings issued by the Engineer on which changes shall be progressively marked and signed by the Engineer so that "As-Built" drawings can be made correctly and expeditiously at the end of the work.

**20.9 Documents by Contractor**

- i. The contractor shall submit to the Engineer, for approval, Quality Assurance plans, design calculations, material specifications for each item and system, samples, as may be called for in the Specifications or as the Engineer may reasonably require. Wherever necessary, the

contractor shall provide as built dimensions to facilitate proper Good for Construction drawings being prepared for various construction detailing.

- ii. Number of Copies of Drawings for Temporary / Ancillary works / Shop drawings and Documents
- iii. All Shop drawings I drawings for Temporary and Ancillary works, Documents, Schedules etc. and revisions thereof shall be submitted by the contractor to the Engineer in 6 copies. Copies required in excess of these shall also be borne by the contractor at his own cost.

#### **20.10 Completion Drawings**

On completion of the work in all respects the contractor shall submit the following

- i. Six sets of "As Built Drawings" in the standard sizes of A0, A1 each containing complete set of drawings for every component of work on approved scale indicating the work "As Built". Each set shall also contain technical literature.
- ii. These drawings shall be prepared on CAD using Auto-Cad version (latest, as directed by Engineer) and shall be recorded on writable memory devices and one set of these devices shall also be submitted.
- iii. Four sets of catalogues of all manufactured materials with the name and addresses of the manufacturers for all equipment provided by the contractor.
- iv. The Certificate of Completion of Works as per the provisions in the General Conditions of Contract will not be issued by the Employer I Engineer in the event of Contractor's failure to furnish aforesaid "As Built" drawings for the entire works.

#### **20.11 Plans and Drawings for Layout of Plant and Equipment**

The contractor shall submit the following information, in triplicate, to the Engineer, for approval, within the time stipulated against each item given below:

- i. A general layout plan for construction plant and equipment required for execution of work, within thirty days from the date of issue of "Letter of Acceptance".
- ii. Drawings or prints showing the locations of major facilities which he proposes to put up at site, at least fourteen days prior to the commencement of the respective work; and
- iii. Any other details and drawings as required under the contract, within the time as specified in the contract.

The cost of all the above activities shall be deemed to be included in the quoted rates of various items of the Price schedule and nothing extra shall be paid for on this account.

### **21. TRAFFIC MANAGEMENT**

- i. The contractor shall make the detailed traffic diversion plans in consultation with Bengaluru Traffic Police. The work is to be executed with proper liaison with Bengaluru Traffic Police. Necessary assistance in the form of issuing letters to the authorities concerned will be given by Bi-RIDE. The scheme should be such that a minimum of two lanes of traffic on each direction of the road should be available for the smooth flow of traffic. The contractor should inspect the site and observe the traffic flow and pattern before making the diversion plans.
- ii. The permanent traffic diversions will be carried out in consultation with traffic police. Contractors shall provide traffic diversion proposals, traffic marshals, cones, traffic diversion boards etc., as desired by Traffic Police.
- iii. Traffic barricade shall be with reflective tapes, traffic signages, traffic sign board, signals, road delineator reflective lights, traffic cones etc. Deployment of adequate manpower shall be for all 24 hrs in 8hrs shifts. Day and night management of the above, including all other necessary provisions, wherever required, shall be taken care of so that safety is ensured during day and night continuously. Temporary traffic diversion for smooth flow of traffic during construction including necessary traffic signs, repairs to the diverted routes I service lanes.

- iv. It includes but not limited to Diversion to other adjoining parallel roads or other suitable roads including strengthening of the same and all provision and maintaining the flow of traffic towards the diverted route with minimal inconvenience to the flow of affected traffic and close liaison with Traffic Department of Bengaluru.
- v. The contractor shall take necessary and adequate measures to ensure uninterrupted traffic flow within the work area during the currency of the work. It shall be the responsibility of the contractor to provide suitable and acceptable diversions for the passage of the traffic. The contractor shall ensure that at no time, his construction equipment interrupts the movement of the traffic on the road and IR Track.
- vi. The contractor shall prepare a comprehensive Traffic Management Plan. The contractor shall also draw a phased program for traffic arrangements / diversions and get it approved from the Employer / Engineer and Traffic Police well in advance with respect to every stage of construction.
- vii. If traffic diversions require construction of temporary roads and / or improvement of the existing roads, the design / drawings for the same including diversion of utilities etc. (if required) shall be prepared by the contractor using the specifications not inferior to that of the existing roads / utilities and get it approved from the Engineer / Employer and Traffic Police. Payment for the same shall be made under relevant item of, **Schedule – C, Price schedule**.
- viii. Before taking up the work in a particular stretch, all the traffic diversion plans applicable to that particular area shall be implemented as per the approved plans / drawings and trial runs carried out to the entire satisfaction of Engineer / Traffic Police. If, during trial runs, some modifications are suggested, the same shall be also being carried out before start of work.
- ix. The contractor shall take all necessary measures for safety of traffic during construction and provide, erect and maintain such barricades (as approved by Engineer) having marking with reflective paint, signs / sign boards, pavement markings, flags, lights, traffic marshals and flagmen as may be required and / or directed by the Engineer for guiding, information and protection of the traffic approaching or passing through the stretch. Red lanterns or flashing warning lights of suitable type spaced suitable intervals mounted on barricades along the diversions shall be provided and kept operational and maintained throughout from sunset to sunrise.
- x. There could be locations where below the station structures, there is running traffic underneath which may not be stopped / diverted and will continue to move uninterrupted during construction and post - construction periods. In the case of the pre-cast elements there could be locations where ground just below the launching area is not accessible or restricted due to traffic movement. The contractor should take care of these factors in to account while deciding the construction methodology / launching scheme for cast-in-situ / precast construction. Nothing extra will be paid for such eventualities.

## 22. LIGHTING AND FIRE PREVENTION

- i. Wherever night working is carried out by Contractor, temporary lighting arrangements of required lumen as per approved layout shall be provided, installed, maintained for the duration of the contract and removed after completion of work by and at the expense of the contractor.
- ii. Flashing lights to warn the traffic on roads shall be used at all times on all obstructions.
- iii. Contractor shall provide and maintain adequate firefighting equipment and take adequate fire precautions for the safety of all personnel, plant, and material including temporary and permanent works and shall take action to prevent damage to or destruction by fire of trees, shrubs and grasses.
- iv. No extra payment will be made for the provision of temporary lighting, flashing lights and fire prevention measures and the entire cost of all such work shall be deemed to have been included in the Scope of Price schedule.

## 23. UTILITIES

- i. Necessary permanent diversion of utility services (Chartered utilities) shall be undertaken by contractor. The contractors shall liaise with the Utility Authorities for carrying out the work expeditiously wherever required so that works at particular locations are not delayed. In case they come across any utilities

(Uncharted utilities) also they shall have to liaise with the agency concerned for the necessary diversion; the cost of diversion shall be paid by Employer under the relevant item of **Schedule-C** of Price schedule. The contractor shall provide any temporary support for the utilities if called for, but at no extra cost. Temporary diversion of utility if necessary at site, the same shall be done by the contractor up to the satisfaction of the concerned utility owner and payment will be made under relevant items of work. Such temporary diversion is permitted only once for the particular utility.

- ii. All uncharted underground shall be shifted by the contractor, irrespective of whether it is temporary or permanent diversion. However, during execution of work, if any uncharted utilities are met, the contractor shall temporarily support or temporarily divert the same at his own cost. In case, this is not possible as decided by Engineer, then the same will be permanently diverted by the contractor and the payment will be made under respective item in the relevant payment schedule of Works under **KPWD / IR-USSOR / CPWD / BWSSB / BESCO-SR 2023-24 and its amendment or latest(Schedule-C,).**
- iii. For the existing utilities owned by Railways, where the shifting thereof can take place only after certain works for its shifting have been completed by the contractor, the concerned contractor shall, undertake and complete the works required for its shifting first. The concerned contractor in this case may be the contractor executing the present work or another contractor, as directed by the Employer.
- iv. The tender utilities drawings are only indicative. Contractor should make his own survey for identification of underground I above ground utilities;
- v. New utilities: In the event the construction of any work is affected by a new utility, the contractor shall be entitled to a reasonable Time Extension in accordance with the provisions of contract. Th decision of Employer is final in this regard.

### 23.1 Damage to Utilities

The contractor shall be responsible for any theft, damage and / or protection of all the existing utilities within the site of work during currency of the Contract. In case of any theft / damage occurring to these utilities while working or otherwise, the contractor shall immediately inform both the Employer's representative and the Engineer's representative as well the utility owning agency and restore the same immediately to the entire satisfaction of the utility owning agency. Any damage due to working / negligence / fault of the contractor (the decision of Employer in this regard shall be final and binding), the same shall be repaired / made good by the contractor at his own cost. Any damage / compensation I penalty etc. if charged by the utility owning agency in this regard shall also be payable by the contractor and no claim in this regard will be entertained by the Employer. Any legal action to be faced in this regard shall also be the responsibility of the contractor. The contractor shall always keep indemnifying the Engineer / Employer against all these issues.

## 24. INTERFACE WORKS

In addition, the contractor shall be required to carry out various interface works as per interfacing requirements. An Approved interfacing Manual will be supplied to the contractor, which needs to be followed by the contractor for all interfacing works.

The Scope of interface works for various interfacing Contracts E.g., Architectural finishes, MEP, Signaling& Telecommunication, Automatic Fare Collection, Traction Power & Power Supply, Track work, Rolling Stock, Noise barrier etc., shall be but not limited to as described below:

- i. Architectural finishes
- ii. MEP works.
- iii. Fixing arrangements for OHE for traction, Signaling post, Telecommunication structures, AFC, PSD, SCADA, Lifts, and Escalators etc.
- iv. ASS and TSS Room size and layout, openings in slab and viaduct beams, foundations and cable trays / ducts / hangers.
- v. Traction Power earthing arrangements- Grid earthing.
- vi. Layout of AFC Equipment in concourse, Raceways and cable trays / power sockets required for AFC Equipment.

- vii. Rolling Stock- structure gauge / schedule of dimensions etc. yellow line marking on platform.
- viii. Location and sizes of platform supervisory panels.
- ix. Location of rear-view mirror Train operation group,
- x. Location Layout, sizes, Shafts, walls, power supply for lifts and escalators
- xi. Construction of Utility Rooms
- xii. Cable ducts / cables / hangers / trays / raceways for routing all type of cables, cross- track cast in cable ducts, space cut-outs to the ceiling / wall finishes for mounting clocks, telephones, public address system equipment etc.
- xiii. Foundations for UPS unit, DG set and other equipment as required.
- xiv. Foundations for antenna mounting tower structure.
- xv. Space and mounting arrangement for work stations / control panels and other equipment.
- xvi. Earthling and lighting protection.

## 25. RESPONSIBILITIES OF CONTRACTOR

### 25.1 Casting Yard

The land for setting up of casting yard and stacking yard as required shall be arranged by the contractor at his own cost. However, assistance can be provided by Bi-RIDE by giving recommendatory letters etc., to the concerned authorities, without any guarantee for providing the land. The casting yard shall have following minimum facilities.

1. Casting beds as required.
  2. Sets of form work / moulds, as required.
  3. All handling facilities for precast elements like over gantry, etc.
  4. Curing arrangements as required.
  5. Stacking arrangements for material and precast elements.
  6. Storing arrangement of materials.
  7. Proper drainage and all-weather approach roads.
  8. All facilities for inspections
- 
- ii. General works such as setting out, site clearance on completion of works. All weather approach roads to the site office should also be constructed and maintained in good condition.
  - iii. All labor, materials, plant, equipment and temporary works, overhead charges as well as general liabilities, obligations, insurance and risks arising out of GCC, required completing and maintaining the works to the satisfaction of the Engineer.
  - iv. Adequate lighting for night works, and also at other times whenever and wherever required by the Engineer.
  - v. All equipment, instruments, labor and materials required by the Engineer for checking alignment, levels, slopes and evenness of surfaces measurements and quality etc. shall be arranged by the contractor.
  - vi. Design mixes and testing them as per relevant clauses of specifications giving proportion of ingredients, sources of aggregates and binder along with accompanying trial mixes. Test results shall be submitted to the Engineer for his approval before adoption on works.
  - vii. Method Statements, for each main activity of the work (temporary and permanent) to be executed detailing the purpose, scope, resources required, sequence / procedure of execution, persons responsible, time frame, safety requirements & measures, risk analysis, Inspections, and Test Procedures along with standard values / acceptable criteria etc. duly approved by the Employer / Engineer before start of that particular activity at site.
  - viii. Contractor shall also prepare / approve and make available to the Employer and the Engineer the work procedure for each sub-activity to be done at the site, detailing the



procedure / process to be followed including work sequence, safety measures, to be followed, level of quality to be maintained, type of material to be used, type of finishing required, and responsibility assigned etc.

- ix. Preparation and compliance with provision of a quality assurance control programme.
- x. Prepare and submit the price breakup schedule based on the Quantities to be executed based on the approved drawings for the purpose of billing
- xi. Safe setting up and functioning of gantry cranes and any other cranes used for lifting activities will be the responsibility of the contractor.
- xii. Safety measures and requirements of site safety plan

The contractor shall make adequate security arrangements for 24x7 protection of Temporary and permanent works and deployed resources.

- I. The Contractor shall be responsible for the security of the Site for the full time the Site is in its possession, except for the specific case after handover to the Employer. The contractor shall set up and operate a system whereby only those persons entitled to be on the Site can enter the Site. To this end, the contractor shall with the consent of Employer provide the specific points only at which entry through the security fence can be affected and shall provide gates and barriers at such points of entry and whereby maintain a twenty-four (24) hours security guard, and such other security personnel and patrols elsewhere as may be necessary to maintain security.
- II. The contractor shall maintain all site boundary fences in good condition and shall so arrange site boundary fences at all access drainage points of work areas that its use of such access points etc., are not restricted by the system or method of achieving the required security measures. Notices shall be displayed at intervals around the Site to warn the public of the dangers of entering the Site.
- III. During the progress of the Works the contractor shall maintain such additional security patrols over the areas of the Works as may be necessary to protect its own and its sub-contractor's work and equipment and shall co-ordinate and plan the security of both the work under this Contract and the work of others having access to and across the Site and the Works.
- IV. In order to operate such a security system, it will be necessary to institute the issue of unique passes to personnel and vehicles entitled to be on the Site, and which may need to be separately identifiable according to the shifts being worked on Site. The contractor shall at the outset determine, together with the Employer I Engineer, a system, and the design of passes to suit the requirements of the foregoing and to suit the methods of work to be adopted by the contractor. The contractor shall at all times ensure that the Employer and the Engineer has an up-to-date list of all persons entitled to be on the Site at any time. The contractor shall also introduce a system of issue passes to any outsider or person I vehicles belonging to agencies other than Employer I Engineers who may have to visit the site in connection with the work.
- V. The contractor shall liaise with the Designated Contractors and the contractors responsible for the adjacent and other interfacing contracts and ensure that coordinated security procedures are operated, in particular in respect of vehicles permitted to pass through the Site and I or the adjacent sites in the latter periods of the Contract.
- VI. Security and checking arrangements as felt necessary shall be provided with advice and help of Police.
- VII. Safe guarding environment.

**25.2 The contractor shall carry out expeditiously and without delay the following works.**

- a. Identify and get approved of the sources of various major construction materials.
- b. Material testing and mix designs of concrete as contemplated in the specifications.
- c. Setting up of fully fledged site laboratories as per the requirements.
- d. Setting up concrete batching & mixing plant.
- e. Deleted
- f. Contractor's site office setup. Maintenance of employer/engineer project site office
- g. Casting yard with complete facilities.
- h. Any other pre-requisite items required for final execution.
- i. Any other items specified in other sections of the contract.

## **26. ASSOCIATED WORKS DEEMED INCLUDED IN SCOPE OF PERMANENT WORKS**

### Contractor's Organization and Plant & Equipment

#### Project Organization Plan

- i) The Contractor's Personnel shall be deployed & maintained in consultation with the Employer and as per the requirements. The Contractor's Superintendence shall be also properly deployed and maintained to carry out the construction activities as described in the relevant General Conditions of Contract (GCC) clause.
- ii) The contractor shall submit an updated Project Organization Plan which includes complete project organization chart during the Construction Phase adding functions and personnel necessary to perform the Works during the Construction Phase in accordance with the conditions of the Contract. This plan shall be updated and resubmitted whenever there are changes to the staff and I or the organizational structure. The plan shall show the management structure and state clearly the duties, responsibilities and authority of key staff members.
- iii) The contractor shall deploy the key personnel of requisite qualification and experience. In case Employer instructs (in writing) the contractor to remove a person of his work force stating the reasons, the contractor shall ensure that the person leaves the Work Area within seven days and shall have no further connection with the Works in the Contract. The Engineer, in case, feels that a person of contractor's work force should leave, the matter shall be brought to the notice of the Employer by the Engineer for issuing suitable instructions to the contractor, after the Employer is satisfied.
- iv) During the Construction Phase, the contractor shall maintain the Design Team in his organization independent of the Construction Team to deal with Preliminary design, definitive design and working drawings.
- v) The minimum requirements for manpower are attached as **Appendix 4 [Organization charts and key positions] of Employer Requirement Annexure-1.**

### **26.1 Plant and Equipment**

- a) The minimum Plant and equipment as shall be maintained in consultation with Employer and the Engineer as per the requirements.
- b) The minimum requirements for plant & equipment are attached as **Appendix 5 [Plant and Equipment] of Employer Requirement Annexure-1.**

## **27. PENALTY FOR NON-COMPLIANCE**

Notwithstanding the provisions elsewhere in the bid documents, the contractor shall be penalized as detailed below:

### a) Correction of Defects

If the Employer / Engineer determines that any item or part of it was constructed with bad workmanship and/or using sub-standard construction materials,

Sl. No.	Nature of Defects (Indicative only)	Penalty (Rs.)
1.	Not maintaining plumb line, level in concrete works / observing honeycombs on the finished surface of concrete	1,00,000 / - each case
2.	Usage of unapproved / sub-standard materials	2,00,000 / - each case

The above-said penalty is envisaged to act as deterrent against bad workmanship and usage of sub-standard construction materials by the contractor and shall be imposed for every occurrence. These penalties are non-refundable.