

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
1.	Section - 11	Attachment 1 (Alignment plan & Profile)	Kindly provide topo survey data carried out by other contractor based on which the alignment plan & profiles are prepared	Since this is the EPC contract, the bidder needs to inspect and satisfy himself the site condition, preliminary survey, GTI investigation and topography of site before submission of the bid.
2.			Bidder also requests Authority to provide the topo survey carried out by other contractor on finished surface with details and extent of works mapped clearly in the topo data.	
3.	Section - 6	Annexure-2 Part A Contract Data	<p>a) Please provide the locations / sections where the RoW constraints exists. Also provide the status of land acquisition / retention measures suggested by other contractor for bidder's understanding.</p> <p>b) It is also specifically understood that encroachment at defense land exists. Please clarify the current status of acquisition and it may be re confirmed to bidder that the time line given to acquire the land which is 90 to 120 days will be understood to be reasonable and land will be handed over to awarded bidder within the specified days.</p>	Status of hindrances (incl Defence land) are mentioned in the Annexure-2 of Part A Contract Data.
4.	Tender Notice	Name of Work: "Design & Construction of Formation in Embankments, Cuttings including Blanketing, Ramp, ROB, Minor Bridges, RUB, ERS/Retaining Wall, Sacrificial Retaining Wall, Drains, Boundary Wall and fencing works At-Grade Section of length 5.80 Km (Ch: 18.400 Km To Ch: 24.200 Km) (Balance Works) and Elevated Viaduct of length 185m (24.200 To 24.385) for BSTP Corridor and also IR Corridor and other related Infrastructural works from Yeshwanthpur to Chikkabanawara including validation of Design and Stability check wherever applicable for works executed by previous contractor (excluding Station Buildings), of Corridor - 2 of Bengaluru	As the scope of work include <b>".....validation of Design and Stability check wherever applicable for works executed by previous contractor"</b> , bidder request to share the design analysis (model files), design documents and design drawings formulated by other contractor.	The Defects Liability Period (DLP): Responsibility for the works executed by the previous contractor shall remain with the previous contractor. However, the new contractor shall be required to carry out the necessary validation, stability checks, and assessment of the works already executed, in order to satisfy himself regarding their adequacy and suitability before continuing with the remaining works.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
		Suburban Transport Project (BSTP)".		
5.		Attachment 2(Tender Drawing) package -3	Kindly provide the design notes of ERS, Elevated Viaduct, MIB, OHE foundations, precast compound wall, RoB, RUBs, Formation side drains. Slope stability analysis for cut slopes, fill slopes and retaining wall walls with surcharge slopes.	Refer S.no 1 & 4 above.
6.			Kindly Provide the Geotechnical Investigation Reports (GIR) and foundation recommendation reports for all structures proposed in the Package.	Tender includes available approved GTI data for reference. However, bidder may carry out independently the additional GTI investigation and satisfied itself to determine the foundation design needed for the works covered in the present tender. Quoted price shall include cost towards additional GTI investigation carried by the bidder.
7.			Please provide the status of 2 Nos RoB approvals from South Western Railways. Kindly confirm whether the bidder shall follow the span arrangement / type of structure proposed in the reference drawings / GADs.	South Western Railway has already accorded the approval for 2 Nos of RoBs.  Please refer the S.no 17 & 18 of Corrigendum for the updated drawings of RoBs including the present tender scope of work.
8.			Kindly confirm that bidder shall follow RDSO superstructure drawings for 54m and 42m spans which are indicated in the GADs provided to bidders.	Refer S.no 7 above.
9.			Authority may also provide dismantling schemes of existing 2 Nos RoBs available for bidder's understanding and the dismantling schemes approval status from South Western Railways including block period required / approved from South Western Railways.	Being EPC contract, the successful bidder shall submit the methodology/ scheme of dismantling of RoB, duration required and block period needed for execution of work.
10.			Kindly provide, protection scheme for existing IR formation at BI-Ride's new RUB construction locations.	Being EPC contract, the successful bidder shall submit the methodology/ scheme of protection of existing IR formation at new RUB locations,
11.			Authority may provide the As-Built drawings prepared by other Contractor for all structures unfinished / completed clearly indicating the designs followed and its status of work completion.	Available data / drawings have been already provided in Section 11 of tender document. The successful bidder shall prepare the as-built drawing for all the works carried out by the previous contractor. The quoted price shall include cost towards making of As-Built drawing of the previous contractor.
12.			As per site condition, the works done by other Contractor are not integrated with existing IR tracks. Kindly provide	Available data / drawings have been already provided in Section 11 of tender document.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
			design issues / approval related issues with respect to such structures. Please forward structure wise details and its road blocks for bidder's understanding.	
13.			Bidder requests Authority for existing utilities and its protection drawings. Authority may also provide the unfinished works status clearly indicating the scope and extent of involvement of the bidder.	Utility shifting of sewer and water pipeline, ET/HT power line / cable crossings, S&T utilities is not in the scope of the Contractor.
14.			Please provide the quality control reports of executed works of other contractor.	The details shall be provided to successful bidder.
15.			There is one water main crossing the proposed alignment. Kindly provide the schemes for diversion of the water pipe line (or) kindly provide the construction method proposed by Bi Ride at this location.	The Water main crossing at chainage at 20.600 is not required to be shifted.
16.			Kindly provide traffic diversion plans / traffic management plans at proposed RoB locations. Please also update the status of approvals of traffic management plans from traffic police.	The bidder shall inspect the work spot and satisfy himself about the identification of site approaches, route plan and movement of transit mixers, launching equipment, heavy machinery, and girder transportation, in consultation with the local traffic police and other local authorities. The necessary request letters for such permissions to the local authorities will be issued by Bi-RIDE upon the request from the contractor. All coordination and liasoning with the local authorities rest with the bidder. KMZ file can also be referred
17.			Bidder requests the status completed & unfinished works of drains / retention system between IR and Bi Ride lines. Kindly provide the design drawings including any integration of IR drainage network with Bi Ride drainage network.	Please refer the tender drawing enclosed.
18.			Kindly provide KMZ file of the project corridor.	KMZ file uploaded in the K-RIDE website.
19.	SECTION VIII: VOL-1	The retaining walls of approximately 3.4 Km length (0.4km partially completed) is required to be constructed and the height is varying from 1m to	0.4 km is partially completed by the previous contractor. Will the Employer provide detailed status reports and quality report.	The details shall be provided to successful bidder.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
		12m for supporting the embankment/cutting slope and the details are in Tender drawing and the scope of work also includes the remaining tasks left incomplete by the previous contractor. Approved structural drawings enclosed in the tender. The contractor has a liberty to follow the same or redesign with the DDC		
20.	Invitation for Bids, Period of Completion	18 Months	Bidder understands that 18 months completion period is very stringent and requests to change the completion period to 26 Months considering project having 2 Nos of RoBs (dismantling and construction of new structures over live tracks).	Tender condition prevails
21.	Submission Date	05 Jan 2026	As this is a Design-Build tender, our team requires additional time to prepare designs based on the clarifications received after our prebid meeting. Given the extensive scope, we also need more time to review the documents and finalize our planning, schedule, and resource plan to submit a competitive offer. We therefore request a 21-day extension, i.e., up to 23 January 2026, for submission of our tender.	Tender condition prevails
22.	-	Clarification on GST	As per point no. 29 of IFT, it is specified that, the rates quoted by the tenderer shall be inclusive of all taxes, levies, duties, royalties etc. excluding GST. In this regard, please clarify whether the Employer will reimburse the applicable GST to the Contractor against each RA bill/ invoice?	Tender condition prevails.
23.	-	Mobilization advance/ P & M advance- Request for interest free advance	The clause 42 of CC/ PCC section 7 specifies mobilization advance as well as the P & M advance as interest bearing advances with interest rate mentioned as SBI MCLR + 2% 3 Year. In this regard, as like in ongoing KRIDE project contract provisions, we request that, the mobilization advance and P & M advance shall be interest free. The purpose of such advances are to support cashflow of the Contractor in the beginning stage of contract for mobilization of huge resources/ setup.	Tender condition prevails

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
			The interest free advance against submission of BG of 110% of advance value will facilitate to serve the said intended purpose. Moreover, the interest rate of SBI MCLR + 2% 3 Year is far more than the existing rates of many banks/ financial firms.	
24.	-	-	In case if the work carried out by the left-out Contractor required rework (on account of design flaw or for any other reason), such requirement shall have to be treated as change of scope/ variation works and shall be paid to the Contractor separately. The risk of such occurrence shall be in scope of the Employer. <b>Please confirm.</b>	The Defects Liability Period (DLP): Responsibility for the works executed by the previous contractor shall remain with the previous contractor. However, the new contractor shall be required to carry out the necessary validation, stability checks, and assessment of the works already executed, in order to satisfy himself regarding their adequacy and suitability before continuing with the remaining works..
25.	Section-2: Instruction to Tenderers (ITT)	Clause c) of Component No. 3	Minimum component of work mentioned is 2 No's. We request you to reduce to 1 No. (or) consider 37 meter of Bow string girder /Open web girder/Composite steel Girder of 1 no.	Tender condition prevails.
26.	Right of Way (ROW)	General	Kindly provide the ROW details and the centre-to-centre distance from the existing operational railway track along the entire alignment.	Alignment drawings attached with tender document indicates ROW. However please note that the Contractor need to carry out the work within the available Railway land/ acquired land by KRIDE. This fact needs to be checked by Bidder and satisfy himself after site verification and before submission of the bid document.
27.	Ownership of Existing Casting Yard	General	During the contract period, will the existing casting yard remain under the control of the previous contractor, or will it be handed over to the successful L1 bidder / K-RIDE? Kindly clarify.	The responsibility of arranging of casting yard for casting of precast elements is in the scope of the Contractor.
28.	Existing Site Camps	General	The existing site camps are currently occupied by the previous contractor. Please confirm when these areas will be vacated and handed over.	The previous Contractor has already vacated the site camp all along the alignment.
29.	Drone Video	General	Request you to share the drone footage presented during the pre-bid meeting for better understanding of site conditions.	Will be made available for viewing/reference purpose in office of GM/Procurement.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
30.	Unsuitable Soil Disposal Locations	General	Please provide the designated dumping locations for unsuitable soil, if identified.	The unsuitable soil disposal locations are already identified by the local authorities and Bidder should verify and satisfy himself in consultation with the local authorities before submission of the bid. All lead and lift shall be included in the quoted price.
31.	Readable AutoCAD Drawings	General	Certain uploaded drawings contain misprints and unclear chainages. Kindly provide clearly legible AutoCAD files.	Such specific drawings will be made available for reference purpose in office of GM/Procurement.
32.	Site Approach / Concreting Route Plan	General	Request you to share the approved route plan for movement of transit mixers, concrete vehicles, and heavy machinery.	The bidder shall inspect the work spot and satisfy himself about the identification of site approaches, Route plan and movement of the transit mixtures, concrete vehicles, and heavy machinery. In consultation with the local traffic police and other local authorities.
33.	Land Hindrance Clearance	General	Please provide the timeline for clearance of buildings, temple structures, trees, IOCL pipeline, and other obstructions along the alignment.	The tender document provides the necessary utility shifting details along with the timeframe for hindrance. Refer Contract data Annexure-2.
34.	Shifting of Sewer & Water Pipelines	General	At multiple locations, sewer and water pipelines are yet to be shifted. Kindly clarify whether this shifting is within the scope of the successful bidder or to be arranged by K-RIDE.	Utility shifting of sewer and water pipeline, ET/HT power line / cable crossings, S&T utilities is not in the scope of the Contractor.
35.	Traffic Permissions for Heavy Machinery Movement	General	Kindly confirm whether K-RIDE will arrange or facilitate departmental permissions for the movement of transit mixers, launching equipment, heavy machinery, and girder transportation.	The bidder shall inspect the work spot and satisfy himself about the identification of site approaches, route plan and movement of transit mixers, launching equipment, heavy machinery, and girder transportation, in consultation with the local traffic police and other local authorities. The necessary request letters for such permissions to the local authorities will be issued by Bi-RIDE upon the request from the contractor. All coordination and liasoning with the local authorities rest with the bidder. KMZ file can also be referred.
36.	Defect Liability for Previously Executed Works	General	Since the scope includes validation, stability checking and continuation of works already executed by the previous contractor, kindly clarify who will bear the Defect Liability	The Defects Liability Period (DLP): Responsibility for the works executed by the previous contractor shall remain with the

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
			Period (DLP) responsibility for previously executed portions—the new contractor or the earlier contractor / K-RIDE.	previous contractor. However, the new contractor shall be required to carry out the necessary validation, stability checks, and assessment of the works already executed, in order to satisfy himself regarding their adequacy and suitability before continuing with the remaining works.
37.	Status of HT/LT Electrical Utilities	General	Kindly clarify the status of HT/LT cable shifting and whether this is within the bidder's scope.	HT/LT cable shifting is not in the scope of this contract.
38.	Tree Cutting & Environmental Clearances	General	Please confirm whether required approvals for tree cutting and environmental clearance have been obtained or will be arranged by K-RIDE.	Yes. Tree cutting and environmental clearance for this project is obtained by K-RIDE. Tree cutting is not in the scope of Contractor.
39.	Night Shift Working Permission	General	Please confirm whether night shift work is permitted, especially in residential areas, or if only day-time work will be allowed.	The bidder shall inspect the work site and satisfy himself regarding the feasibility of carrying out day and night operations, including obtaining the necessary working permissions in consultation with the local police and other relevant authorities. However, the contractor shall plan and execute the work in a manner that minimizes disturbance and noise pollution during night hours for the residents living in the adjoining areas.
40.	Responsibility for Existing Utility Shifting	General	Kindly confirm that all existing, identified utility shifting along the alignment shall be the responsibility of the Employer.	Utility shifting of sewer and water pipeline, ET/HT power line / cable crossings, S&T utilities is not in the scope of the Contractor.
41.	Responsibility for Unidentified/Uncharted Utilities	General	Please confirm whether any unidentified, uncharted, or newly discovered utilities encountered during execution shall also be handled and shifted by the Employer.	Refer S.no 40 above.
42.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK,  SectionVIII, II) BRIEF SCOPE, 1. Elevated Viaduct	Design & Construction Elevated Viaduct of Length 185m (24.200 to 24.385) using U girder or I-girder including ramps.	Please clarify whether the levels maintained in L-section for the viaduct at obligatory locations in 185m length are satisfying for both U-Girder and I-Girder structure depths.	Rail levels are fixed. Being EPC contract, the sub structure and super structure needs to be designed accordingly.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
43.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK,  SectionVIII, II) BRIEF SCOPE, 2. AT GRADE FORMATION	..... allied works approach road work viz., Retaining wall, Sacrificial retaining wall,.....	Kindly provide the locations / stretches where sacrificial retaining is required to be provided.	Sacrificial wall is not envisaged in this package.
44.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK,  SectionVIII, II) BRIEF SCOPE 3. At Grade, f)	.....Approved structural drawings enclosed in the tender. The contractor has a liberty to follow the same or redesign with the DDC.	As per pre-bid meeting held on 18 <sup>th</sup> November 2025, it was clarified that the drawings are approved for structures except for RoBs and the construction has to be done as per the approved drawings. However as per Clause 3, there is an employer giving an option to redesign with the DDC. Please clarify, contractor should follow approved drawings or appoint DDC for redesign where works are not executed.	Bidder to follow construction of superstructure of ROB as per the railways approved GAD. However, foundation, substructure and other component of the ROB are to be designed by Bidder (their DDC).  However, all structural drawings approved by the Bi-RIDE as indicated in the bid document can be used for construction.
45.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK,  SectionVIII, II) BRIEF SCOPE 3. At Grade, k)	The successful bidder shall undertake the design validation and stability assessment of the previously completed works, ensuring their compliance with the required standards and specifications.	During the pre-bid meeting, it was clarified that the Contractor need not have to revalidate the designs and balance execution shall be done as per the approved drawings available. Please confirm.	The Defects Liability Period (DLP): Responsibility for the works executed by the previous contractor shall remain with the previous contractor. However, the new contractor shall be required to carry out the necessary validation, stability checks, and assessment of the works already executed, in order to satisfy himself regarding their adequacy and suitability before continuing with the remaining works.
46.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK, SectionVIII, II)	Miscellaneous items for works which are not covered in schedule A and B shall be executed and payment shall be paid under Section C, provisional sum	Please provide the list of miscellaneous items which are envisaged under this provisional sum.	Tender condition prevails.



**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
	BRIEF SCOPE 4.MISCELLANEOUS WORKS			
47.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK, SectionVIII, IV) Detailed Scope of Work 1.Objective	In full recognition of this objective, and with full acceptance of the obligations, liabilities and risks which may be involved, the Contractor shall undertake the execution of the Works. The general and specific requirements of the employer are detailed out in this document for understanding of the bidders and for mandatory compliance by the successful bidder/contractor. The Employer's requirements have been divided into different sections / sub-heads for convenience only. They do not restrict any cross-references. The Contractor shall take into account inter-relations between various parts of works. No claim shall be entertained on account of compartmental interpretations.	Though contractor will take inter-relations between various parts of works, bidder requests Employer to specify the boundary limits of such inter-relations as the statement in the clause has no cap on scope of works leading to many interpretations with regards to scope of works.	Tender condition prevails.
48.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK, Section VIII, 1.0 DETAILED SCOPE OF THE WORK B) EARTHWORK IN EMBAKEMENT AND CUTTING	The drainage arrangement between IR tracks and BSTP tracks at formation level, side drains at toe / ground level, drains at berm level, catch water drains / saucer drains are included in the scope of work.	Please provide the locations of the drains at berm level, catch water drains / saucer drains.	Typical cross section indicating drain is available in tender drawing which can be referred. The actual location of drains may have to be asses by the contractor after carrying out calculation of rain water runoff.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
	INCLUDING RETAINING WALL AND DRAINS:			
49.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK, Section VIII, 1.0 DETAILED SCOPE OF THE WORK, C. ROB, MINOR BRIDGES, RUB and Other Special Spans	Works / Design of items specified under this Clause.	During the pre-bid meeting, it was clarified that the Contractor need not have to revalidate the designs and balance execution shall be done as per the approved drawings available except RoBs. Please confirm.  Also Employer may let the bidder know items under this Clause, which are required to be designed.	The Defects Liability Period (DLP): Responsibility for the works executed by the previous contractor shall remain with the previous contractor. However, the new contractor shall be required to carry out the necessary validation, stability checks, and assessment of the works already executed, in order to satisfy himself regarding their adequacy and suitability before continuing with the remaining works.
50.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION  AND SCOPE OF WORK, Section VIII, 1.0 DETAILED SCOPE OF THE WORK, D. MISCELLANEOUS: INCLUDING ROADS, BARRICADING, QUALITY, INTERFACE WORK, CASTING YARD, AND EQUIPMENT, PERSONNEL ETC.	S.No. 1 to 42	Please provide the quantum of items / works (chainage wise) to be executed by bidder in two parts:  1) Items which are executed by other Contractor and which are unfinished.  Items which are newly to be taken up.	Bid document include details of the works executed by the previous contractor and balance work (including new works) covered in the scope of present tender.
51.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL	S.No. 1 to 23	Please clarify the quantum of road works including public roads which are to be constructed by bidder in two parts:	The tender drawings shall be read along with tender document provides the details of

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
	INFORMATION AND SCOPE OF WORK, Section VIII,		<ol style="list-style-type: none"> <li>1) Roads which are executed by other Contractor and which are unfinished.</li> <li>2) Items which are newly to be taken up.</li> </ol>	permanent road work involved for RUBs, and its ramp. However as per the contract document maintenance of the existing road for approaching the work locations, temporary diversion haulage roads etc are also part of the EPC contract.
52.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 1.2 Clearances, Investigations and Reinstatement	S.No. 1.2.1 to 1.29	Please provide the list of stakeholders and clearances, reinstatements, protections, traffic diversions required to be provided in the project along with the quantity.	Tender conditions prevail.
53.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 1.3 Detailed scope of works.	S.No.1.3.1 to 1.3.4	<p>Kindly provide:</p> <ol style="list-style-type: none"> <li>1. List of project partners</li> <li>2. Their domain and relevancy with the current scope</li> <li>3. List of Utilities and its status of execution by other Contractor</li> </ol> <p>Geotechnical investigations</p>	Tender conditions prevail.
54.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 1.4 Design.	S.No. 1.4.1 to 1.4.5	<p>Please clarify the following:</p> <ul style="list-style-type: none"> <li>As per pre-bid meeting, bidder need to follow the approved designs for construction. The works which are required to be designed by bidder may be specified.</li> </ul>	<ul style="list-style-type: none"> <li>The Defects Liability Period (DLP): Responsibility for the works executed by the previous contractor shall remain with the previous contractor. However, the new contractor shall be required to carry out the necessary validation, stability checks, and assessment of the works already executed, in order to satisfy himself regarding their adequacy and suitability</li> </ul>

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
			<ul style="list-style-type: none"> <li>Whether the bidder should appoint a proof consultant for works left to be carried out.</li> <li>Kindly provide the 3D models prepared by other contractor</li> </ul>	<p>before continuing with the remaining works.</p> <ul style="list-style-type: none"> <li>The scope of work of the present contract includes appointment of DDC and proof checking agency.</li> <li>The available data is already shared in the bid document.</li> </ul>
55.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 1.5 Interface and Coordination.	S.No.1.5.1 to 1.5.8	<p>Kindly provide the following:</p> <ul style="list-style-type: none"> <li>List of interfaces / stakeholders / partners</li> <li>Interfaces matrix clearly defining the boundary limits of works of stakeholders, dependencies and project stage at which interfacing is required to be done (<i>provided matrix is very generic lacking clear marking of boundaries of scope in form of drawings / sketches</i>)</li> <li>Access routes, cutouts, cable trenches, services corridors etc which are required by other partners and their quantum with drawings and locations</li> </ul> <p>Pending interface disagreements between project partners / stakeholders etc</p>	Refer the interface matrix enclosed in the tender document.
56.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 1.6 Utility Diversions.	S.No. 1.6.1 to 1.6.11	<p>Kindly provide / clarify the following:</p> <ul style="list-style-type: none"> <li>List of utilities at foundation locations which may probably infringe with proposed foundations for bidder's understanding</li> <li>List of utilities diverted</li> <li>List of unfinished utility diversions</li> <li>List of utilities to be diverted</li> </ul>	<ul style="list-style-type: none"> <li>Utility shifting of sewer and water pipeline, ET/HT power line / cable crossings, S&amp;T utilities is not in the scope of the Contractor.</li> </ul>

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
			<ul style="list-style-type: none"> <li>List of military and gas utilities and its status of diversions</li> <li>Temporary diversions required</li> <li>Temporary utility protection list and its protection details</li> </ul> <p>List of NOCs approved, in progress and to be obtained</p>	
57.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII,, G. SALIENT FEATURES OF DESIGN & CONSTRUCTION AND OTHER INSTRUCTIONS	S.No. 1 to 95	<p>Kindly provide / clarify the following:</p> <ul style="list-style-type: none"> <li>DBR of BSTP</li> <li>List of locations where solar panes are required to be fixed on ERS</li> <li>As per the pre-bid meeting, approved drawings are required to be followed for construction. Which of the designs are specifically required to be carried out by bidder</li> <li>List of minor / major utilities which can't be diverted.</li> <li>Strengthening requirements of minor / major utilities.</li> <li>As per the pre-bid meeting, the horizontal and vertical alignments shall be followed as per the approved drawings. However, as per Clause 21, the contractor shall validate and design a best fit alignment. This is contradicting. Please clarify.</li> <li>List of locations where speed reductions are to be imposed.</li> <li>List of permanent diversions (completed and yet to be carryout)</li> </ul>	<ul style="list-style-type: none"> <li>DBR is available in KRIDE website.</li> <li>Solar panel installation is not in the scope of this tender.</li> <li>Refer S.no 49 above.</li> <li>Refer S.no 56 above.</li> <li>If any shall be designed and to be protect by the Contractor.</li> <li>The plan and profile of the alignment are fixed.</li> <li>The plan and profile of the alignment are fixed.</li> <li>Diversions if any Please refer Contract data Annexure-A</li> </ul>

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
			<ul style="list-style-type: none"> <li>Traffic police approval status for permanent diversion yet to be carried out.</li> <li>29) “..... Contractors shall provide any temporary support for the utilities, if needed, but at no extra cost.....” Please Clarify the temporary support requirements with locations.</li> <li>Whether the bidder should appoint a proof check consultant for works left to be carried out.</li> <li>Time period of actual performance monitoring of bridges / structures</li> <li>Locations of road widening and drains to and its approved drawings</li> <li>Sn.No 94). Please provide the probable list of missed out items</li> </ul>	<ul style="list-style-type: none"> <li>The bidder shall inspect the work site and satisfy himself regarding the feasibility of carrying out day and night operations, including obtaining the necessary working permissions in consultation with the local police and other relevant authorities. However, the contractor shall plan and execute the work in a manner that minimizes disturbance and noise pollution during night hours for the residents living in the adjoining areas.</li> <li>If any shall be designed and to be protect by the Contractor.</li> <li>The scope of work of the present contract includes appointment of DDC and proof checking agency.</li> <li>The bidder should design the structure/bridges for the life span covered in the contract.</li> <li>Tender condition prevails</li> <li>Tender condition prevails</li> </ul>
58.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII,, 2. Phases of Permanent Work	The drawings approved by KRIDE are enclosed with the tender documents and may be used directly for the execution of the works. For drawings that have not been approved by KRIDE, the bidder shall prepare and submit the required designs and drawings	Please provide a list of permanent structures / temporary structures which are not approved by Employer / Engineer.	Tender condition prevails.

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
		(such as General Arrangement Drawings and structural designs) for approval by the Employer through the General Consultant (GC) prior to execution		
59.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII,, 5. Availability of Land	A major portion of the required land for the execution of works is available along the alignment. The remaining land will be acquired and handed over to the contractor progressively	Please provide the remaining land acquisition details.	The details are available in Section 6 Contract data.
60.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 11. RESTRICTIONS IN WORKING	Existing City Roads	<ul style="list-style-type: none"> <li>Please provide the list of roads where one-way is imposed</li> <li>Kindly provide a list of roads where construction material is allowed to be carried along with time restrictions</li> </ul>	The bidder shall inspect the work site and satisfy himself regarding the feasibility of carrying out day and night operations, including obtaining the necessary working permissions in consultation with the local police and other relevant authorities. However, the contractor shall plan and execute the work in a manner that minimizes disturbance and noise pollution during night hours for the residents living in the adjoining areas.
61.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 17. SURVEY AND FIXING WORKING BENCH MARKS AND ALIGNMENT MARKERS	17.1 Bench Marks	Contractor understands that the previous contractor has completed the survey and the control points data / Bench Mark data will be provided to the bidder for having continuity of working at unfinished work locations and new works. Please clarify.	Available survey data shall be provided to successful bidder.
62.		17.2 Alignment	Please clarify whether the bidder shall follow the alignment fixed by the other contractor	Alignment drawings available in the tender document are to be followed.
63.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK,	STRUCTURAL ELEMENTS, SHAPE AND FORM	Please clarify that the shape of the structure shall be as per the designs carried out by other contractor / Railways (for obligatory spans)	Except for the super structure the shape of substructure may be adopted by the bidder same as adopted by previous contractor. However, superstructure need to be design

**Tender Number KRIDE/BSTP/C2/PACKAGE-3/2025      DATE: 04.11.2025**  
**BENGALURU INTEGRATED RAIL INFRASTRUCTURE DEVELOPMENT ENTERPRISE LIMITED (Bi- RIDE): C2/PACKAGE – 3**  
**Pre-Bid Queries**

S. No	Clause No., Section & Pg. No.	Original Clause in the Tender	Clarification/Suggestion by the bidder	Response by Authority
	Section VIII, 17. SURVEY AND FIXING WORKING BENCH MARKS AND ALIGNMENT MARKERS, 19.			and validated as per the Employer requirement.
64.	EMPLOYER'S REQUIREMENT – VOL-1 GENERAL INFORMATION AND SCOPE OF WORK, Section VIII, 17. SURVEY AND FIXING WORKING BENCH MARKS AND ALIGNMENT MARKERS, 23.	Utilities	<ul style="list-style-type: none"> <li>Please provide list of permanent diversion of chartered utilities under execution and its status of works by other contractor.</li> </ul> <p>Also, provide the list of chartered utilities which are permanently required to be diverted.</p>	Utility shifting of sewer and water pipeline, ET/HT power line / cable crossings, S&T utilities is not in the scope of the Contractor.