

SECTION 8A PART 1 EMPLOYERS REQUIREMENT**GENERAL INFORMATION & SCOPE OF WORK****NAME OF THE WORK**

Construction of 2nos of Road over bridge (ROB) and 1nos Road Under bridge (RUB) along with construction of service road and drainages in Lieu of Level crossings (LC) along the Corridor-4 Heelalige to Rajankunte. Bangalore.

I) BRIEF SCOPE

The proposed work is in between Heelalige and Baiyappanahalli. The work mainly consists of Construction of Road over Bridge (ROB) with BOW string, Composite Girder, RCC/PSC I girder span with Earth retaining wall approaches and Construction of Road under Bridge (RUB) using precast elements along with construction of service road, drain, footpath works etc. Upkeeping of traffic diversion road. The scope also includes interfacing and coordination with other contractors at the intersection points and with Indian railways/other agencies/authorities/local authorities, wherever required, for construction of 2nos of ROB and 1nos of RUB.

Details of Level Crossing				
SL No	Level Crossing (LC) No	IR Chainage	Location	Proposed structure
1	LC125	185/675	Singena agrahara, Bangalore	Road over Bridge (ROB)
2	LC126	187/176	Chintalamadivala, Bangalore	Road Under Bridge (RUB)
3	LC127	187/641	Huskur, Bangalore	Road over Bridge (ROB)

CONSTRUCTION OF ROAD OVER BRIDGE (ROB) AND ROAD UNDER BRIDGE (RUB) IN LIEU OF EXISTING LEVEL CROSSING (LC)

- A. Construction of Road Over Bridge (ROB) in lieu of existing LC 125 (Singena Agrahara) and 127 (Huskur). Construction of ROB consists of main components such as BOW String, Composite girders, Open / Pile Foundation, Pier, Pier cap, RCC / PSC I girders with RCC slab, Reinforced Earth approaches/Retaining wall, road pavement works on ROB and approaches including Service roads with drainage system and Foot path. Scope also includes development of alternate roads, by making good of existing road or construction of new road, for temporary traffic diversion.
- B. Construction of Road Under Bridge (RUB) in lieu of existing LC 126 (Chintalamadivala). Construction of RUB using precast segments by launching method or any suitable method as decided by the Engineer/Employer at the time of execution. Scope also includes construction of approaches by providing ramp with necessary slope, drainage arrangements as per relevant code/orders, base slab, backfilling on side of walls with boulders/sand/gravels as per the instruction of Engineer, road pavement works and retaining walls in approaches including Service roads with drainage system and Foot path works as per the approved drawing. Scope also includes development of alternate roads, by making good of existing road or construction of new road, for temporary traffic diversion.

II) DETAILED SCOPE OF WORK**1.0 OBJECTIVE**

The objective of the contract is the Construction & testing of permanent works, construction and removal of Temporary Works and rectification of defects appearing in Permanent Works by the contractor in the manner stipulated in the Contract. In full recognition of this objective, and with full acceptance of the obligations, liabilities and risks which may be involved, the contractor shall undertake the execution of the Works. The general and specific requirements of the employer are detailed out in this document for understanding of the bidders and for mandatory compliance by the contractor. The Employer's requirements have been divided into different sections / sub-heads for convenience only. They do not restrict any cross-references. The contractor shall take into account inter-relations between various parts of works. No claim shall be entertained on account of compartmental interpretations.

1.1 SCOPE OF THE WORK.

Below table shows the details of Road over Bridge (ROB) and Road under Bridge (RUB)

Details of Road over Bridge (ROB) and Road under Bridge (RUB)				
SL No	Level Crossing (LC) No	IR Chainage	Proposed structure	Structure details
1	LC125	185/675	Road over Bridge (ROB)	52m Bow string girder - 1nos, 20m PSC I girder – 7span with RT/RE wall approaches for 2 lane road traffic
2	LC126	187/176	Road Under Bridge (RUB)	Pre-Cast segment RCC box of size 6.00X2.90m (2.75 M clear height)
3	LC127	187/641	Road over Bridge (ROB)	37.491m (SK) Composite girder - 2nos, 20m PSC I Girder - 8nos with RT/RE wall approaches.

A. Road over Bridge (ROB) and Road under Bridge (RUB) permanent works.

- i. Construction of foundation works for Road over Bridge (ROB) including piles and pile caps / open foundations / rafts for columns / piers (wherever required) up to the minimum founding depths in accordance with the actual soil parameters as obtained from detailed sub-surface exploration as specified or directed. The Construction methodology is required to be approved by Engineer before carrying out the works. The founding level will be decided based on the Geotechnical reports by Engineer / Employer during construction or based on the method as approved by Engineer.
- ii. Supply, fabrication and erection of OPEN WEB GIRDER (OWG)/BOW String/ Composite Girder as per RDSO drawing, as per BSTP /DBR, IRS/IS specification for fabrication of steel bridge girders., IRS B-1/2001, IRS Welded bridge code (as corrected up to date), using contractors supply of steel conforming to IS:2062 quality 'BO', grade E350 from SAIL/TISCO/RINL/JSW complete. The work includes supply of steel, fillet or butt welding, post weld treatment, steel drifts, shop welding, shop riveting, HSFG Bolts, jigs, fixtures, testing of weld by NDT/radiography or any specified method. The work includes transportation of fabricated girder components from contractor's workshop to bridge site including loading and unloading with contractor's own labour, materials, tools, plants, machinery, scaffolding etc., with all lead, lift, ascent, descent, crossing obstruction etc., including all taxes, royalties etc., complete in all respects and as directed by the Engineer.

NOTE: 1. All steel plates used in the fabrication of this Bridge shall be of Grade E350 Fe 490 (B0) 2. Rolled sections would be confirming to IS:2062 quality E 250 Fe410 (B0), Fully killed and normalized. 3. The scope includes, preparation, submission and getting approval of fabrication (shop) drawings/schemes from railways/Bi-RIDE by contractor, cutting, shaping, drilling holes, welding of components, welding consumables, all inspection and testing of raw materials, fabrication process and fabrication material, connections of all the types of ties, stiffeners, packing, diaphragm, HSFG. bolts, steel drifts, welding shop, rivets, templates, gigs, fixtures back up supports, accessories etc., and marking each member for site identification and transporting various components from contractor's fabrications yard/workshop to bridge site in packages bundles and other means with due care and safeguards, as described in the contract conditions and specifications and as directed/approved by engineer-in-charge including loading, unloading, sorting, member-wise systematic matching etc., complete with contractor's own labour, material, tools & plants including all lead, lift and taxes complete. 4. All works shall be carried out as per approved drawings, relevant codal provisions, technical specifications (corrected up to date) and as directed by the engineer-in-charge. 5. The girder components transported to the site shall be stacked at site properly as directed by engineer-in-charge and no extra payment will be made for the same. 6. The Price shall also include trial assembling in the shop yard or at site as directed by the engineer-in-charge, contractor has to arrange for laboratory testing of steel and submission of the results to the Bi-RIDE. no extra payment will be made for this. 7. The contractor has to engage 3rd party as a consultant/inspection (approved by RDSO or RITES or any other approved agency) for testing of the weld of the fabricated welded type girders, as required. 8. The price is inclusive of conducting of welding procedure specification sheet (WPSS) and procedure for qualification record (PQR) to qualify welder and welding procedures. 9. The price is inclusive of conducting laboratory tests on samples of steel materials and welds like physical and chemical tests as per IS respectively, as and when required. 10. The price is inclusive of conducting test on welds like Dye penetration test (DP), Magnetic particle test (MP) Ultrasonic test (UT) and Radiography test (RT) as required. 11. In case of Rolled steel section confirming to IS:2062 quality "B" or "C" are not available in market; Employer may permit use to steel confirming to IS 2062 quality "BR" on case-to-case basis by satisfying about non availability of quality "B" or "C". The metallization and painting are included in all steel superstructure.

Metalizing treatment of all steel surfaces shall be done by spraying aluminium having 99.5% purity with a coating of 150 microns by minimum 2 passes. 12. Painting of metalized steel sections shall be done as First coat- Primer to IS: 5666, Second coat- Zinc chromium paint to IS: 104 and Third & fourth coat- Aluminium paint to IS: 2339.

- iii. Performing load test on OPEN WEB GIRDER / BOW string girder / Composite girder as per design loading standard, including loading unloading the spans taking observation and all other activities and submission of results to engineer. The complete load test will be carried out as per scheme approved by Engineer. This test shall be conducted at the stage of commissioning of the bridge.
- iv. Construction of Abutments / piers, Pier caps / Bed blocks, bearings, as specified or as directed.
- v. Pile caps / Open Foundations (M35 Grade) resting at any depth depending upon the site condition shall include excavation, leveling course, PCC, dewatering, sheet piling / soldier piling & wooden lagging, if required, Backfilling complete in all respects.
- vi. Providing and laying M50 Grade reinforced cement concrete for precast PSC I-Girder, portal beams and pier-arm etc. (Post-Tensioned), simply supported standard / special spans of all types (straight or curved as per approved GAD), in the casting yard including provision of lifting the girders from the mould and shifting the same to the stacking yard

The Scope includes all infrastructure in the casting yard, gantry cranes, moulds, shuttering, casting beds, mobile cranes, stores, concrete batching plant, testing labs, bulk heads, approved curing arrangements as required, all handling etc. Teflon sheet at the end for placing on portal / arrangement for placing bearing as required and shown in drawing etc. Pre-stressing system (Strands, Anchorages, sheathing, vent pipe, etc.). The Scope shall include cost of lifting hooks and using required dosage of admixture in concrete for obtaining required workability as per approval of Engineer.

All the PSC precast I girders shall be checked for UPV (Ultra sonic pulse velocity) test by NABL Accredited Agency before dispatching from casting yard to site. Rates for the test are included in Scope.

- vii. Conducting Load Testing on I Girder as per IRC SP51, including making all arrangement and conducting satisfactory Load testing on simply supported span constructed by I Girder, erected in position on the piers at site. Arrangement for application of actual design serviceable vertical load of approx. 150 MT to 200 MT for I Girder spans or as directed by Engineer and arrangement for measurement of deflection at various salient points of the girder and submitting a report. The details of placement, position, increment of load on the simply supported span and installation of measurement devices etc. shall be as directed by the Engineer.
- viii. Providing and laying M35 grade concrete using 20mm maximum nominal size aggregates, reinforced cement concrete including the cost of cement, fine aggregates, coarse aggregates for Viaduct and all structures of all size, shape & heights for crash barrier, Median, entry structure columns, beam, plinth beam, staircase, lift walls, parapets, diaphragms, cross-girder, deck slab including centering, shuttering, propping, staging, scaffolding, curing, necessary tools, plants, machinery and all related operations etc. using steel shuttering & steel props

Form work to be designed in such a way that traffic on road / IR track is allowed during the work at all times. The Scope shall include cost of providing grooves, chamfers, moldings, cut-outs, necessary fixtures, insert plates, sleeves for various purposes, shear connectors etc. complete, specifications and as directed by the Engineer.

- ix. Providing and laying M35 grade using 20mm maximum nominal size aggregates grade reinforced cement concrete, using sacrificial shuttering for all heights in deck slab in between I girders in main span or obligatory span or any other locations including design of sacrificial shuttering along with method statement, design shall be approved by the Engineer. Supplying, fixing, positioning pre-embedded studs in concrete, structural decking panel (Sacrificial shuttering of approved make) with yield strength of 500 Mpa galvanized steel (min 275gms/sqm zinc coated) as per IS 277 or equivalent standard and all related operations. The structural decking panel shall have nominal effective cover width, nominal 51 mm deep ribs with a nominal 316 mm centre to centre with the embossment (shear Groove) on top and side of ribs for better composite action. Including the shear stud, universal beam, edge form, steel bracket, screws and fasteners, sealant, insulation, closures, edge angle, hoop iron and labour and machinery cost for erection and placing in position etc. complete as per the drawing and specification and as directed by the Engineer. Scope shall include cost of providing grooves, chamfers, moldings, cut-outs, necessary fixtures, insert plates, sleeves for various purposes, shear connectors etc. complete as per drawings, specifications and as directed by the Engineer.

The scope shall also include preparation of construction joints as per specification and providing approved wire mesh/weld mesh at such location as approved by Engineer or as shown in drawings. Scope shall also include using required dosage of admixture in concrete for obtaining required workability as per specification & approval of Engineer.

- x. Providing & laying Reinforced cement concrete M35 grade using 20mm maximum nominal size aggregates or as per approved design and drawing for pile foundations with socketing in weathered rock, soft rock, hard rock of any type and any depth if arising. The piling with temporary liners / permanent liners & socketing in soft rock / hard rock are included. The initial load test, routine load test, dynamic load test, lateral load test, pullout test, pile integrity test, cross hole sonic test, plate load test also to be conducted as per applicable IS code.

Scope also includes cutting / chipping of pile up to cut off level or up to good concrete and built up of pile up to required level. The scope also includes loading, unloading and disposal of surplus excavated material along with pile heads using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer. Contractor shall ensure that during transportation, the carried material does not spill out.
- xi. Supply and Installation of Elastomeric bearings based on detailed design including bearing pedestals, seismic restrainers, shear keys etc.
- xii. Expansion joint, sealant in the expansion joints as per concept plan as per specification.
- xiii. Manholes with manhole covers made of Cast Iron on the deck with locking arrangement as per the drawing.
- xiv. Earthing arrangement, drainage system, inserts for signaling masts in the parapets and other systems, as may be required.
- xv. Providing Retained soil/fill or Reinforced soil/fill in the approaches as per relevant code, design, drawings or as per instruction of Engineer.
- xvi. Designing, providing and erection of specified grade precast RCC fascia panels as per relevant code, design, drawings or as per instruction of Engineer.
- xvii. Providing, placing and compacting to desired density approved backfill material in layers as per approved methodology including testing for reinforced fill portion and random fill portion in the approaches between the Reinforced Soil (RS) wall panels as per approved drawings as per clause 3103 of MORTH specification. The soil should be predominately coarse grained, not more than 10% of particles should pass 75-micron sieve.
- xviii. Conducting all relevant tests on precast panels, soil reinforcements, soil used in backfill etc. as per relevant code, design, drawings or as per instruction of Engineer.
- xix. Pre-cast elements: Providing and laying M40 reinforced cement concrete using 20 mm graded aggregates or as per approved design and drawing for precast parapet, pre-cast drains, crash barriers etc., in the casting yard including provision of lifting the elements from the mould and shifting the same to the stacking yard.
 - a. The Scope includes all infrastructures in the casting yard, gantry cranes, moulds, shuttering, casting beds, mobile cranes, stores, concrete batching plant, testing labs, approved curing arrangements as required.
 - b. The Scope includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, required dosage of admixture for concrete.
 - c. The Scope shall be also inclusive of Loading, transporting precast elements from casting yard to work site, launching and erection in position using gantry or crane complete with cast in situ stitch concrete of same grade.
 - d. The Scope is inclusive of providing bolts & inserts for fixing hand rails.
 - e. The scope is also inclusive of providing Bi-RIDE logo in parapet.
- xx. Providing & laying Reinforced cement concrete M35 grade using 20mm maximum nominal size aggregates or as per approved design and drawing, Reinforced cement concrete using Portland slag cement (Directly from manufacturer or blending of OPC+GGBS for the following concrete works:
 - a. Open Foundation / stepped foundation / Raft, Combined Footing, Columns, Grade beam, monopile pedestals, U/G water tank and Structures of road widening works such as foundation, substructures and superstructures of culverts, retaining walls, RE Wall foundations, return walls, precast / cast-in-situ culvert deck slabs, road median, drains etc. including excavation for all depths from lowest ground level through

existing water bound macadam road / bituminous road / concrete road / soil / moorum / hard rock / soft rock old structures below ground as encountered of all thicknesses, dismantling other structures, dead utilities, dewatering, pumping and bailing out water, strutting and shoring, formwork, backfilling in foundation with good earth / quarry dust / sand watering, compacting with a vibratory plate compactor complete as per specifications.

- b. The Scope includes loading, unloading and disposal of surplus excavated material using covered trucks to contractor's dumping yard with all leads and lifts and as directed by the Engineer.
- c. The contractor shall ensure that during transportation, the carried material does not spill out.
- d. The scope shall include cost of using required dosage of admixture in concrete for obtaining required workability as per approval of Engineer, curing of concrete.
- xxi. Providing TMT-500D / 550D grade steel bar reinforcement (conforming to IS:1786, HYSD Fe 500 / 550 grade) at all heights & depth including straightening bars, cutting, bending, hooking binding with approved quality 18 gauge G.I binding wire, after placing in position tying, lapping and / or welding wherever required and anchoring to the adjoining members wherever necessary as per drawings (Laps, Hooks and Wastages shall not be measured and paid) including cost of all materials, bar bending charges, labour, lead & lifts etc., Complete as per specifications and as directed including welding involved towards stray current protection effects as per the system approved by Engineer.

As far as possible bars of the maximum length available shall be used. For bars having larger diameter more than 20mm mechanical couplers shall be provided as per Technical Specifications and no lap shall be permitted. Welding in lieu is not permitted unless specified in the drawings or as instructed by the Engineer. Lap joints are permitted wherever required. However, mechanical couplers in place of lap joints may be permitted by the Employer without any extra payment, with the specific approval of Employer/Engineer for the specific elements / members / works / locations on case-to-case basis.

For pile reinforcement, welding of lap joint is allowed.

The scope includes all welding and providing mechanical couplers, all types of laps, standard laps, spacer bar, U-bar, chair, bend deduction as required and nothing extra is payable on this account. Anti-corrosive treatment / paints exposed steel surfaces and all other related operations as required to complete the work as per specifications.

- xxii. Supplying of uncoated stress-relieved low relaxation steel strands conforming to IS: 14268 (class-II), for pre-tensioning of I-girders (PSC I girders) (simply supported spans) including spacers, stressing of strands, protection of exposed cut-strands, anti-corrosive paints, HDPE debonding tubes at ends of strands if required, and all related operations.
- HDPE debonding tubes for prestressing strands (to be cut off flush to concrete after casting), epoxy-based sealing compound at edges of strand and epoxy putty to avoid slurry ingress during concreting. The quantity given is the net length of tubes without extra tube length required during construction. Scope includes filling HDPE debonding tubes with grease as specified in ASTM.

- xxiii. Levelling Course: Providing & laying plain cement concrete M15 / M20 grade using 20mm maximum nominal size aggregates in pile foundation, open foundation, stepped foundation, combined footing, raft foundation, retaining walls, return walls, walls, U / G water tank, culverts, drains, slab on grade, tie beams, basements, levelling course or any other works as directed by the Engineer, etc. rate is inclusive of required dosage of admixture in concrete for obtaining required workability and as per specifications, approved drawings, laid in layers not exceeding 15 cm thick layers, as per drawing including cost of all material, form work / shuttering, dewatering during concreting, vibrating, compacting, curing, hire charges of machinery, all lead and lift, loading, unloading, transporting, stacking, finishing the exposed faces etc., complete.

Skin reinforcement, if necessary, shall be provided

- xxiv. Providing Boulder backing behind abutment, wing wall, return wall, retaining wall with hand packed boulders & cobbles with smaller size boulders toward the back including all lead, lift, labour & other incidental charges as complete work in all respects.
- xxv. Providing and laying of filter media consisting of granular materials of GW, GP, SW groups as per the approved specification in required profile behind Slab bridges, RCC boxes, Abutments, wing walls / return walls etc., above bed level with all labour and material complete job as per drawing and technical specification of RDSO.

- xxvi. Drilling holes up to required diameter or 32 mm diameter, providing Weep Holes in stone masonry / Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm AC pipe extending through the full width of the structure with slope of 1V:20H towards drawing force.
- xxvii. Design, manufacture, supply & installation of the approved expansion joint (Omega Seal) at the site at formation level under the supervision of manufacturer's representative as per specification and expected movement (25 to 50 mm) as mentioned in relevant drawings.
- xxviii. Design, manufacture, supply & installation of the approved expansion joint (Strip Seal) at the site at formation level under the supervision of manufacturer's representative as per specification and expected movement (25 to 50 mm) as mentioned in relevant drawings (wherever required).
- xxix. Supply and fixing in position true in line & level, Elastomeric bearings of approved make, placing and fixing in location as per specification and as directed by the engineer.
- xxx. Supplying to site and placing of POT/PTFE Cum Bearings / spherical bearings (Free POT bearing, Fixed POT bearing, Longitudinal guide POT bearing and Transverse guide POT bearings) and its components in position during casting of pier / pedestal and superstructure, including, grouting of holes for anchor bolts and underside of base plate with approved non-shrink cementitious grout as per specification. The forces and movements are as per the design.
- xxxi. Providing and fixing G.I. brackets with suitable covering arrangement at required locations for electric cables & Signaling and Telecom cables as per tender drawing.
- xxxii. Fabrication & Supply of drainage spout hot dip galvanized of dimension 300mmx180mm with MS Flat 50mmx6mmx100mm long with gratings of MS Flat 25mmx6mm with spacing of 50mm c / c and MS pipe 122mm dia. verticals as per drawing including installation of the spout with all tools, plants, leads and lifts and in position in complete and as directed by the Engineer.
- xxxiii. Preparation of temporary Arrangement Drawings (TAD), Launching Scheme, Fabrication/Detailed Shop Drawings including drawing office dispatch lists (DODL), and other documentation as required by Engineer.
- xxxiv. Preparation of Quality Assurance Plan (QAP) for super-structure including bearings.
- xxxv. Provision of integrated drainage system for RUB which includes cross drains, catch water drains at approaches with grating arrangements before hump, side drains, soak pit/collection well/injection well, etc. as per relevant IR Code or as per the relevant IR instructions.
- xxxvi. Pre-cast Segments for RCC Box: Providing and laying M35 reinforced cement concrete using 20 mm graded aggregates or as per approved design and drawing for RCC BOX segment for RUB in the casting yard including provision of lifting the elements from the mould and shifting the same to the stacking yard.
 - a. The Scope includes all infrastructures in the casting yard, gantry cranes, moulds, shuttering, casting beds, mobile cranes, stores, concrete batching plant, testing labs, approved curing arrangements as required.
 - b. The Scope includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, required dosage of admixture for concrete.
 - c. The Scope shall be also inclusive of Loading, transporting precast elements from casting yard to work site, launching and erection in position using gantry or crane complete with cast in situ stitch concrete of same grade.
- xxxvii. Transportation of pre-cast box segments from casting yard to the site launching and erection in position. Loading, transporting precast segments from casting yard to work site, launching and erection in position with launching girder, including erection and shifting of launching girder (Min. two No of launching girders to be mobilized), temporary supports, launching girders, erection equipment's, transporting etc., applying epoxy based bounding agent on end surface of segments after dry matching including temporary prestressing required during its curing period and positioning on bearings etc. This shall be operated for any type of launching scheme adopted.
- xxxviii. The Standard Drawings of box culverts (25 MT loading) of RDSO for minor bridges may be referred and the tentative spans are given in the minor bridges list. The standard drawings of RDSO for major bridges & ROB may be referred. The standard RUB Drawings (Segmental Construction) as per IRS/RDSO may be referred,.
- xxxix. RE Wall for ROB: Casting and laying in position M40 grade pre cast concrete facia panel / pre cast CC blocks with architectural finish of suitable size and thickness as per approved drawing but not less than minimum 180mm thick excluding architectural finishes and including (Earth work excavation for foundation.

providing initial levelling pad (minimum 150mm thick and having suitable width) as necessary, using M15 grade plain cement concrete. Necessary connection arrangements for soil reinforcement necessary coping beam, neoprene sponge joint material between reinforced soil wall fascia and crash barriers, the backfill material and the drainage material shall be separated using permeable non-woven geotextile or synthetic geo grid and approved design, necessary anchor rods at the toe of wall for laying first pre cast CC blocks. Including all materials, labour, lead and lift, hire charges of all plants, machinery, lead lifts, loading, unloading etc., complete as per MORTH specifications and as directed by Engineer-in-charge..

- xl. Retaining wall: Supplying and providing well graded crushed aggregate as drainage bay backing along the retaining wall including supplying and providing perforated drainage pipes connecting to the nearby drain including compaction of the filled material at a specified layer thickness as per MORTH specifications and as directed by Engineer-in-charge.
- xli. For ROB: Filling coarse grained soil/earth in embankment for road approach as per approved reinforcement earth technology behind the precast fascia panels with contractors supply of back fill materials which shall be free from organic or other deleterious materials and shall conform to the mechanical and physio chemical requirements including mechanical compaction as per MORTH specifications and as directed by Engineer-in-charge.
- xlii. For ROB: Supplying Assembling joining and laying of soil reinforcing elements connecting with precast modular blocks, including connecting arrangements, all materials, labour, lead and lift. hire charges of machinery, complete. complying MORTH specifications and as directed by Engineer-in-charge.

B. Road Works and other allied works.

- i. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross section, and transportation with all & lift lead complete as per specifications, including scarifying the existing bituminous.
- ii. Construction of embankment for road work with approved materials gravel / Moorum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement complete as per specification, including cost of gravel / moorum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No.305.
- iii. Construction of sub grade and earthen shoulder with approved material Gravel / Moorum with all lifts & lead, transporting to site, Spreading, grading to required slope and compacted to meet requirement of table No.300-2 complete as per specification, including cost of earth, watering charges & compaction by vibratory roller to 97% of modified proctors density MORTH Specification No.305 including compaction.
- iv. Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite / trap / basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V revision.
- v. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to Wet Mix Macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base / base course on well-prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications, MORTH specification No.406.
- vi. Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications.
- vii. Providing and applying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60kg per sqm using mechanical means complete as per specifications. Clause 502 of MORTH V revision.
- viii. Providing and laying bitumen mastic wearing course (as per specifications) with industrial bitumen of grade 85/25 conforming to IS : 702, prepared by using mastic cooker and laid to required level and slope, including providing antiskid surface with bitumen precoated fine grained hard stone chipping of approved size at the rate of 0.005 cum per 10 sqm and at approximate spacing of 10 cm center to center in both directions, pressed into surface protruding 1 mm to 4 mm over mastic surface, including cleaning the surface, removal of debris etc. all complete. (Considering bitumen using 10.2% as per MORTH specification).

- ix. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 505 of MORTH V revision. Using 40 / 60 TPH capacity H.M.P with sensor paver Gr-II with 4.5% VG-30 Bitumen.
- x. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects as per specifications. Clause 507 of MORTH V revision. Using 40 / 60 TPH capacity H.M.P with sensor paver Gr-II with 5.5% VG-30 Bitumen and lime filler @ 3% (percentage by weight of Aggregate).
- xi. Construction of Junction arrangements with cross roads as per the site condition.
- xii. Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface / Concrete Surface. Painting lines, dashes, arrows etc., on roads in two coats on new work with ready mixed road marking paint conforming to IS: 164 on bituminous surface.
- xiii. Painting two coats on new concrete surfaces: Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces including cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete as per specification.
- xiv. Road delineators: Supplying and installation of delineators (Roadway indicators, hazard markers, object markers), 80-100cm high above ground level, painted black and white in 15cm wide strips, fitted with 80x100mm rectangular or 75mm circular reflectorized panels at the top, buried or pressed into the ground and conforming to IRC-79 as per drawings including cost of all materials, labour, loading, unloading, lead, lift, transporting, etc., complete as per specification.
- xv. Supplying and fixing pre cast solid concrete kerb stones made out of M15 / 20 (CC 1:2:4) and finished with CM 1:3 Plastering and finishing, cutting, with all lead and lifts etc., complete of size 450 x 200x 400mm.
- xvi. Supplying and laying interlocking pre-cast CC block pavers of approved design factory manufactured of specified grade cement concrete on foot paths, circulating area, road junctions etc, including setting in position over 25mm thick bedding layer of fine sand, filling the joints with fine sand, levelling including compaction as per IS 15658, minimum of 80mm thick blocks of M35 grade for medium traffic.
- xvii. Supplying and fixing precast RCC gratings including cost of all materials, transportation, labour etc. complete (60x40 cm) with all lead and lifts.
- xviii. Providing and fixing railing used in rows for footpath or anti-crash barrier railing.
- xix. Providing & laying non pressure RCC pipe as per the requirement
- xx. Temporary road diversion works are in the scope of Alignment contract, however if need arises, the contractor under this contract will be required to construct alternate road for diversion of current traffic passing the LC. Maintenance of the alternate road will be in the scope of the contractor until opening of ROB or handing over of road to the concerned authority for public use. The payment for this work will be made under relevant Schedule based on latest KPWD SOR.
- xxi. All temporary traffic diversion works, which will be required for the smooth flow of running traffic in order to carry out the works without any interruption including all safety precautions, signage, barricading, emergency lighting, traffic marshals, look-out men / watchmen etc.; shall be carried out. The permanent traffic diversions shall be carried out in consultation with traffic police. Contractor has to provide traffic diversion proposals, traffic marshals, cones, traffic diversion boards etc., as desired by Traffic Police. The text for painting will be approved by Engineer.
- xxii. The Contractor shall make the detailed traffic diversion plans in consultation with Bengaluru Traffic Police. The work is to be executed with proper liaison with Bengaluru Traffic Police. Necessary assistance will be given by Bi-RIDE. The scheme should be such that minimum of two lane of traffic on each direction of the road should be available for the smooth flow of traffic. The Contractor should inspect the site.
- xxiii. The contractor has to get necessary permission/ NOC from the railway, road, police and other concerned regulatory authorities for blocking services and working in such locations. Bi-RIDE will Facilitate for getting them permission from concerned regulatory authorities for working in such locations.

- xxiv. Road works and allied works to be carried out in co-ordination with GBA/BBMP/Zilla Panchayath/PWD etc as per MORTH, NH specification or applicable specifications. Contractor may also take up development or extension of culverts or construction of new culverts along the alternate road, if necessary, as directed by Engineer.
- xxv. Portable barricades in construction Zone: Installation of steel portable barricade with horizontal rail 300mm wide, 2.5m in length fitted on a 'A' frame made with 45x45x5mm angle iron section, 1.5m in height, horizontal rail painted (2 coats) with yellow and white stripes, 150mm in width at an angle of 45 degree, 'A' frame painted with two coats of yellow paint, complete as per IRC: SP:55-2001 including cost of all materials, labour, loading, lead, lift, transporting etc., complete as per specification.
- xxvi. Traffic cones: Supplying of red fluorescent with white reflective sleeve traffic cones made of low-density polyethylene (LDPE) material with a square base of 390x390x35mm and a height of 770mm, 4Kg in weight, placed at 1.5m interval all as per BS-873 including cost of all material, labour, loading, unloading, lead, lift, transporting, etc., complete.
- xxvii. Retro-Reflectorized Road traffic signs: Supplying and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC: 67- 2001 made of high intensity grade micro prismatic HIP type-IV sheeting, including lettering fixed over aluminum sheeting, 2 mm thick firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing.
- xxviii. Retro-reflective board - Caution Indicator / Stop indicator / Speed indicator / Whistle Board / any other board with 1.50 mm thick MS plate and MS plate stiffeners on M.S. T angles 75 mm x 75 mm x 6 mm and 4.75 m long approximately as per the specified drawing including cutting, drilling holes in the angles, providing hold fasts, bolts and nuts with washers of required size, bolting, welding.
- xxix. Filling pot holes and patch repairs with bituminous concrete.
- xxx. The Contractor has to ensure cleanliness of the roads and footpaths by deploying man power for the same. The Contractor shall have to ensure proper brooming, cleaning and washing of roads and footpaths at regular intervals or as and when required or directed throughout the entire stretch till the currency of the contract including disposal of sewage. Regular interval implies that Roads and Foot-paths should be maintained in clean condition throughout. Nothing extra shall be payable on this account.
- xxxi. Day to day cleaning of worksite throughout the execution period.
- xxxii. Clearing of site and handing over of all the Works, as specified or as directed.
- xxxiii. Maintenance of the completed Work during the period as specified. Contractor has to do maintenance during the defect liability period. If any damage occur due to third party, then liability will not remain with the tenderer of this work.

C. Initial site Preparatory works

- i. Before carrying out the work at site, necessary permissions from local agencies / authorities / road authorities / railway authorities such as GBA/BBMP, Zilla Panchayat, PWD, BWSSB, BESCOM, GAIL, KPTCL, traffic police etc., shall be required to be obtained by the contractor. Employer will assist only by the way of issue of necessary letters.
- ii. Any work affected by the construction must be temporarily supported by the contractor. The work of temporarily supporting the utilities and services during the execution of works shall be deemed to be part of the contract.
- iii. The contractor shall take all precautions for safe guarding the environment during the course of construction works. He shall abide by all laws, rules and regulations in force governing pollution and environmental protection that are applicable in the area where the works are situated. The contractor must take all necessary steps to fix specially dust nuisance during the construction of the works.
- iv. The levels, measurements and other information concerning the existing site as shown on drawings are believed to be correct, but the contractor should verify them for himself and also examine the nature of the ground as no claim or allowance whatsoever will be entertained on account of any error or omission in the levels or strata turning out different during execution from what is shown in the drawings.
- v. The contractor shall at all time carryout the work on highway/road/service road/railways tracks in a manner creating least interference to the flow of traffic or train operations. The contractor shall take prior approval of

Engineer, traffic police, GBA/BBMP/ZP/PWD, Railways, traffic police etc., for approval of traffic diversion plan during construction works.

- vi. Site to be cleared of any obstruction along the ROB/RUB works.
- vii. Tree cutting, preservation and disposal (or) translocation along the alignment for cutting / disposal / Translocation / afforestation in lieu of cutting / Translocation.
- viii. Demolition of RCC framed structures, Brick masonry buildings including basement etc. as existing at site without making damage to adjacent structures, utilities and taking away and disposing all the debris and released materials etc.
- ix. Conducting survey and fixing bench marks and alignment markers.
- x. Necessary permanent / temporary diversion of Utilities.
- xi. Temporary barricading wherever required.
- xii. Deployment of adequate manpower (Traffic marshals and watchmen) for management of traffic at intersection, junctions, traffic diversions etc.
- xiii. Demolition / dismantling of road, footpath, kerb stone, central verge, boundary wall, etc.
- xiv. Surveying by establishing DGPS control points and TBMs, True and proper setting out and layout of the works marking of alignment and pier locations, vertical & horizontal clearances for the elevated section including modifications, if any, as per drawings

No extra amount will be paid to re-do or to re-establish any of the survey points. The control points shall be fixed using DGPS double frequency and the accuracy of 1 in 50,000 or better shall be assured.

- xv. Providing temporary barricade as per the approved drawing, painting (including primer of approved quality) with synthetic enamel paint of approved colour, quality and brand, painting letters and logo of Bi-RIDE, including maintenance of the same duly cleaning the same on fortnightly basis and immediately repainting whenever required, arrangement for blinker lights on barricades during night as per requirement and as per the instruction of the Engineer.

Barricading should be rugged and fixed / anchored in ground firmly during the construction. It shall be maintained in position till completion of all works at the relevant location. Nothing extra will be paid for dismantling and re-erecting the barricades at a different location. The barricades shall be relocated as the work progresses and as directed by the Engineer.

- xvi. Supply of caution watchmen at locations where caution orders is imposed and at all work sites near the IR track at the rate of one caution watchman per 8 hours shift round the clock with necessary three cell electrical torch, banner flags, hand flags etc. for continuous vigil and to exhibit necessary signals to the trains for their safe passage over the caution spot as directed by the Engineer in charge.
- xvii. Felling of trees of girth as directed (measured at a height of 1m above ground level) with lead and stacking of material including preservation.
- xviii. Tree cutting, preservation and disposal (or) Translocation along the alignment for cutting/disposal/translocation/afforestation (as per the norms of Forest Department) in lieu of cutting/translocation

The applicable permits/ permissions for felling of trees / Translocation shall be arranged by Employer. The tree cutting and disposal is included in the scope of work. Payment for cutting/translocation will be made under relevant BOQ item. The cut trees will be the property of the contractor. However, the contractor shall deposit an amount not less than Reserve Price of the trees (as fixed by Forest Department/ BBMP) plus FDT (Forest Development Tax) to Bi-RIDE for onward transmission to Railways/BBMP/Forest Department, as the case may be.

- xix. Transportation for disposal of tree trunks, branches, roots, complete including loading and unloading as per BBMP / Forest and local authority guidelines.
- xx. Preparation of earth ball of tree roots of desired depth & diameters including necessary soil tests
- xxi. Dislodging, lifting, transportation and translocation tree from original place to the new place including all arrangements, labour etc. for successfully completing the work.

- xxii. Transportation of all usable materials like B.S slabs / precast RCC slab, cement concrete blocks, interlocking paver blocks, kerb stones, steel items, Telephone Poles. Electric Poles to designated site as directed by Engineer by mechanical transportation including all lift, lead, loading, unloading, labour, machinery etc.
- xxiii. Diagonal Cross trenching works for identifying underground Utility at every Pier location, ROB, RUB, Retaining Wall location, sacrificial wall etc., to the required length, width and depth, which includes excavation in all types of soil, hard soil, rock, footpath, bitumen road, concrete road, medians etc. cutting of all types road surfaces and backfilling the same with available excavated earth.

The scope also includes surveying and taking coordinates of the existing Utility and submitting the reports (hard & soft copy) of the same as per the directions of the Engineer.
- xxiv. Dismantling of existing structures after ensuring necessary approval from the competent authority of the concerned department. The structures like culverts, bridges, buildings, retaining walls, Railway Platforms, Compound walls and other structure comprising of masonry, cement concrete, pre-stressed / reinforced cement concrete, brick / tile work in cement mortar, stone masonry rubble in cement mortar, stone pitching / dry stones spalls, removal of all types of Hume pipes, cement concrete pavements, kerb stones, BS slab / precast slabs of drain / footpath, paver blocks of footpaths, removal of silt or silt mixed with sand, etc. including T&P and scaffolding wherever necessary, including disposal of dismantled material with all lead and lifts including all labour, hire charges all machineries etc., complete by any mechanical means or any other means as direct by Engineer. Loading / Unloading G.I. sheets, rails, joists, built up sections, angles, C.I., Ductile pipes, A.C Pipes, or G.I. pipes RCC / PCC beams / slabs and other miscellaneous ironwork or wood work.
- xxv. The scrap materials will be the property of the contractor except the materials of local authorities (GBA/BBMP, BWSSB, BESCOM, BSNL) and Railways.
- xxvi. Any other item of work as may be required to be carried out for completing the construction of ROB/RUB structures as specified in drawings including all necessary interface works with infrastructure contractors, system contractors, etc. in all respects in accordance with the provisions of the Contract and / or to ensure the structural stability and safety during and after construction.
- xxvii. Casting Yard: The land for setting up one numbers of casting yard and stacking yard as required shall be arranged by the Contractor at his own cost. However, assistance can be provided by Bi-RIDE by giving recommendatory letters etc., to the concerned authorities. The desirable area for each casting yard shall be as per the requirement and shall be decided by the Bi-RIDE after recommendation by Engineer. No land for casting yard or offices/laboratories etc., will be provided by the employer.
- xxviii. The contractor shall carry out
 - a. Setting up of fully fledged site laboratory as per the requirements.
 - b. Setting up concrete batching & mixing plant.
 - c. Contractor's site office setup.
 - d. Casting yard with complete facilities
- xxix. Construction & maintenance (till the end of DLP) of at least 1 (One) nos. of Project Offices (earmarked for Employer & Engineer separately) at the Site/casting yards as given below
 - a. The area of each Project / Site office will be as approved by Employer within the overall limit of area mentioned in Appendix-VI, read in conjunction with clause 1.3 for additional offices.
 - b. Project offices: The locations of the Project Offices shall be approved by the Employer. The work of providing the above project offices for Employer and the Engineer shall be commenced in the right earnest and at the earliest, but not later than 15 (Fifteen) days from the date of issue of LOA. All the project offices shall be made fully functional with doors and windows, proper layout design (approved by Employer) with all furniture, equipment, appliances, seating arrangement, computers, printers, personnel, high speed broadband internet and Wi-Fi routers, etc. (as mentioned in the Employer's requirement) within 60 (Sixty) days from the date of issue of LOA. Any delay in providing the office will attract penalty as decided by Engineer and Employer.
 - c. Deleted.
 - d. The area, locations, layouts, designs, disposition of doors and windows, other technical requirements, furniture, computers & printers, appliances, seating arrangement, materials of doors & windows, landline

internet connections, WIFI routers etc., of project offices & site offices shall be as per the requirement of Employer and the Engineer & as decided and approved by Employer.

- e. The specifications, equipment and other requirements of Project offices & Site offices are given in detail in Appendix-VI.

NOTE: All the requirements of offices, furnishings, equipment, appliances, tools, maintenance standards, personnel – including their qualifications and expertise, are designed for effective execution and close monitoring of the progress and quality of work. The tenderer shall note that all the conditions will be enforced in letter and spirit.

- xxx. The Contractor shall implement a Project Quality Management Plan in accordance with ISO-9001 “Quality System – Model for Quality Assurance in Design of temporary work/Development, Production, Installation and Servicing” or any other system as approved by Engineer to ensure that all materials, workmanship, plant and equipment supplied and work done under the contract meets the requirements of the contract.
- xxxi. The Contractor shall provide the Key Personnel as per Appendix-IV.
- xxxii. The Contractor shall provide the Key Plant and Equipment's as per Appendix-V.
- xxxiii. Wherever night working is carried out by Contractor, temporary lighting arrangements as per approved layout shall be provided, installed, maintained for the duration of the contract.
- xxxiv. The contractor shall at all-time carryout the work on either side of existing IR tracks/ highway/road/service road in a manner creating least interference to the flow of traffic. The contractor shall take prior approval of the Engineer and traffic police regarding traffic arrangements and diversion of traffic during construction.
- xxxv. The contractor shall take suitable and sufficient measures as per SHE manual for working at height.

2. RELEVANT DOCUMENTS

The Preliminary Design / Definitive Design for all temporary structures shall also be submitted by Contractor for Engineer's Approval.

Engineer shall issue Good for Construction (GFC) drawings to Contractor for the execution of works in accordance with the agreed terms and conditions of the Contract Agreement.

The following Documents shall be referred in conjunction with each other by the Contractor for construction work as these are mutually complimentary to each other:

- a) Good for Construction Drawings will be issued by the Engineer with the approval of Employer
- b) Employer's Requirements
- c) Instructions
- d) Technical Specifications and explanatory notes
- e) Contract Conditions
- f) Particular Conditions of Contract
- g) Price Schedule
- h) Indian and International Standards referenced in the bid document
- i) The schedules and any other documents forming part of the Contract
- j) Any other related section in the bid document

The Contractor shall always seek advice from the Engineer in the event of conflicts among above cited documents. In case of conflict, Engineer's decision shall be final and binding.

3. GENERAL

The project site is located in and around Bengaluru City. The tendered work is BSTP project along Corridor-4 of Suburban Rail Project between Heelalige and Benniganahalli.

The scope of work includes construction of 4nos of Road over bridge (ROB) and 1nos of Road under bridge (RUB) along Corridor-4 of Suburban Rail Project between Heelalige and Benniganahalli.

Availability of Land:

The major portion of the required land for the execution of works is available along the alignment. The remaining land or portion of land shall be acquired and handed over to the contractor progressively. However, the contractor may have to take lease of the land temporarily for installation of his facilities like batching plant/ Casting Yard/ Site Work Shop etc. The bidders are advised to make detailed study and cater for such expenditure in the bid.

Approaches to the project site:

The land acquired for the project caters for construction and operation of the proposed line. Project site is located along the existing GBA/BBMP/ZP/PWD roads. The contractor shall conduct detailed survey and should include the cost of inputs for any such approach roads in his bid for the work.

However, in case any existing road has to be utilized for transportation of materials to the site of work and in the process the road gets damaged or needs to be strengthened and the authority owning the said road submits demand to Employer to carry out some specific works in order to strengthen/repair the road, Employer shall get such works executed through the existing contractor.

Bidders should find out the capacity of the quarries and accordingly plan procurement of course/fine aggregates either from the existing quarries or establish their own quarries and crushing arrangements.

It is the responsibility of the contractor to thoroughly examine the site of work and all constraints before submitting the bid(s).

- i. Before carrying out the work at site, necessary permissions from various local agencies / Railway authorities / road authorities such as SWR, GBA/BBMP, PWD, Traffic Police etc., shall be required to be obtained by the contractor. The Employer shall assist only by way of issue of necessary support letters.
- ii. Any services affected by the works must be temporarily supported by the contractor. The work of temporarily supporting and protecting the public utility, services during execution of the works shall be deemed to be part of the contract and the amounts are included in rates quoted. Nothing extra shall be payable on this account.
- iii. The contractor shall take all precautions for safeguarding the environment during the course of the construction of the works. He shall abide by all laws, rules and regulations in force governing pollution and environmental protection that are applicable in the area where the works are situated. The contractor must take all necessary steps to fix specially dust nuisance during the construction of the works.
- iv. The levels, measurements and other information concerning the existing site as shown on the drawings are believed to be correct and indicative, but the contractor should verify them for himself and also examine the nature of the ground as no claim or allowance whatsoever will be entertained on account of any error or omission in the levels or strata turning out different during execution from what is shown on the drawings. The contractor should validate the L- Section and horizontal alignment using MX Rail/ applicable latest software.
- v. The present position of preliminary works of the section is as below; any incidental works required to be carried out in this regard shall be the responsibility of the contractor and the amounts are included in rates quoted. Nothing extra shall be payable on this account. In case any new items are required for such works, the same will be processed as per the need on mutual consent.
 - a. The existing road of GBA/BBMP / Road approach of Railway can be used for construction of viaduct structures, at-grade section etc.
 - b. Utilities pertaining to Existing IR track, GBA/BBMP, BWSSB, GAIL, BESCO and other private (OFC) have been identified and indicative.
- vi. The preliminary works such as site clearance, barricading, trail trenching etc., wherever required, shall be taken up simultaneously along with mobilization activities.
- vii. Trenching for identification of utilities and re-location / diversion of utilities if encountered;
- viii. The contractor shall at all-time carryout the work on either side of existing IR tracks/ highway/road/service road in a manner creating least interference to the flow of traffic. The contractor shall take prior approval of the Engineer and traffic police regarding traffic arrangements and diversion of traffic during construction.
- ix. All temporary traffic diversion works, which will be required for the smooth flow of running traffic in order to carry out the works without any interruption including all safety precautions, signage, barricading, emergency lighting, traffic marshals, look-out men / watchmen etc.; shall be carried out.

- x. The permanent traffic diversions shall be carried out in consultation with traffic police. Contractor has to provide traffic diversion proposals, traffic marshals, cones, traffic diversion boards etc., as desired by Traffic Police.
- xi. Works to be performed shall also include all general works, including Road widening and allied works of any kind necessary for the due and satisfactory construction, completion and maintenance of the works to the intent and meaning of the drawings adopted and technical specifications, to best Engineering standards and orders that may be issued by the Engineer from time to time.
- xii. The road works and allied works shall be carried out in co-ordination with BBMP as per MoRTH, specifications. On award of work, the contractor has to start the road work along and complete the same.
- xiii. Road widening works wherever required. Further, if diversions of roads need any up gradation as desired by the Engineer contractor will carry out the works and will be paid under the relevant Price Schedule. Road widening and drainage work to be completed before the commencement of viaduct /at-grade section work at any particular location.
- xiv. Restoration of Road and allied works immediately after completion of work up to road level or as per instructions of Engineer.
- xv. Tree cutting and (or) transplanted along the alignment for cutting/transplantation will be arranged by Contractor at her/his own cost. The applicable permits/ permissions for felling of trees / transplantation shall be arranged by Employer.
- xvi. Demolition of RCC framed structures, Brick masonry buildings including basement etc. as existing at site without making damage to adjacent structures, utilities and taking away and disposing all the debris and released materials etc. Shall be done by contractor, the amount of the are included in the rate quoted.
- xvii. All disposable excavated material shall be collected and transported for disposal at contractors dumping yard which has to be approved by relevant authorities. Dumping yard area cannot be provided by the employer.
- xviii. The tyres of the vehicles leaving Site have to be cleaned with Jet Wash to avoid spillage of earth / mud on public roads. The Contractor has to ensure cleanliness of the roads and footpaths by deploying man power for the same. The Contractor shall have to ensure proper cleaning and washing of roads and footpaths on all the times throughout the entire stretch till the currency of the contract including disposal of sweep age. Nothing extra shall be payable on this account.
- xix. The CONSTRUCTION PROGRAMME AND PROJECT MONITORING is to be given as mentioned in General Conditions of Contract. The detailed programme has to be in the form of a quantified bar chart or MSP / Primavera activities from start to completion of the work.
- xx. PROJECT MANAGEMENT INFORMATION SYSTEM (PMIS) The Contractor shall utilise a PMIS integrating with BIM software such that all documents generated by the Contractor can be transmitted to the Engineer by electronic means (and vice versa) and that all documents generated by either party are electronically captured at the point of origin and can be reproduced later, electronically and in hard copy. A similar link shall also be provided between the Engineer office at site and the Employer's Office by the Contractor.
- xxi. Maintaining and keeping the Existing Railway banks, structures and adjacent roads clean in the area of work and where construction machineries ply.
- xxii. Measures to minimize water, air and noise pollution;
- xxiii. All aspects of quality assurance, including testing of materials and other components of the work, as specified and as directed;
- xxiv. Clearing of site and handing over of all the Works, as specified or as directed
- xxv. Maintenance of the completed Work during the maintenance period as directed;
- xxvi. Submission of completion (i.e., 'As-Built') drawings and other related documents as specified; and
- xxvii. The contractor shall not display any name-board for the works without the written permission of the engineer.
- xxviii. No labor camp shall be allowed at work site or any unauthorized place.

4. OBTAINING CLEARANCES/CERTIFICATES FROM AUTHORITIES

The contractor shall arrange well in advance stage wise as may be required, submission of all the required documents and drawings for approval from other authorities and installation of the works and their inspection and obtain approval/completion certificates with respect to his work as required for use and connection of the utilities and occupation from the Statutory Authorities. The Contractor shall obtain and deliver to the Engineer, on completion of the works, the final Inspection Report and approval from the Authorities.

5. INTER COMMUNICATION FACILITIES

Telephone and fax services are available at Bengaluru. Should the Contractor wish to use Radio communication on the site, the Employer will recommend to the appropriate authority the application for allocation of radio frequencies to the Contractor.

6. SITE INFORMATION

The project site is located in and around Bengaluru City. Bengaluru is well connected to other parts of the country by Road, Rail and Air. It has an international Airport. The location of the work and the General site particulars are shown in the General Arrangement Drawings enclosed in the bid documents.

7. RESTRICTIONS IN WORKING

It has to be noted by the Bidder that

- a) The various items of construction work have to be carried out in narrow roads / streets of Bengaluru city/Beside/across/Parallel to the existing railway line where there are buildings adjacent to the road/track and railway traffic may be heavy. b. There are restrictions for movement of trucks and heavy vehicles (ex: trailers) carrying construction materials, cleaning during the day hours on some roads.
- b) There are some one-way roads where traffic can't move in both directions.
- c) Generally, at least two lanes of traffic in both directions have to be kept while the works are on, including foundation works.
- d) The construction of structures will have to be planned in such a manner that they do not obstruct or interfere with the existing roads; railways tracks and other utilities. Since the entire Alignment is coming in parallel to the existing IR track/ road, the movement of trains/Heavy Vehicles is expected, wherever the stations / approaches to the stations / Viaduct works are at the middle/Beside of the IR Track/road / across the railway tracks/roads, erection of pre-cast members may have to be planned in such a way that the erection shall be done from one end with Back feeding. Unless the competent authorities permit to execute such works using cranes and restricting the movement of the Vehicles/trains, the same may be planned to carry out during night Also, while working in the night hours' noise pollution should be kept to an acceptable level. The bidder should take all these facts into account while quoting rates and devise his methodology of working accordingly.
- e) Where work is required to be carried out at locations adjacent to such Existing IR tracks, roads, utilities, structures, monuments, religious structures, etc., suitable safety and protection arrangements will have to be ensured. Nothing extra will be payable on these accounts. It should also be ensured that no damage is caused to any such element and Engineer/ Employer shall be indemnified against such damage at no extra cost.

8. GENERAL CLIMATIC CONDITIONS

Bengaluru is located in meridians of 12° N latitude and 77°3' E Longitude, spread over an area of 531 sqm km. located at an altitude of 900m, Bengaluru boasts of delightful weather around the year registering maximum temperature of 34° centigrade in summer and minimum temperature of 14° centigrade in winter. Bengaluru receives both the Southwest and Northeast Monsoons, getting an annual average rainfall of 760 mm, generally during the months of May to September/October. Bengaluru falls in Seismic Zone II.

9. DAMAGE TO PROPERTY

The contractor shall organize all his activities so as not to cause any damage to the property of Railway or that of other agencies or any third party. In spite of taking all precautions, in the unfortunate event of any damage to the property, then the contractor shall not only indemnify the Employer of the claims made by the affected parties but also settle the matters with the affected parties as per law. If the nature of damage is one of that affecting the train movements or causing a safety hazard to the public, then the situation will be treated as an emergency and the Engineer reserves the right to take all necessary steps as deemed necessary to restore train operations or to remove the hazardous situation or to mitigate the damage, at the risk and cost of the contractor.

9.1 Survey Equipment

The contractor should provide the survey equipment and other accessories as per the instructions of Engineer as and when required. He should also provide all necessary help as required by the Engineer for checking the works, whenever required.

9.2 All power requirements for execution of works shall be arranged by the Contractor from his own resources. Subject to availability of power, the Employer/Engineer will recommend to the Railway Authorities for providing power connection. The Contractor shall bear the cost of installation and payment of necessary charges for providing such power connections as per the Terms and Conditions of the Railway.

9.3 Structural elements, shape and form

The bidder shall note different structural elements in shape, form and structural configuration in plain. The structural elements may be skew, tapered, curved etc. The bidder shall include these factors while quoting his rates. All the above are to be covered in the quoted rates and nothing extra shall be payable towards this.

9.4 Stability of the elements

During construction, the stability of each element must be ensured until the connections through which the stability is achieved, are fully operative. This might require temporary, supporting, bracing etc. This is contractor's responsibility, and no extra payment is to be made.

9.5 Stability of the Structure

The overall stability of the structure must be ensured during each phase of constructions. This might require special provisions. This is also contractor's responsibility and no extra payment will be made.

9.6 Temporary Works

Traffic barricade with reflective tapes and other necessary traffic signages should be provided wherever required so that safety is ensured during day and night continuously. Temporary traffic diversion for smooth flow of traffic during construction including necessary traffic signs, repairs to the diverted route/service lanes, if required, restoration of diverted route to original condition etc. shall be done by contractor at his cost.

Contractor shall also provide any temporary support for the utilities (charted or uncharted), wherever required, at no extra cost to Employer.

The above listed works are only brief but the actual scope of work shall be as specified in the concerned document and/or as specified or directed by the Engineer.

9.7 Design for Temporary Works

The Design should cover all the items pertaining to all temporary works, traffic diversion scheme, form work, casting and stacking yard, staging, launching scheme for girders / beams and/or transportation scheme for various structural elements and materials to be transported to and from site during construction period.

The Contractor shall himself formulate a practical and viable scheme for design/ fabrication of shuttering, casting, curing, testing and launching/erection of girders / beams/ and all other structures. The bidder should, along with the bid, specify the scheme that he proposes to adopt for carrying out all the works including fabrication, transportation, stacking and erection of steel structure and casting, curing, stressing, testing and launching/erection of girders / beams.

The contractor shall formulate the erection scheme, design the staging, including all necessary temporary structure, prepare fabrication drawings in accordance with relevant provision of applicable IRC standards and submit the same to the Engineer for approval with third party certificates. These works will be executed only after the approval has been obtained from Engineer

D. Deleted.

E. DRAWINGS:

GFC DRAWINGS:

Errors, Omissions and Discrepancies in Specifications and Drawings:

It shall be the responsibility of the Contractor to promptly bring to the notice of Engineer any error, omission fault, defects or discrepancy in the contract documents, specifications and drawings for the work which are discovered while reviewing the contract documents or in the process of execution of the works and obtain his orders thereon. In case any feature of the work is not fully described and set forth in the drawings and specifications, the Contractor shall forthwith apply to the Engineer for further instructions, drawings or specifications.

Only stated dimensions are to be taken and not those obtained from scaling drawings.

In case of errors, omissions, faults, defects and/or disagreement on the drawings or between the drawings and specifications the following principles shall be followed.

As between the written description or written dimensions on the drawing and the corresponding one in the specifications, the former shall apply.

As between the written description of the item in Bill of Quantities and the detailed description in the specification of the same item, the **former shall prevail**.

The drawings on a **large scale** shall take precedence over those on a smaller scale; and

Drawings approved as construction drawings from time to time shall supersede corresponding drawings previously approved.

Meaning and intent of specifications and Drawings:

If any ambiguity arises as to the meaning and intent of any portion of the specifications and drawing or as to execution or quality of any work or material, or as to the measurement of the works, the decision of the Engineer thereon shall be final subject to the appeal (within 7 days of such decision being intimated to the Contractor) to Engineer/Employer who shall have the power to correct any errors, omissions, or discrepancies in the specifications, drawings, classifications of works or materials and whose decision in the matter in dispute or doubt shall be final and conclusive.

Responsibility For Specifications, Design and Drawings

a. Specifications

One copy of technical specifications shall be supplied to the Contractor.

MORTH / CPWD, KPWD specification / other Specifications / Codes viz. IS, IRS, IRC, DSR etc. shall be procured by the Contractor from the market. One set of these specifications shall always be kept at contractor's site office for reference.

b. Drawings for Permanent Works:

- i. GAD showing general dimensions & details elaborating the scope of work (not based on detailed design) are supplied along with the tender documents. These drawings are broadly indicative of the work to be carried out. These drawings are not "Construction Drawings" and details indicated therein are for general guidance only and shall be modified by the Engineer, to incorporate additional details as per design, and as described in the Specifications. Construction drawings shall be supplied progressively depending on the progress of work by the Engineer/Employer during execution of work well in time for each activity. The contractor cannot claim as a matter of right that all GFCD (Good For Construction drawings) shall be given soon after award of contract. GFCD/Advance copies required for the next three months work shall ordinarily be given by the Employer for his planning, procuring etc. The GFCD will be released as and when it is required without any delay to the successful Tenderer after the issue of Letter of Acceptance.

No claim whatsoever shall be admissible on account of any changes that may be introduced by the Engineer

- ii. The "Good for Construction" drawings which shall be issued to the Contractor by the Engineer after the award of work shall delineate the extent of work to be done by the Contractor
- iii. No deviation shall be made from these drawings without a written authorization from the Engineer.
- iv. Contractor shall co-ordinate with Division and SWR/HQ for getting approvals and necessary permits, as and when required..

c. Design, Drawings and Specifications for Temporary/ Ancillary works.

- i. Contractor's proposal for erection of all Ancillary and Temporary works shall be in conformity with the proposals submitted along with the tender and / or as approved by Engineer.
- ii. The contractor would design all the Ancillary and Temporary works including launching girder / truss, temporary supports, false work, formwork, staging scheme etc. and will submit the same and related working drawings to the Engineer for approval. After check by an independent third-party designer. Bar Cutting and bending schedule for the reinforcement, shop drawings for fabrication work, detailed

drawings for anchorage and temporary supports for prestressing cables etc. shall also be prepared by the Contractor and submitted for Engineer's approval

iii. Shop drawings

Based on "Good for Construction" drawings issued by the Engineer the Contractor shall prepare shop/fabrication drawings to scale as specified, indicating the required details. The shop drawings shall be prepared before execution of work, after taking actual site dimensions and all existing and proposed services/structures etc.

Shop drawings submitted by the Contractor shall be in sufficient detail to indicate the type, size, arrangement, breakdown for packing and shipment, the external connections, fixing arrangements required, the dimensions required for installation and interconnections with other equipment and materials, clearances and spaces required between various portions and any other information specifically called for

All reference points shall be in relation to the levels and locations, given in the Architectural and Services drawings duly cross-checked on site and confirmed. All locations and levels should be indicated with respect to grid and reduced levels with respect to the Bench Mark adopted for the Project and indicated in the drawings issued by the Engineer

The Contractor shall verify the dimensions of all the necessary structural, architectural, Mechanical, Electrical & Plumbing (MEP) Services and other elements, relevant to the system being done, before proceeding with the preparation of the shop drawings and proceeding with the physical work at site and make suitable adjustments to accommodate within the spaces available

iv. Approval of Engineer of any such proposal / drawings shall not relieve the contractor of his responsibility of sufficiency of such works

v. Drawing Management

The Contractor shall submit all such drawings for Temporary / Ancillary works and shop drawings to the Engineer well in advance before he desires to commence the works and get the same approved from the Engineer. These drawings should be submitted only after they have been duly detailed, checked and verified within the Contractor's organization ensuring that the details and data shown/furnished on the drawings are correct and that the requirements of other disciplines have been taken care of. The names and complete signatures of the Contractor's personnel responsible for the drawings shall be contained on each drawing. Any drawing which does not contain the above names and signatures shall be summarily returned to the Contractor and treated as not having been submitted.

The drawings submitted for approval shall be in any one of the standard sizes - AO, AI, A2, A3 or A4, in accordance with Indian standards

All drawings shall show the following particulars in the lower right hand corner in addition to the Contractor's name

Project Title

Name of the Employer

Name of Consultant

Contract No.

Title of Drawing.

Scale

Date of Drawing.

Contractor's Drawing Number.

Space for the Engineer's drawing number.

Name of the Engineer.

Name of Review Consultant.

This drawing is based on Drawing No. (s).

Further detail is given on Drawing No. (s).

- d. Each drawing shall carry a revision number, date of revision and brief details of revisions carried out. Whenever any revision is carried out, the revision number must be updated. The revisions carried out

on the drawing shall be clearly marked by clouding and each cloud revision numbered by marking the revision number in triangle. The clouding shall be done on the backside of the tracing by pencil. All dimensions on drawings shall be metric units, unless otherwise specified. However, all levels shall be in meters.

All shop drawings shall be prepared on CAD using AUTO-CAD Version 2008 or higher.

Shop drawings shall be prepared for the following works:

Reinforcing bar bending schedules

Working drawings for placing of reinforcement

All form works, Shuttering and Scaffoldings

Shop drawings for structural steel

Shop drawings for launching Girder / Truss including support arrangement

Metal work (ferrous and non-ferrous) for, rolling shutters, railings, balustrades, grilles gratings, screens, inserts, structural work in built up sections etc.

Seismic joints

Expansion joints

Construction joints

Waterproofing

All MEP services

Any proprietary system

e. Drawing Management at Site

The Contractor shall ensure that all drawings meant for further engineering, fabrication, erection and field work are issued to his personnel in a controlled manner - a proper record shall be maintained to show to whom the drawing is issued and to ensure that the latest revisions of the drawing is being followed for further work. All superseded drawings shall be promptly withdrawn from the personnel to whom they are issued and stamped "SUPERSEDED" in RED. The Contractor shall maintain a register of drawings, with their revision/issue number, as received from the Engineer and a record of their distribution to the designated personnel within their organization.

The Contractor shall maintain at Site a set of the drawings issued by the Engineer on which changes shall be progressively marked and initialed by the Engineer so that "As-Built" drawings can be made correctly and expeditiously at the end of their Work at Site.

Revision of Approved Drawings for Temporary/ Ancillary and Shop Drawings

If, at any time before the completion of the Work, changes are made necessitating revision of approved Shop drawings/ drawings for Temporary/ Ancillary works, the Contractor shall make such revisions and proceed in the same manner and observe procedure for obtaining approval of the Engineer as for the approval of the original drawings

v. Documents by Contractor

The contractor shall submit to the Engineer, for approval, Quality Assurance plans, design calculations, material specifications for each item and system, samples, as may be called for in the Specifications or as the Engineer may reasonably require. Wherever necessary the Contractor shall provide as built dimensions to facilitate proper Good for Construction drawings being prepared for various construction detailing.

v. Number of Copies of Drawings for Temporary/ Ancillary works/ Shop drawings and Documents

All Shop drawings / drawings for Temporary and Ancillary works, Documents, Schedules etc. and revisions thereof shall be submitted by the Contractor to the Engineer in 6 copies in size as required by Engineer. Copies required in excess of these shall be borne by the Contractor at his own cost.

d. Completion Drawings:

On completion of the work in all respects the contractor shall submit the following:

Three sets of "As Built Drawings" in the standard sizes each containing complete set of drawings for every component of work on approved scale indicating the work "As Built". Each set shall also contain technical literature.

These drawings shall be prepared on CAD using Auto-Cad version (latest/as directed by Engineer) and shall be recorded on writable CDs and one set of these CDs shall also be submitted.

Four sets of catalogues of all manufactured materials with the name and addresses of the manufacturers for all equipments provided by him.

The Contractor shall also submit one original "As Built" drawings on polyester film or as directed by Engineer of quality as approved by Engineer/ Engineer's Representative.

The Certificate of Completion of Works as per the provisions in the General Conditions of Contract shall not be issued by the Engineer in the event of Contractor's failure to furnish aforesaid "As Built" drawings for the entire works.

e. Plans and Drawings for Layout of Plant and Equipment

The Contractor shall submit the following information, in triplicate, to the Engineer, for approval, within the time stipulated against each item given below:

A general layout plan for construction plant and equipment required for execution of work, within thirty days from the date of issue of "Letter of Acceptance".

drawings or prints showing the locations of major facilities which he proposes to put up at site, at least fourteen days prior to the commencement of the respective work; and

Any other details and drawings as required under the contract, within the time as specified in the contract.

Cost of all the above activities shall be deemed to be included in the quoted rates of various items of the Bill of Quantities and nothing extra shall be paid for on this account.

Appendix – I - Programme Requirements

1.1 General

Construction Programme and project monitoring

- I. The contractor shall propose and submit his detailed construction program separately and as per the procedure detailed in the scope of work. Contractor may be asked to schedule and complete the work block wise / area wise in a phased manner fixing priorities to different stretches of the work to give access to other interfacing contracts as mentioned in the Bid documents.
- II. The tentative construction program shall be submitted within the period as specified in the Bid document for approval of the Engineer as 'Baseline Program'. The base line program shall clearly reflect interface and access dates for other civil/ system-wide contracts. The basis of the time schedule for each activity such as productivity of man and machines and time cycle of each activity and resource planning shall be submitted along with the base line program.
 1. After the work has started, the Contractor shall deliver in the first week of every month to the Engineer an update of the Construction Program showing changes, if any, in planning or progress scheduling and reflecting the progress of all the activities of the network and the project status as at the end of previous month.
 2. If the Contractor falls behind the approved Construction Program by more than one month, he shall, within fourteen days of the date of such information, submit for approval, a revision of the construction program showing the proposed measures, including augmentation of plant, labor and material resources to complete the works on time.
 3. Whenever the Contractor proposes to change the construction program, he shall immediately advise the Engineer in writing and, if the Engineer considers the change a major one, the Contractor shall submit a revised program for approval.
 4. Detailed Network Plan (Works Program): Detailed Network Plan shall be prepared by the Contractor for each and every activity within the same time frame and in the same sequence. Activity at this level shall not be more than 15 days' duration, except for summary items like procurement/ mobilization etc.
- III. The Contractor shall select a PC-based broad planning and control software (licensed version of Primavera etc.). The two networks shall be implemented on works as detailed in the Scope of work. The Contractor shall supply one original licensed copy of the software selected including manuals and any subsequent versions thereof at no extra cost along with the Baseline program network and detailed network plan and load it on the PC system of the Engineer so that uniform monitoring of the project is done and any slippages are identified well in time and corrective action taken. The contractor shall also arrange suitable training of the personnel of Engineer on the selected software, if required, at no extra cost.
- IV. The following reports, in agreed formats and frequency, shall be submitted by the Contractor at his own cost:
 - i. Progress Reports
 - ii. Material Status Reports
 - iii. Equipment and Manpower Deployment Reports
 - iv. Any other Report desired by the Employer or the Engineer
- V. The Engineer's monitoring team will have access to all the data/information of the Contractor, required for the assessment of the progress and monitoring. If necessary, the monitoring team will visit the Vendor/Contractor's works in order to assess the status of critical activities.
- VI. Periodic Project Status Review Meetings will be held by the Employer or the Engineer. The Contractor shall depute his Engineers/Managers at appropriate level as decided by the Engineer to attend the Review Meetings.
- VII. Progress photographs of the major events shall be submitted by the Contractor along with the Progress Reports. Video Recording of the progress of works shall be maintained from beginning till completion of work as directed by the Engineer.
- VIII. The Contractor shall provide additional inputs whenever the PERT-CPM/ network diagram (Primavera) indicates a possible slippage in the completion schedule. Such additional inputs may require supplementing of equipment, personnel, work in excess of the normal work per day, and work in excess of the normal work per week or other resources. Provisions in the relevant Clause of Conditions of Contract and Particular of conditions of contract will be applicable in cases of delays due to Contractor.

1.2 Purpose of Program

- a) The purpose for the requirement of Program (Scheduling) information described in this document is to provide the Engineer with status reports for managing, monitoring and coordinating the awarded contract during the execution within the overall multi-contract project schedule. It describes a series of reports to be submitted by the Contractor to the Engineer during the execution of the contract, following the award of Contract.
- b) The Bidder/ Contractor shall program his work at all times to meet the Key Dates and the Works Area Hand-over Dates specified in the bid documents and the specified interface periods for the design and installation of the Works with those of the Designated Contractors and shall during the progress of the Works constantly monitor his progress against the programs described below.
- c) The Bidder/ Contractor shall include in all programs his work obligations towards shared access, shared Site areas and other coincident or adjacent Works Areas.
- d) The Works Program, and all more detailed or revised versions, shall be submitted to the Engineer for his consent.

1.3 Methodology

- a) The computerized Primavera network using the Precedence Diagramming Method (PDM) has been selected by the Employer as the technique for contract management system and in coordinating the multi-contract project. This technique shall also be employed by the Bidder in preparing their Bid submissions and by the Contractor in their Construction Stage submissions.
- b) Unless otherwise agreed by the Engineer, all programs submitted by the Contractor shall be produced using computerized Primavera Networks developed implementing the Precedence Diagramming Method (PDM) with Resource Loaded Charts and Tables.
- c) The Contractor shall implement and use throughout the duration of the Contract, a computerized system to plan, execute, maintain and manage the planning, design, pre-construction, construction, and sub-contracts in executing the Primavera scheduling by PDM. The reports, documents and data shall be provided monthly and shall be an accurate representation of the current status of the Works and of the work remaining to be accomplished; work planned to be taken up during next month, shall provide a sound basis for identifying problems, deviations from the planned works, and for making decisions; and shall enable timely preparation of the same for presentation to the Engineer.
- d) Program management software
Primavera programming software used shall be Primavera 6.0 v 21.12 programming software shall be used.

1.4 Submissions

- 1.4.1 The Contractor shall develop bid Program into the Initial Works Program including an outline Narrative Statement and submit within 28 days of the date of receipt of Letter of acceptance and its more detailed version within 15 days of receiving the Engineer's consent to the proposed Initial Works Program.
- 1.4.2 Activities in the initial works program should be arranged as per the Works Break down Structure (WBS) of the work. The WBS of the work would be developed by the contractor in consultation with the Engineer. Contractor would get the WBS approved by the Engineer and the program expert.
- 1.4.3 The first Three Month Rolling Program shall also be submitted along with Initial Works Program within 28 days of the date of receipt of Letter of Acceptance and all subsequent editions shall accompany the Monthly Progress Report. The Monthly Progress Reports shall also include a Program Update as described below. These programs shall subsequently be updated as described below.
- 1.4.4 Following the Engineer's consent to Contractor's Initial Works Program submission, the contractor shall make submissions of the Detailed Works **Program** suitably amended to take into account the programs of Designated Contracts. It is the Contractor's responsibility to ensure timely co-ordination with the Designated Contractors to review, revise and finalize his Initial Work Program so as not to affect the progress of Works/ and or the works of the Interfacing Contractors. The resubmitted program when approved by the Engineer and the program expert shall form the **Baseline Program** against which actual progress of the Contract shall be reckoned. As the work progresses, it may be necessary to update/ revise the Baseline program but such updating shall only be carried out with the prior consent of the Engineer or when directed by them.
- 1.4.5 For Initial & Detail Work Program submission, one (1) original and six (6) copies each (along with

electronic copy) of the following Programs and Reports shall be submitted to the Engineer:

- a) Program: Baseline Primavera Network
 - b) Program: Baseline Milestone based Cost Activity Schedule
 - c) Baseline Schedule Report
 - d) Narrative
 - e) Baseline Physical Progress 'S' curve
 - f) Baseline Resource Charts (with Resource levelling)
 - g) Detailed Method Statement
- 1.4.6 The Engineer shall review and comment on the Contractor's programs and information submitted. The Engineer will confirm his consent or otherwise of the submissions.
- 1.4.7 The Engineer shall require the Contractor to re-submit within fifteen (15) calendar days if he is of the opinion that the programs and information submitted by the Contractor is unlikely to meet the Contract key dates.
- 1.4.8 If in the opinion of the Engineer, any of the Contractor's revised programs or Baseline Schedule Report is not acceptable, it shall be construed as a failure of the Contractor to meet a Milestone.
- 1.4.9 Notwithstanding the above, the Engineer may at any time during the course of the Contract require the Contractor to reproduce the computer-generated Baseline Schedule Report described above to reflect actual activity dates and generate schedules based upon "what if" statements. The initial computer-generated report after receiving the Engineer's consent will serve as the base against which the contract progress will be measured. Any changes to the Report reflected in subsequent Baseline Schedule Reports shall also require the Engineer's consent.
- 1.4.10 Failure to include any element of work required for performance of the Contract shall not relieve the Contractor from completing all works required under the Contract to achieve the original or any extended key completion date.

1.5 Works Programme

- 1.5.1 The Works Programme shall show the Contractor's plan for organizing and carrying out whole of the Works.
- 1.5.2 The Works Programme shall be a computerized Primavera network developed using the Precedence Diagramming Method (PDM) and shall be present in bar chart and time-scaled network diagram format to a weekly time scale.
- 1.5.3 Tasks in the Works Programme shall be sufficiently detailed to describe activities and events that include, but are not limited to, the following:
- (a) Key Dates, and Works Area Hand-over Dates and Interface dates.
 - (b) All physical work to be undertaken in the performance of the Contract obligations, including Temporary Works,
 - (c) The requested date for issue of any drawings or information by the Engineer,
 - (d) Procurement of major materials and the delivery and/or partial delivery date on-Site of principal items of Contractor's Equipment,
 - (e) Commissioning date of Contractor's major equipment
 - (f) Any off-site work such as production or pre-fabrication of components,
 - (g) installation of temporary construction facilities,
 - (h) Interface periods with Designated Contractors or utility undertakings,
 - (i) Design, supply and/or construction activities of sub-contractors,
 - (j) Any outside influence which will or may affect the Works.
- 1.5.4 The Works Programme shall show achievement of all Key Dates, Interface dates and Works Area Hand-over Dates. The Works Program shall also show all Milestones, but the Milestones shall not be taken as imposing any constraints that in any way affect the logic or limit any other dates in the program.
- 1.5.5 Activity descriptions shall be unique, describing discrete elements of work. Any activity creating an imposed time or other constraint shall be fully defined by the Contractor.
- 1.5.6 The Works Programme shall be organized in a logical work-breakdown-structure including work stages and phases, and shall clearly indicate the critical path(s).
- 1.5.7 Activity duration shall not exceed 15 days, unless otherwise consented to by the Engineer, except

non-construction activities such as submittals, submittal reviews, procurement and delivery of materials or equipment and concrete curing. The Contractor shall submit a Program/Project Calendar cross reference clearly indicating the allowance for holidays.

1.5.8 The Works Program, in each submission, shall be accompanied by an Activity Report and a Narrative Statement as described below in both electronic and hard copy format (time scale logic diagrams in A1/A3 size, reports in A4 size).

1.5.9 Activity Report shall list all activities, and events in the Works Program, sorted by activity identification number.

The Activity Report shall include the following for each activity and event:

- i. *Activity identification number and description,*
- ii. *Duration expressed in Days,*
- iii. *Early and late start & early and late finish dates. Planned start and finish dates,*
- iv. *Calculated total float and free float,*
- v. *Predecessor and successor(s), accompanying relationships and lead/lag duration,*
- vi. *Imposed time or date constraints,*
- vii. *Calendar.*

1.5.10 Narrative Statement

The Narrative shall be a comprehensive statement of the Contractor's plan and approach for the execution of the Works and the achievement of key dates, handover dates, submission dates and any intermediate dates. It shall incorporate outline method statements in respect of major items of work including construction sequences, launching scheme, resources required including primary item of plant, Construction Equipment required, person responsible, quality checks, inspection and test procedures, tolerances, Temporary Works and the like, risk analysis, etc. for carrying out that activity. It shall fully explain the reasons for the main logic links in the Program and include particulars of how activity duration is established. This shall include estimated quantities, production rates, hours per shift, work days per week and a listing of the major items of Construction Equipment planned for use on the project. Activities, which may be expedited by use of overtime or additional shifts, shall be identified and explained. A listing of holidays, and other special non-work days being used for the computer reports shall be included.

1.5.11 Baseline Physical Progress 'S' Curve

The Contractor shall also submit a forecast Cumulative Physical Progress 'S' curve based on the time-phased distribution of cost in the Primavera Network Logic Diagram, expressed in percentage terms. This 'S' curve shall be generated from the computerized Primavera Network Logic Diagram.

1.5.12 Baseline Resource Charts

The Contractor shall also submit a Resource Charts, generated from the Contractor's Primavera Network Diagram, showing the anticipated manpower and main Construction Equipment usage during the execution of the Project. The Resources shall be properly levelled using primavera VP6 software.

All submissions of proposed Works Programs subsequently, after approval of the Initial Works Program, shall include the actual physical progress of work and forecast of the remaining work. Actual progress shall be stated in percent complete, remaining duration, and actual start and finish dates for each activity in the Works Program.

1.6 Initial Works Programme

1.6.1 The Initial Works Programme submitted as under Clause 1.4.1 need not include the full details given under Clause 1.5 above. It should be a condensed version with combined activities of longer duration but must show clearly how the requirements of the Contract are to be achieved. Activities in the initial works program should be arranged as per the Works Break down Structure (WBS) of the work. The WBS of the work would be developed by the contractor in consultation with the Engineer. Contractor would get the WBS approved by the Engineer. The outline Narrative Statement shall be in sufficient detail to clearly show the Contractor's intention.

1.6.2 Within 15 days of the Engineer's consent to the Initial Works Program, the Contractor shall submit to the Engineer an expanded and more detailed version of the Initial Works Program containing all of the information and detail required under Clause 1.4 and 1.5 above.

1.6.3 Such submission shall make use of the Program submitted earlier but refined to include the best

estimates of dates for the work of Designated Contracts which has impact on the Contractor's program. Such programs shall be amended subsequently to incorporate the actual dates/ schedule of the affecting contracts. It is the Contractor's responsibility to ensure timely co-ordination with the Designated Contractors to finalize the Initial Program, without affecting progress of the work.

1.7 Works Programme Revisions

- 1.7.1 The Contractor shall immediately notify the Engineer in writing of the need for any changes in the Works Program, whether due to a change of intention or of circumstances or for any other reason. Where such proposed change affects timely completion of the Works or any other Key Date the Contractor shall within fourteen (14) days of the date of notifying the Engineer submit for the Engineer's consent its proposed revised Works Program and accompanying Narrative Statement. The proposed revised Works Program shall show the sequence of operations of any and all works related to the change and the impact of changed work or changed conditions.
- 1.7.2 If at any time the Engineer considers the actual or anticipated progress of the work reflects a significant deviation from the Works Program, he may request the Contractor to submit a proposed revised Program which together with an accompanying Activity Report and Narrative Statement, shall be submitted by the Contractor within fourteen (14) days after the Engineer's instruction. The proposed revised Works Program shall show the sequence of operations of any and all work related to the change and the impact of changed work or changed conditions. Revisions should not affect the overall completion of the project.
- 1.7.3 All activities that have negative float must be analyzed by the Contractor to identify the impact on the timely completion of the Works or on the achievement of Key Dates.

1.8 Three-Month Rolling Programme

- 1.8.1 The Three-Month Rolling Programme shall be an expansion of the Detailed Works Program, covering sequential periods of three months. The Three-Month Rolling Program shall provide more detail of the Contractor's plan, organization and execution of the work within these periods. In particular, the Contractor shall expand each activity planned to occur during the next three (3) month period, if necessary, to a daily level of detail.
- 1.8.2 The Three-Month Rolling Program shall be developed as an Primavera network, and shall be presented in bar chart and time-scaled network diagram format. Bar charts shall be presented on an A4 and time-scaled networks diagrams on an A3 size reproducible media. Tasks in the program shall be derivatives of and directly related to tasks in the approved Works Program.
- 1.8.3 The Contractor shall describe the discrete work elements and work element inter-relationships necessary to complete all works and any separable parts thereof including work assigned to sub-contractors within the contract period.
- 1.8.4 Activity duration shall not exceed two (2) weeks unless and otherwise consent of Engineer is granted.
- 1.8.5 Each activity in the Three-Month Rolling Program shall be coded, or described so as clearly to indicate the corresponding activity in the Works Program.

1.9 Three-Month Rolling Programme Revisions and update

- 1.9.1 The Three-Month Rolling Programme shall be extended forward each month as described under Clause 1.8.1 above. Each submission of the Three-Month Rolling Program shall be accompanied by a Program Analysis Report, describing actual progress to date, and the forecast for activities occurring over the next three-month period in order to achieve progress as per the approved Works Program.
- 1.9.2 If the Three-Month Rolling Program is at variance with the Works Program, the Program Analysis Report shall be accompanied by a supporting Narrative Statement describing the Contractor's plan for the execution of the activities to be undertaken over the three-month period, including program assumptions and methods to be employed in achieving timely completion.
- 1.9.3 The Contractor shall revise the Three-Month Rolling Program or propose revisions of the Works Program, or both, on a monthly basis to ensure consistency between them.
- 1.9.4 Three-Month Rolling Program (revised) to be submitted on a monthly basis by 5th of every month with respect to the progress achieved by the last day of the previous month. A penalty of ₹. 100,000/- (Rupees One

Lakh) per instance will become applicable to the contractor for non-submission of the revised Three-monthly rolling program as per above clauses, irrespective of the causes lead to variances if any and the penalty will be deducted in the subsequent IPC which will be non-refundable.

1.10 Weekly review

Once a week, on a day mutually agreed to by the Engineer and the Contractor, a meeting will be held to assess progress by the Contractor during the previous week, progress review which will also be attended by the programs Expert and the Contractor's Program Engineer. The Contractor shall submit a construction schedule listing activity completed and in-progress from the previous week and the activities scheduled for the succeeding two weeks based on the detailed Works Program. Copies of the schedule shall be submitted on A3 sized papers.

1.11 Project Calendar

For the Project, the Contractor shall adopt 7 days a week calendar, identical calendar for the purpose of programming and Execution of Works. Official documents shall be transacted during 6 days' week – Monday through Saturday. For Project purposes, a week begins at 0001 hours on a Monday and ends at 2359 hours on a Sunday. The completion of an activity or the achievement of an event when given a week number shall be taken to mean midnight on the Sunday at the end of the numbered week. An access date or activity start date when given as a week number shall be taken to mean 0001 hours on a Monday of the Numbered week.

1.12 Programming Personnel

The Contractor shall submit, as part of its Staff Organization Plan, the names and required information for the staff to be employed on Works Programming. The principal Works Programmer shall hold reputable professional qualifications acceptable to the Engineer including at least five (5) years relevant experience in programming civil engineering works. Others in the group shall have at least three (3) years' experiences in such work. The programmers shall be employed by the Contractor full time on the Contract until the completion or such earlier time the Engineer may give his consent.

1.13 Programme and Report Submission Format

The Contractor shall submit one (1) original and six (6) copies and one (1) reproducible (for Programs) of all submissions to the Engineer. All submissions shall be in A0, A1, A3 or A4 size, as appropriate except as may otherwise be agreed by the Engineer. In addition, the computerized program and report shall be submitted in compatible discs. The format for all Program and Report submissions shall be strictly in accordance with the format as stated herein or as requested by the Engineer.

2. Monthly Progress Reports

2.1 General

The Contractor shall submit to the Engineer, a Monthly Progress Report. This Report shall be submitted by the end of each calendar month and shall account for all work actually performed from 26th day of the last month and up to and including the twenty-fifth (25th) day of the month of the submission. It shall be submitted in a format to which the Engineer shall have given his consent and shall contain sections/sub-sections for, but not be limited to, the topics listed in clauses below.

2.2 Physical Process

- a) It shall describe the status of work performed, significant accomplishments, including critical items and problem areas, corrective actions taken or planned and other pertinent activities, and shall, in particular, address interface issues, problems and resolutions.
- b) It shall include a simplified representation of progress measured in percentage terms compared with percentage planned as derived from the Works Program.

2.3 Programme Update (For Entire Project)

Programme updating shall include

- (a) The monthly Program Update which shall be prepared by recording actual activity completion dates and percentage of activities completed up to the twenty-fifth (25th) of the month together with estimates of remaining duration and expected activity completion based on current progress. The Program Update

shall be accompanied by an Activity Report and a Narrative Statement. The Narrative Statement shall explain the basis of the Contractor's submittal:

- (i) Early Work and Baseline Submittals – explains determination of activity duration and describes the Contractor's approach for meeting required Key Dates as specified in the Contract.
- (ii) Updated Detail Program Submittals – state in narrative the Works actually completed and reflected along Critical Path in terms of days ahead or behind allowable dates. Specific requirements of narrative are:
 - a) If the Updated Detailed Work Programme indicates an actual or potential delay to Contract Completion date or Key Dates, identify causes of delays and provide explanation of Work affected and proposed corrective action to meet Key Dates or mitigate potential delays. Identify deviation from previous month's critical path.
 - b) Identify by activity number and description, activities in progress and activities scheduled to be completed.
 - c) Discuss Variation Order Work Items, if any.
- (b) The Program Status which shall: -
 - (i) Show Works Program status up to and including the current report period, display Cumulative progress to date and a forecast of remaining work.
 - (ii) Be presented as a bar-chart size A3 or A4 and as a time-related logic network diagram on an A1 media, including activity listings;
- (c) The Activity Variance Analysis which shall analyze activities planned to start prior to or during the report period but not started at the end of the report period as well as activities started and/or completed in advance of the Works Program.

2.4 Three Month Rolling Program

The monthly issue of the Three-Month Rolling Program.

2.5 Financial Status

It should include following

- a) A narrative review of all significant financial matters, and actions proposed or taken in respect to any outstanding matters.
- b) A spread sheet indicating the status of all payments due and made.
- c) A status report on status of extra items, if any

2.6 Status of Claims

A report on of the status on any claims outstanding. The report shall in particular provide interim updated accounts of continuing claims.

2.7 Milestones/Key Dates Status

A report on the status of all milestones/ key dates due to have been achieved during the month and forecasts of achievement of any non-achieved key dates and those due in the next month

2.8 Resources Status

- 2.8.1 The Contractor shall submit to the Engineer each month a detailed list by trade classification, of manpower employed during the report period, stock of all major construction materials as also a list of all serviceable major items of construction plant and equipment on site including those which are proposed to be mobilized during the next month.
- 2.8.2 A report on the status of deployment of all key personnel and other manpower by trade Vis – a - Vis their deployment schedule and explaining constraints if any.
- 2.8.3 Status of stock of all the major construction material vis -a- vis its requirements for next month.
- 2.8.4 Status of all serviceable major construction plant and equipment at site.

2.9 Procurement Report

- 2.9.1 A summary of all significant procurement activities during the month, including reasons of delay (if any) and

action taken to overcome problems.

- 2.9.2 A report listing major items of plant and materials which will be incorporated into the Works. The items shall be segregated by type as listed in the Specifications and the report should show as a minimum the following activities:

- (a) purchase Order Date – Scheduled/ Actual,
- (b) manufacturer/ Supplier and Origin,
- (c) letter of Credit Issued Date,
- (d) manufacturer/ Supplier Ship Date – Scheduled/ Actual,
- (e) method of Shipment,
- (f) Arrival Date in India – Scheduled/ Actual.
- (g) Arrival date at site and commissioning date

The report should also explain the delays (if any) in arrivals of the major equipment at site and the actions taken by the Contractor to expedite the same and the measures proposed to makeup the time loss.

2.10 Production and testing

It should include following:

- (a) A review of all production and manufacturing activities during the month.
- (b) Summaries of all production and manufacturing outputs during the month together with forecasts for the next month.
- (c) Review of all testing activities (both at site and at the manufacturer's premises) during the month.

2.11 Safety

A review of all safety aspects during the month including safety inspections / audits, reports on all accidents and actions proposed to prevent further occurrence.

2.12 Environment

- 2.12.1 A review of all environmental issues during past month shall include all monitoring reports, mitigation measures undertaken, and activities to control environmental impacts.
- 2.12.2 In case of failure of the Contractor to make submissions as per section 1.4 herein above, the Employer/ Engineer shall retain 5% of the due progress payment till the submissions. For non-submission of Monthly Update and Progress Reports as per Clause 2 herein above, the Employer/ Engineer shall retain 5% of the due progress payment in each case, which shall be released upon submission of the same. In case the submissions are not made in the month it is due, the retained payment would be released only in the next Monthly Running Bill.

Appendix – II - Method of Measurements for Permanent Works**1 Introduction**

- 1.1 The detailed procedure to be followed for the recording of measurements and for the preparation and passing of Contractors Bills for permanent works is set out in the following paragraphs.

2 Measurement of Works**2.1 General**

- 2.1.1 Measurements shall be taken at such intervals as are found necessary or convenient. Generally, one bill will be preferred in a month or as specified in the contract.
- 2.1.2 Entries should be made only in ink, and no entry should be erased or defaced so as to make it illegible. Correction of mistake, if any, shall be made by neatly crossing out the incorrect entry and rewriting and correct words or figures. All such corrections should be initialed by the Contractor's Engineer as well as by the Engineer's Representative at site.
- 2.1.3 Format of Record of Measurements sheets and procedure for issue of these measurement sheets shall be as decided by Engineer / Employer.
- 2.1.4 Before starting the earth work for embankment, cutting, bridge excavations etc., the initial ground levels shall be taken jointly along with engineer.

2.2 Items for which Good-for-Construction GFC Drawing is issued

- 2.2.1 As soon as the Good-For-Construction GFC drawing for a work is issued, the Contractor will calculate the details of quantities of various items of PRICE SCHEDULE involved, in a format approved by Engineer, and submit the calculations and schedule of quantities to the Engineer / Engineer's Representative and get them approved for the drawing.
- 2.2.2 Once the schedule of quantities is thus approved, the Contractor will submit five copies of the approved schedule to Engineer's Representative in an approved format.
- 2.2.3 The Contractor will submit his payment claims based on the approved schedule of quantities along with certification of actual work done as per specifications, drawings and contract conditions and within the tolerances as specified. Measurement will be entered in Record of Measurement Sheet duly signed jointly on each page by Contractor's authorized qualified engineer and Engineer's Representative.
- 2.2.4 Abstract of measurement will be prepared by the contractor in the approved form based upon these measurements.

2.3 Items for which Good-For-Construction GFC Drawing is not issued

- 2.3.1 For all such works, whose measurement cannot be calculated from any Good-For-Construction (GFC) drawing, all measurements will be taken by the Contractor's authorized qualified Engineer in the presence of the Engineer's Representative at site. These measurements will be recorded on approved form of Record Measurement Sheet and signed jointly by contractor and Engineer's Representative.
- 2.3.2 Contractor will ensure that a properly qualified Engineer is deputed for taking measurements and also that all the measurements taken are witnessed and signed by the Engineer's Representative.
- 2.3.3 All measurements should be recorded at site on the Record of Measurement Sheet in the presence of the Engineer's Representative.
- 2.3.4 Each Measurement Sheet should be signed by the Contractor's Engineer as well as by the witnessing Engineer's Representative.
- 2.3.5 Based on the recorded measurement contractor will prepare abstract of quantities in the approved format.

Appendix III - Quality Manual**Table of Content**

1 Purpose	31
2 Scope	31
3 Definitions.....	31
4 Responsibilities.....	31
4.1 Project Directors	31
4.2 Senior Managers	32
4.3 Designers.....	32
4.4 Quality Managers and Officers.....	32
4.5 Section, Site, Discipline Engineers and Foremen.....	33
4.6 Supervisors.....	33
4.7 All Employees.....	33
5 Legal and Other Requirements.....	33
6 Quality Objectives.....	34
7 Quality Standards, Codes and Specifications.....	34
8 Tender and Procurement	34
9 Design and Engineering.....	34
10 Construction	35
11 Commissioning and Handover.....	36
12 Operations and Maintenance.....	37
13 Training	37
14 Closing.....	38
15 Quality Surveillance, Non-Conformities and Improvement.....	38
16 Quality Monitoring and Reporting.....	39

1 Purpose

This document titled 'Construction Quality Guideline' sets the minimum Quality Standards that are to be adopted and implemented across all the projects of the BSTP project Programs. This document only provides an outline and overview of the obligations, the detailed and specific quality requirements are described in Indian Legislation.

2 Scope

- This procedure applies to Bangalore Suburban Rail Projects and sub projects at BSTP, project information / records created regardless of format, which includes information generated by the General Consultant, D&B Contractor(s) and 3rd Parties.
- Bi-RIDE contracts complete packages. These packages consist in detail engineering, construction / production, quality planning, assurance and control and at last quality verification.
- Bi-RIDE requires the fulfilment of the Bi-RIDE CMS Quality Policy, the quality objectives and the project quality plan(s) throughout the lifecycle of the contracted work

3 Definitions

Table 1: Definitions

Term	Definition
Bi-RIDE	The Employer and Client
General Consultant	Bangalore Suburban Rail Projects' General Consultant (Egis, AECOM & WSP JV).
The Engineer	General Consultant
Initiator / Originator	The person who starts the process.
Participant	The person who is or may be involved in the implementation of the procedure.
D&B Contractor	The organization contracted by the Employer to carry out the Project D&B works.
3 rd Parties	3 rd party Project stakeholders.
Project Partners	The term 'Project Partners' used throughout this document includes the Client, General Consultant, other Consultants, Contractors, Subcontractor's, Suppliers and anyone else who undertake works on the Bangalore Suburban Rail projects.

4 Responsibilities

4.1 Project Directors

- Provide positive leadership on quality issues.
- Promote an enthusiastic quality culture that delivers positive commitment to and engages all employees in continuous improvement in quality performance.
- Keep abreast of developments of Indian quality legislation and industry standards.
- Ensure that a quality management system is implemented within their sphere of responsibility and monitor and review its effectiveness and take necessary improvement action.

- e. Monitor that personnel under their control comply with their individual responsibilities in quality matters.
- f. Ensure that the disciplinary process to address breaches of the quality policy or management system is applied where necessary.

4.2 Senior Managers

- a. Senior Managers are people in the organisation at any level above senior supervisor and below director.
- b. Provide positive leadership on quality issues within their area of operation.
- c. Promote an enthusiastic quality culture that delivers positive commitment to and engages all employees in continuous improvement in quality performance.
- d. Implement the business unit quality management system. In particular:
 - i. Identify quality training needs and have the necessary training arranged and when arranged, release those who require training.
 - ii. Make arrangements for quality induction training for all new starters at the workplace under their control.
 - iii. Implement operating procedures, for the planning and control of activities associated with identified risks.
 - iv. Ensure that written method statements, risk assessments and/or quality rules are brought to the attention of management.
 - v. Appoint appropriate personnel to undertake quality duties.
 - vi. Ensure that suitable arrangements are in place for the effective control of changes to planned methods of work.
 - vii. Keep abreast of developments in Indian quality legislation and industry standards.
 - viii. Monitor and review the effectiveness of the quality management system and report deficiencies.
 - ix. Monitor that personnel under their control comply with their individual responsibilities in quality matters.
 - x. Give personnel under their control, including contractors, clear instructions as to their responsibilities to ensure correct working methods.

4.3 Designers

- a. Ensure staff, are competent and adequately resourced to address the quality issues likely to be involved in the design.
- b. Consider quality when designing structures, equipment systems, temporary works.
- c. When carrying out the design, provide adequate information about any quality risks associated with the design.
- d. Coordinate activities with that of others to improve the way in which quality is managed and controlled.

4.4 Quality Managers and Officers

- a. Provide positive leadership within their area of operation and promote the adoption of best practice.
- b. Promote an enthusiastic quality culture that delivers positive commitment to and engages all employees in continuous improvement quality performance.
- c. Keep abreast of developments in quality legislation and industry standards.
- d. Monitor and report on the effectiveness of the quality management system and progress against the quality performance standards and make recommendations for improvement as appropriate.
- e. Monitor and report on operational quality performance and make recommendations for improvement and monitor to ensure that effective action is taken.
- f. Lead and provide functional management for any quality personnel under their control.
- g. Assist with the identification of quality training needs, and monitor delivery and recording.

- h. Monitor and report on the implementation of the approved quality objectives.
- i. Produce quality performance reports as required.
- j. Promptly alert line and functional management to significant quality issues and where appropriate be involved in the investigation and ensure that the findings are reported.
- k. Review quality reports, identify any trends and ensure that there is an appropriate response to prevent future recurrence.

4.5 Section, Site, Discipline Engineers and Foremen

- a. Appreciate the responsibility allocated to individuals within the operative and management structure.
- b. Set a good example and leadership on the site.
- c. Ensure that only trained and authorised workers use plant and equipment and that persons undergoing training do not operate plant and equipment unless closely supervised by a competent person.
- d. Ensure that employees under their control attend quality induction training before working on the site and that they are correctly supervised at all times
- e. Ensure that materials, plant and equipment under their control or brought to site by the subcontractor has any necessary certificates of test, inspection and examination and is safe to use
- f. Ensure that clear instruction and information is given to persons under their control.
- g. Carry out recorded quality inspections of site conditions.
- h. Attend any meeting on quality issues as required and as applicable, co-operate with all personnel on matters of quality.

4.6 Supervisors

- a. Supervisors are people at the first level in the organisation that have responsibilities over the work of others.
- b. Provide positive leadership on quality issues for the members of the work team for which they are responsible.
- c. Promote a positive attitude in the workforce and encourage behaviours that protect both people and the environment.
- d. Monitor that personnel under their control comply with their individual responsibilities in quality matters.
- e. Give personnel under their control, including contractors, clear instructions about the required methods of work.
- f. Identify any quality training requirements of personnel under their control and advise appropriate management accordingly.
- g. See that all quality issues are reported immediately to the relevant manager.

4.7 All Employees

Set a good personal example on quality issues within your area of operation.

5. Legal and Other Requirements

- a. All work is to be undertaken in compliance with the requirements of Indian Law. If no local standard exists or the applicable standard is not specified, the appropriate and compatible internationally recognised standard or code of practice shall be adopted.
- b. The hierarchy of standards is as follows:
 - i. Indian Standards (IN),
 - ii. Euro Norm (EN),
 - iii. British Standards (BS),

- iv. International Standards and Codes of Practice
- v. Alternative standards may be proposed if they can satisfactorily be demonstrated that they are equivalent, in all respects, to the defined standards. Where there is a discrepancy or a conflict, the higher or stricter standards shall take precedence. Project Partners are to ensure that all prescribed registers, certificates and records are maintained and available for inspection at the relevant work locations by any authorised person.

6. Quality Objectives

- a. Quality objectives must be defined and made available for all internal and external stakeholders. The completion of the quality objectives must be checked on a regular basis and the measures must be adopted accordingly in line with the Bi-RIDE's Quality Strategy and to achieve Right the First Time.
- b. These quality relevant objectives (KPI) will be defined by the Bi-RIDE's Executive Management and Program Team as appropriate.
- c. Quality goals which are applicable to each program and/or project contract and particular type of work will be defined by the Project Partner with agreement of the Engineer.

7. Quality Standards, Codes and Specifications

- a. Quality standards, codes and specifications must be defined during design and engineering by the engineering disciplines (infrastructure and civil works, system/MEP, rolling stock, operation and maintenance) for the different packages.
- b. The program will comply with all pre-defined international codes and standards which satisfies the requirements of ISO 9001:2015 and deliver a state-of-the-art BSTP.

8. Tender and Procurement

- a. Quality during tendering and procurement will be ensured by the following measures:
 - i. All tendering documents must fulfil the requirements of ISO 9001:2015.
 - ii. All program partners must be certified according to ISO 9001:2015. The certification must include the scope of services being provided to Bi-RIDE and include the specific project location.
 - iii. Basic quality requirements for all tendered parts must be defined (during design and construction) with documentation by engineering discipline (e.g. infrastructure and civil works, system/MEP, rolling stock, operation and maintenance).
 - iv. Define selection criteria based on selected capabilities and experiences.
 - v. Define pre-qualification in line with Bi-RIDE processes and procedures.
 - vi. Detailed quality requirements must be defined by program partners according to the complexity of their scope of supply (to be defined during procurement Process).
 - vii. Potential program partners must provide a provisional quality plan according to the complexity of their scope of supply (to be defined during procurement). This provisional quality plan must be submitted together with the bidding documents.
 - viii. Ongoing improvements of quality requirements (e.g. change of standards) by the Bi-RIDE program and potential program partners must be incorporated throughout the project lifecycle.
 - ix. Tendering documents must be approved by engineering discipline, where applicable (e.g. infrastructure and civil works, system/MEP, rolling stock, operation and maintenance).

9. Design and Engineering

- a. The contractor must define:
 - i. Design and engineering stages.

- ii. Review, verification and validation appropriate to each design and engineering stage.
- iii. Responsibilities and authorities for design and engineering.
- iv. Inputs, related to the contract requirements, must be defined as there are:
- v. Functional and performance requirements:
 - Applicable statutory and regulatory requirements.
 - When applicable, information derived from previous similar designs.
 - Other requirements essential for design and engineering.
- b. Design and engineering outputs must:
 - i. Define relevant standards, codes and specifications.
 - ii. Meet the project requirements.
 - iii. Define testing/inspection procedures as appropriate.
 - iv. Provide appropriate information and documentation (e.g. for purchasing,
 - v. Construction/production, testing, training, operation, maintenance etc.).
 - vi. Be reviewed at suitable stages by an independent Design Verification Engineer (DVE) in order to:
 - Evaluate the ability of the results or design and engineering to meet requirements.
 - Identify any problems and propose necessary actions.
- c. Design and engineering changes must be identified and records maintained
- d. Design and engineering changes must be reviewed, verified and validated as appropriate, and approved by DVE before implementation.
- e. Changes must be explicitly mentioned in order to highlight that the initial requirements have been altered.
- f. During testing phase special attention should be paid to changes (of scope or quality requirements) to the project.
- g. All defined quality relevant measures must be integrated in the contractor's Quality Management Plan (QMP).
- h. Design and engineering results must be checked, evaluated and validated by DVE before construction/production begins. These checks, evaluations and approvals must be documented and reported (communicated). The quality of the design work must be validated by the DVE at the end of the contract.

10. Construction

- a. To ensure adequate quality planning during the construction phase the following measures are foreseen:
 - i. Program Partners must have a validated QMP
 - ii. Copy of the contractor's current QMP
 - iii. Schedule showing all foreseen tests/inspections
 - iv. Schedule to perform audits in the contracted work
 - v. Procedure describing the handling of corrective action
 - vi. Procedure describing non-conforming items
 - vii. Process for continuous improvement.
- b. Program Partners must accomplish their work according to their validated QMP and have to:
 - i. Fulfil quality requirements.
 - ii. Accomplish the work according to the relevant standards, codes and specifications.
 - iii. Document and report the accomplished work.
 - iv. Train their personnel and assess their competencies.
 - v. Fulfil the requirements related to the contracted work.
 - vi. Perform and document planned tests/inspections.
 - vii. Deliver as-built-drawings to Bi-RIDE.
 - viii. Demonstrate the traceability of all quality relevant issues.
 - ix. Preserve products.
 - x. Control the monitoring and measuring equipment, including documentation.

- xi. Perform and document internal audits.
- xii. Handle non-conformities according to the related procedure. Nonconformities must be demonstrated to Bi-RIDE propositions/solutions resulting from nonconformities
- xiii. Carry out a continuous improvement (corrective and preventive action) with documentation. Solutions resulting from the continuous improvement process must be analysed
- c. The Engineer will, as regularly as deemed appropriate, monitor work samples with a frequency to ensure quality:
 - i. By inspecting the contractor's work on site.
 - ii. Verify the contractor's work according to the QMP.
 - iii. Perform and document planned tests/inspections.
 - iv. Verify the as-built-drawings of the contractor.
 - v. Analyse and approve changes within the contract.
 - vi. Pay special attention to project changes (scope or requirements) during test phase.
 - vii. Perform internal audits for each applicable contract.
 - viii. Analyse non-conformities with the contractor and approve solutions.
 - ix. Analyse solutions resulting from the continuous improvement process of the contractor within the contract and approve them.
 - x. Testing
- d. To ensure adequate quality planning during the test phase the following measures are foreseen:
 - i. Involving of end-user
 - ii. Organisation of test performance
 - iii. Definition of test results
 - iv. Test scheduling
 - v. Definition of any quality procedures during test performance
 - vi. Training of personnel, as required
 - vii. Test documentation.
- e. Performing quality assurance during the testing phase will be guaranteed by the following measures:
 - i. Definition of functions
 - ii. Observance and fitting of new designed functions with documentation
 - iii. Observance and fitting of functions which caused problems during design and
 - iv. Engineering or construction phase with documentation
 - v. Observance and fitting of functions which have been changed or optimised during design and engineering or construction phase with documentation
 - vi. Testing documentation in general.
- f. Bi-RIDE contracts complete packages. These packages consist in detail engineering, construction / production, quality planning, assurance and control and at last quality verification.
- g. Bi-RIDE requires the fulfilment of the Bi-RIDE Quality Policy, the quality objectives and the project quality plan(s) throughout the lifecycle of the contracted work.

11. Commissioning and Handover

- a. To ensure adequate quality planning during the commissioning and handover phase the following measures are foreseen:
 - i. Involving of end-user
 - ii. Organisation of commissioning procedures
 - iii. Definition of commissioning results
 - iv. Commissioning scheduling
 - v. Definition of specific quality procedures for commissioning process
 - vi. Training of personnel
 - vii. Commissioning documentation

- viii. As-built-drawings must be prepared and supplied upon completion.
- b. To ensure adequate quality assurance during the commissioning and handover process a number of measures have to be foreseen. These measures include, but are not limited to a general check of project, project packages and interfaces, including check of:
 - i. Documentation
 - ii. Materials
 - iii. Buildings and installations
 - iv. Electrical equipment
 - v. HVAC equipment (all building services)
 - vi. Earthworks
 - vii. Concrete works
 - viii. Structural works
 - ix. Waterproofing
 - x. Painting and coating
 - xi. Operation processes and procedures
 - xii. Training processes
 - xiii. Regular testing and inspection processes and equipment
 - xiv. Emergency and escape procedures and equipment.

12. Operations and Maintenance

- a. Quality planning during operation and maintenance will be guaranteed by adopting the following measures:
 - i. Operation ability must be demonstrated and documented.
 - ii. Operating rules must be defined.
 - iii. Roles and responsibilities must be defined.
 - iv. Operation personnel must be trained, including the certification of the trainees.
 - v. New personnel must be trained according to the job-requirements before starting. Fulfilling of the job-requirements must be demonstrated and documented.
 - vi. All training measures must be planned.
 - vii. Required, adequate documentation (operation and maintenance manual) must be available.
 - viii. Inspections must be planned.
 - ix. Precautionary maintenance must be planned.
 - x. Inspection and maintenance personnel must be trained.
 - xi. Inspection and maintenance tools must be available.
 - xii. Spare parts must be available.
 - xiii. Inspection and maintenance documentation must be available.
 - xiv. Operation and maintenance procedures must be defined.
- b. To ensure adequate quality assurance during operation and maintenance the following measures are foreseen:
 - i. Operational ability procedure
 - ii. Personnel training documentation and planning procedure
 - iii. Inspection planning and documentation procedure
 - iv. Maintenance planning and documentation procedure.

13. Training

- a. To ensure adequate quality planning for the training the following measures are foreseen:
 - i. Operation personnel must be trained according to a pre-defined training schedule with demonstration of the fulfilling (e.g. examination, depending on the job description) of the requirements.

- ii. Inspection and maintenance personnel must be trained according to a pre-defined training schedule with demonstration of the fulfilling (e.g. examination, depending on the job description) of the requirements.
- iii. New personnel must be trained according to the job requirements before starting. Fulfilling of the job requirements (e.g. examination, depending on the job description) must be demonstrated and documented.
- b. To ensure adequate quality assurance for the training the following measures are foreseen:
 - i. Personnel ability procedure
 - ii. Personnel training documentation and planning procedure.

14. Closing

- a. To ensure adequate quality planning for the closing process of the contract the following measures are foreseen:
 - i. Operation ability must be demonstrated over a pre-defined period
 - ii. Tests and inspections must be finished and documented
 - iii. Personnel must be trained.
- b. To ensure adequate quality assurance for the closing of the project all previous quality planning, assurance and control measures must be closed. Therefore, all project elements must be checked to ensure the required documentation is available and handed over to Bi-RIDE. For example:
 - i. Tendering and Procurement
 - ii. Contracting
 - iii. Design and Engineering
 - iv. Construction
 - v. Testing
 - vi. Commissioning and Handover
 - vii. Operation and Maintenance
 - viii. Training.
- c. A completion list will be implemented and all missing documentation must be compiled within an adequate timeframe. The contract will be closed when Bi-RIDE gives a written confirmation of the final acceptance of all deliverables before handover to the operator.

15. Quality Surveillance, Non-Conformities and Improvement

- a. The Quality Manager (QM) must conduct internal audits at planned intervals to determine whether the QMP:
 - i. Conforms to the planned arrangements and to the requirements of Bi-RIDE
 - ii. Is effectively implemented and maintained.
- b. An audit program must be planned, taking into consideration the status and importance of the processes and areas to be audited, as well as the results of previous audits. The audit criteria, scope, frequency and methods must be defined. An audit schedule must be prepared.
- c. If non-conforming project execution is detected the following measures are required:
 - i. Take action to eliminate the detected non-conformity
 - ii. Authorise its use, release or acceptance under concession by a relevant authority
 - iii. and, where applicable, by Bi-RIDE
 - iv. Take action to preclude its original use or application
 - v. Take action appropriate to the effects or potential effects of the non-conformity, if the non-conforming project execution is detected after beginning of operation.
- d. When non-conforming project execution is corrected it must be subject to re-verification to demonstrate conformity to the requirements.

- e. Records on the nature of non-conformities and any subsequent actions taken, including concessions obtained must be maintained.
- f. The QM must continually improve the effectiveness of the QMS through the use of the quality policy, quality objectives, audit results, analysis of data, corrective and preventive actions and project quality reviews.
- g. The QM must take action to eliminate the causes of non-conformities in order to prevent recurrence. Corrective actions must be appropriate to the effects of the nonconformities encountered and include, but are not limited to:
 - i. Reviewing non-conformities
 - ii. Establish the causes of non-conformities
 - iii. Evaluating the need for action to ensure that non-conformities do not recur
 - iv. Assessing and implementing corrective action
 - v. Recording the results of action taken
 - vi. Reviewing the effectiveness of the corrective action taken.
- h. The QM must determine action to eliminate the causes of potential nonconformities in order to prevent their occurrence. Preventive actions must be appropriate to the effects of the potential problems, at least:
 - i. State potential non-conformities and their causes
 - ii. Evaluating the need for action to prevent occurrence of non-conformities
 - iii. Set and implement the needed action
 - iv. Records of results of action taken
 - v. Reviewing the effectiveness of preventive action taken.

16. Quality Monitoring and Reporting

- a. To ensure the effectiveness of the quality monitoring and reporting Bi-RIDE will implement a quality committee who will meet regularly. This quality committee will analyse and report to the management team of the Bi-RIDE program the following matters at least (not limited to the list below):
 - i. Minutes of the previous meeting/review of pending actions and decisions
 - ii. Quality key issues
 - iii. Project status
 - iv. Project documentation and reporting
 - v. Inspection and testing
 - vi. Surveillance
 - vii. Non-conformities and improvement
 - viii. Audits
 - ix. Next meeting

Appendix-IV - Organisation Chart and Key Positions

The Contractor shall provide the following organization chart for the Works as follows:

1) Head office Organization Chart

One organization chart shall be provided for the Contractor head office indicating the management and staff structure, with responsible personnel/departments described for all aspects of the work.

2) Site organization Chart

The Contractor shall provide the proposed site organization indicating the proposed structure, staff partners and positions necessary to adequately manage and control the Works.

The Contractor shall have a competent team of Managers, Engineers, Technical staff etc. so as to complete the work satisfactorily as per various requirements of the contract.

Key positions (not limited to) and corresponding qualification and experience are as under

Sl. No	DESIGNATION	QUALIFICATION	EXPERIENCE LEVEL (FOR SIMILAR WORKS)	MIN. NO. REQUIRED
1	Project Manager (Team Leader)	Bachelor's Degree/Post Graduate Degree in Civil Engineer	Minimum 18 years total experience and 5-year experience in the role of Project Manager in the execution of similar type of work	1
2	Deputy Project Manager/ Construction Manager	Bachelor's Degree in Civil Engineer	Minimum 15 years total experience and 5-year experience in the role of Construction Manager in the execution of similar type of work.	1
3	Design manager	Post Graduate Degree/ Bachelor's Degree in Structural Engineer	Minimum 15 years total experience and 5-year experience in the role of Design Manager in the execution of similar type of work	1
4	QA & QC Manager.	Bachelor's Degree in Mechanical Engineer	Minimum 12 years total experience and 8-year experience in execution of similar type of work.	1
5	Chief Safety and Health Manager	Bachelor's Degree in Civil Engineer & Diploma in Safety Course.	Minimum 8 years total experience and 3-year experience in the role of Chief Safety and Health Manager in the execution of similar type of work.	1
6	Geotechnical Engineer	Bachelor's Degree in Civil/ Geotechnical Engineer	Minimum 8 years total experience and 3-year experience in the role of Geotechnical Engineer in the execution of similar type of work.	1
7	Billing Engineer/ Quantity Surveyor.	Graduate / Diploma in Civil Engineering	Total minimum experience of 5 years with knowledge of computer applications for Degree and 8 years for Diploma with knowledge of Computer applications.	1
8	Senior Civil Engineer	Bachelor's Degree in Civil Engineer	Total minimum 7 Years for graduate & 10 years for Diploma in relevant field.	5

NOTES:

1. The above categories of key positions shall be minimum required for successful completion of the work which shall be deployed at different points of time as per the progress and requirement of work and may not be required to deploy simultaneously and continuously. However, these personnel shall be deployed at site in advance as

per requirement and as directed by the Engineer and the decision of Engineer in this regard shall be final and binding. The above Manpower deployment plan shall be submitted by the contractor within the 14 days of award of work and shall be approved by Engineer in charge / Employer.

2. The Contractor shall submit the CVs of the above key positions to Engineer for his approval within 28 days of issue of letter of Acceptance (LOA).
3. The contractor shall deploy resources as per the above-mentioned minimum requirement and also confirm to deploy manpower over and above the minimum numbers indicated above, if the work requires so.
4. The performance of project personnel deployed will be evaluated periodically by Employer during the contract period. In case the performance of any of the project personnel is not satisfactory, the Contractor shall replace them with better or equivalent personnel immediately as per directions of the Engineer.
5. Tenderer may propose any number of names of Personnel for each Key Position. Any of the proposed personnel as approved by the Employer for each key position have to be mandatorily deployed in case of award of work.
6. Non-deployment of the Key personnel as per approved personnel for Sl.no 1, 2, 3, 4 & 5 as per approved manpower plan leads to imposition of Penalty of Rs 2,00,000 /- Per Key personnel per month. For other personnel, a penalty of Rs. 50,000/- per person per month shall be levied.
7. The proposed Key personnel are not to be changed till the completion of the work. Under emergent circumstances, in case they are required to be changed, the new incumbent should have similar or better experience and qualification than as required above. These changes are permitted only with the approval of the Employer. Change in key personnel for one time without penalty is permitted. However, for subsequent changes there will be Penalty at Rs 2,00,000 /- Per Key personnel for Sl.no 1, 2, 3, 4 & 5.
8. All Key Personnel must be permanently stationed at Bangalore till the completion of the work.
9. The penalties imposed are non-refundable.

Appendix-V - Plant and Equipment

The Tenderer or JV as a whole must deploy the minimum required Contractor's Equipment for the Works as given below.

S. No.	Type of equipment required for the work.	Minimum No. of Units of equipment required for the work	Remarks
1	Piling Equipment Rotary Rig/Hydraulic Rig for soil boring and rock boring including diamond bits for rock boring.	2nos	
2	Piling rig (Tripod) with conventional winch	2nos	
3	Fully Automatic and Computerized Batching Plant -1 Nos. (1 of 30 Cum/h) minimum or equivalent capacity in different configuration at casting yard with a RO of suitable capacity for proper quality of water.	1nos	
4	Concrete boom placers	1nos	
5	Concrete pumps with sufficient pipes	2nos	
6	Transit Mixtures	5nos	
7	Pile cap Shutters	5set	
8	Pier and pier cap Shutter, staging and supporting arrangement for all type of Piers	6set	
9	Pre cast pre-tension I Girder Beds along with necessary shutter and support arrangements	5 Beds with Shutters	
10	250 MT or more capacity suitable cranes for erection of I Girders / RCC Portals, super structures of ROB/RUB	1nos	
11	Cranes in casting yard/site of suitable capacity	2nos	
12	Trailers for carrying I Girders/Pier caps and other Precast elements of Suitable capacity as per site requirement	1nos	
13	Man-lift for adequate height	2nos	
14	Crash Barriers & Friction slab Shutters	4sets	
	Road work, Embankment and cutting works.		
15	Hydraulic excavator (1 cum bucket)	2nos	
16	Tippers/trucks (10 cum capacity)	5nos	
17	Crane 5 MT capacity	2nos	
18	Crane 35 MT capacity	2nos	
19	Generators 125 KVA	1nos	
20	Vibratory roller 8-ton capacity	1nos	
21	Smooth wheeled roller 8-ton capacity	1nos	
22	Pneumatic road roller	1nos	
23	Tandem road roller	1nos	
24	Water tanker of 6000 lit capacity	2nos	
25	Grader	1nos	
26	Plate Vibratory Roller	1nos	
27	Slope Compactor Roller	1nos	
28	Survey equipment's: Total stations and auto level	2set	

Notes:

- The Tenderer shall undertake to deploy sufficient resources to carry out the Works. These resources are for peak period of each activity and shall be mobilised by the Contractor to suit his works programme.
- If the Contractor opts for short line method for casting, the number of pre-cast bed shall be increased accordingly.
- The Contractor's Equipment shall not be more than five years old reckoned from the date of original manufacture.
- Hiring of Cranes shall be as per approved vendors for supply of cranes. The contractors are free to propose and utilize plant and machinery after getting approval from the Engineer. Third party certification of cranes, competency certification of the operators etc. would be required before grant of approval.
- Deleted
- The proposed Contractor's Equipment shall not in any event be construed as a submission of final requirement for the Works.

- vii. Plant and equipment indicated above is minimum to be deployed at appropriate stage of the work. However, depending on the requirement to complete the work within the stipulated completion period the Tenderer shall deploy additional machinery as circumstances warrant at no extra cost. Plant and machinery above shall not be older than 5years. In case of failure of any plant and machinery deployed at site the same shall be repaired/replaced within 7days from the time of failure.
- viii. Tenderer shall submit the copies of ownership of the equipment, In case of hire / purchase, Copies of MOU with the supplier/ owner of the equipment.
- ix. *Contractor shall be penalized as deemed fit.
- x. The above type of plant and equipment (but not limited to) may be required for execution of the work. The contractor shall submit the details of plant & equipment to be deployed in the above table within 28 days of issue of LOA to the Engineer for approval.
- xi. Deleted.
- xii. Deleted.

Appendix – VI – Office Accommodation, Equipment and Personnel

- 1 Accommodations for the Employer & Engineer (earmarked separately) with sufficient natural light & ventilation with the layouts, designs, materials, appliances, personnel etc. approved by Engineer / Employer.
- 1.1 The contractor shall provide the following offices within the time limits specified (Refer details of Penalty*, in case of delay beyond the limits):
 - 1.1.1 Project office accommodation of at least 100 Sqm (with at least 30% of specific area decided by the Employer, air-conditioned) spread across 1 Project Offices (the minimum number mentioned in the scope) for the Employer & Engineer with air-conditioned cabins for senior officials of Employer and Engineer (as decided by the Employer) and conference halls, as per the approved drawings. Project Office shall have separate areas/buildings ear marked for Employer & Engineer, as approved by the Employer. Distribution and periodical redistribution of the above area in different offices will be done by the Employer as per the need.
 - 1.1.2 Deleted.
 - 1.2 Deleted.
 - 1.3 Deleted.
 - 1.4 Small or teensy-weensy, cramped, grungy, shabby, dribbling, shoddy sheds / cabins with temporary / inferior materials / furnishings will not be allowed as project/site offices, even temporarily.
 - 1.5 The following specifications shall be followed for various items of the Project / Site office earmarked for Employer/Engineer. All the requirements mentioned above and below are minimum requirements and shall be complied with. These are not exhaustive and any associated specification for any other relevant item can be specified by the Engineer / Employer. Superior specifications / materials than those specified can be used with the approval of Engineer / Employer.
 - i. False Ceiling:
 - a. GI-powder coated (T & L) grid system and high-density fiber reinforced Cement board of approved brand, texture, colour & quality of size (1200 x 1200) mm, 6mm thick are having density of 1250 Kg / m3 conforming to ASTM-E84, ISI 14862-2004, respectively
 - ii. Doors:
 - a. 2.1 m X 1.2 m Teak wood door – (Main Door); Brass Fittings; PVC Doors or any other approved doors for toilets
 - b. Doors of approved material shall be provided for the cabins of various senior officials of Employer & Engineer and for the conference hall.
 - iii. Windows:
 - a. UPVC / Aluminium windows 3 track Sliding windows with M.S grill; frames with metal mosquito nets (gap-less) in one track
 - iv. Tiles:
 - a. Vitrified tiles (Scratch Proof) / Wooden flooring of approved brand & quality for office cabins & common rooms; Antiskid tiles of approved brand & quality for the floors of bathrooms
 - v. Toilets, Plumbing & Sanitary ware:

CPVC pipes for internal work and PVC pipes for outer walls (2.5" PVC pipes)

All Fittings shall be of ISI standard. Ceramic Fittings of approved brand & quality shall be provided for all sanitary ware of washrooms & washbasins. All plumbing fittings, doors, handles etc., shall be of approved brand & quality.

Attached washrooms with one wash basin with pedestal (or wall mounted) and a platform and one wall mounted EWC shall be provided for at least four cabins and for conference hall in each Project Office and for at least two cabins in each Site Office. The Employer may redistribute the above as per the requirement. In addition, at least one common toilet each with at least four urinals

for men and at least two EWCs shall be provided near the common area in each Project Office. In addition, one exclusive toilet with one washbasin and one EWC shall be provided for Female staff in each Project Office / Site office. At least one attached washroom with one wash basin and one EWC shall be provided in one cabin in each Site office. At least one common toilet with at least two urinals and at least two EWCs shall be provided in each Site Office. In addition, one separate toilet (outside the building) with one washbasin and at least one IWC shall be provided in each Project Office and each Site Office for assistants, office boys site attendants, drivers, mechanics, cleaning staff etc. By all means, uninterrupted clean water supply shall be ensured in all these toilets for all the 24 hours till the end of DLP. Hand wash of approved quality shall be available on all wash basins and it shall be recouped as and when required. Hand towels of approved quality and colour shall be available on a towel rod / hanger near all wash basins and the same shall be got washed once in every 2-3 days, depending on the need. They shall be replaced as and when necessary.

All project offices / site offices and their premises and all the toilets (attached, common and outside) shall be maintained in a clean and hygienic condition by deploying dedicated staff for this purpose. The cleaning of all the toilets shall be done frequently (common toilets - once in about 2-3 hours). The exact frequency of cleaning of each toilet will be specified by the Employer based on the need in each Project office / Site office and the same shall be meticulously followed.

All the toilets shall be provided with mosquito nets and efficient & noise-less exhaust fans. The nets shall be periodically checked for any gaps, holes etc., through which mosquitoes can enter and the nets shall be always maintained hole-free and gap-free. The exhaust fans shall be always maintained in proper working condition.

The dimensions of toilets and disposition of openings and fittings shall be at least in accordance with the anthropometric data as per the relevant IS code(s).

vi. Electrical Wiring:

- a. Concealed wiring with fire proof cables of IS standard, as directed, with approved materials

vii. Electrical Fittings & Appliances:

- a. Switches, fans, split type air conditioners of required tonnage (to suit the cabin concerned or the conference hall) and fluorescent ceiling lamps (LED / CFL) of sufficient lumen of approved brand, lumen & quality.
- b. The outer units of split type air conditioners shall be sufficiently away from the cabins or conference halls, as approved by the Employer, so that the noise is not audible to the officials

viii. Painting:

Inside: primer one coat +2 coats of emulsion paint of approved brand and colour. Outside: 1 coat primer+2 coats of weather proof paint of approved brand and colour.

ix. Others:

- a. Overhead water tanks with sufficient Head of water to ensure the required velocity for water supply; Septic tanks authorised connection to public sewerage system

x. Networking:

- a. Wiring with CAT6E cable or superior, with switches and router connector point as per the approved Plan.

xi. Intercom: A system of intercom telephones, as specified and approved

1.6 The contractor shall provide at least the following furniture / facilities in each project office and site office for the use of Employer and Engineer:

- a. Manager's Premium tables of approved brand, colour, texture, height & quality: size at least 5'x3' L-table with side cadenza complete with laminate finish – as per the requirement.
- b. Executive Tables of approved brand, colour, texture, height & quality: size at least 4'x3' table with side cadenza complete with laminate finish – as per the requirement.

- c. Conference Tables (20' x 6' approx.) of approved brand, colour, texture, height & quality with conference chairs: for 20 - person seating - as per the requirement.
- d. Workstations of approved brand, colour, texture & quality with partitions up to the approved height: size 4'x 5'. Modular workstations green ply makes with merino Laminate and storage cabinets - in least 8 nos. as per the requirement.
- e. Workstations of approved brand, colour, texture & quality with partitions up to the approved height: Modular size 4'x3' straight workstation with partition and storage. Cabinets under the working counter as per the approved plan- as per the requirement.
- f. High back High quality revolving Executive chairs of approved brand, colour, texture & quality with tilt able neck rest and adjustable hand rests (adjustable in 3 dimensions) and with fabric finish - as per the requirement.
- g. Medium back revolving chairs with hand rests of approved brand, colour & texture and quality with FRP finish- as per the requirement.
- h. Low back revolving chairs of approved brand and quality with FRP finish - as per the requirement.
- i. White magnetic boards and pin boards in each room/work stations, white board with stand & 4 white board markers of approved colours (to be recouped as and when needed) and one LED TV of 55 inch (LG, Samsung, Sony make) of approved size, brand and quality for projecting the presentations for conference room (for each Project Office).
- j. Racks & shelves as per the requirement in all chambers and common area, as approved.
- k. Supplying, erection, testing and commissioning of Off-Line UPS system suitable for operation with all accessories on sufficient power back up (with minimum backup time of 2 hours) including 12V DC, AH Batteries in polypropylene container for UPS low maintenance tubular batteries, to meet the power load in case of power disruption (for project office). The system should be able to feed the power to all the desktop computers, printers etc. for at least 4 hours continuously.
- l. Split type air-conditioners of approved make and quality - as per the requirement.

In addition, the contractor shall provide the following for each Project/Site Office:

- a. Telephones, intercom & High-speed Broad Band Connection - 2 Land line connections + 10-line intercom with instruments & Broad Band Connection.
- b. Digital colors Photocopy Machine (Up to A3 size)- 01 no. of approved brand & quality
- c. Refrigerator (290 Litre capacity) - 01 no. of approved brand & quality
- d. Microwave oven – 02 nos. of approved brand & quality
- e. Drinking Water Dispenser (Hot, Cold & Normal) - 01 no. of approved brand & quality
- f. Standby DG Power - As required, to run and maintain the office for at least 6 hours.
- g. Safety Helmets, Boots, and any other safety device - as per Requirement to be specified by the Employer / Engineer.

NOTES:

Though the above requirement of furniture and others is mentioned for each office, Engineer / Employer may redistribute the total requirement as per the need of each quarter or earlier. Transporting the same from / to each project / site office each quarter or earlier, based on need, forms a part of the scope of the work. The sizes of a few tables, side racks etc. may be more or a little different from the sizes mentioned above, to suit the layout. The decision of the Employer is final in this regard.

In addition to the above, the following furniture, appliances, equipment, and tools are required combined for all the project/site offices (This is additional requirement for all the offices. Distribution and periodical redistribution of these to various Project & Site offices will be done by the Employer, as per the need). Employer may alter the specifications depending on market availability, requirement and other site considerations etc.

- h. Side units with table - 30 sets
- ii. Filing cabinet (36 lockers unit) – 15 nos.
- iii. Lockers cabinet (36 lockers unit) – 12 nos. iv. Steel Cupboard - 12 nos.

- iv. Digital Camera – 01 No.
 - v. Crockery including cups and saucers – 50 sets.
- 1.7 The contractor is required to maintain the offices till the end of DLP and to provide the following (but not limited to):
- i. Timely pay all electricity/phone/water/high-speed Broad band charges (A nominated staff member of the contractor shall take care of timely payment without being reminded.)
 - ii. Timely provide all stationery items and consumables for office use and keep a reserve, as approved (A nominated staff member of the contractor shall take care of them and ensure reserve supplies.)
 - iii. Carry out all necessary repairs to office, equipment, appliances, toilet fittings immediately, as and when required, without any delay (A nominated staff member of the contractor shall daily inspect all of them and identify any problem and undertake repairs, even without being told.)
 - iv. Provide mineral water bottles as per the daily consumption of the staff (A nominated staff member of the contractor shall take care of them and ensure reserve supplies.)
 - v. Provide fully functional pantry for supply of with all utensils and equipment necessary for supply of tea, coffee, snacks, sanitizers, tissue papers etc., as per the requirement on daily basis and during late evening/early morning/night working etc. (A nominated staff member of the contractor shall take care of them, without any delay.)
 - vi. Arrange proper and safe conveyance (through four wheelers engaged for this purpose) to female staff working for Employer/Engineer, whenever the work gets delayed and whenever the situation warrants (as decided by the Employer) - (A nominated staff member of the contractor shall take care of them.)
- 1.8 Fire extinguishers shall be provided as per the recommendations of the Bengaluru City Fire Brigade.
- 1.9 Deleted.
- 1.10 The contractor shall provide, erect, and maintain appropriate name boards, as specified, with approved materials, for each of the offices and cabins. The material of each name board, font size, font type, spellings etc. on each name board and their locations shall be as approved by the Employer before they are erected.
- 1.11 The contractor shall supply the following personnel within 30 days from the date of issue of LOA for the use of the Employer, till the end of DLP.
- a) Watchmen: Round the clock at each Project / Site office
 - b) Computer operator / Data entry operator: 01 nos.
 - c) Office boy cum Site attendant: 02 nos.

The candidature of all the above personnel shall be as personally approved by the Engineer / Employer. Any inefficient / problematic personnel shall be replaced forthwith. The qualifications, expertise, allotment of work, working time, shifts, overlap time, grouping, seating arrangement and any other related matter will be as decided by the Employer. The decision of the Engineer / Employer is final in all these regards. Proper approved safety equipment shall be provided for the site attendants.

2 **Equipment for the use of Engineer and Employer:**

The contractor shall provide the following new equipment and software at each Project office as listed and maintain them for the exclusive use of the Employer and the Engineer till the end of DLP (**The distribution will be done by the Employer**):

- (a) Desktop Computers (with computer tables) – 02 nos. of approved brand & quality with cordless keyboards and cordless mice, as approved by the Employer. The computers shall be Intel core i7 or its latest generic descendent or higher, running at the specified and approved clock rate (Hyper technology) with no wait state, If the Central Processing Unit has no floating-point arithmetic capabilities, a math-coprocessor shall be installed.

A minimum of 1TB (SSD) 5400RPM 16GB RAM with software configurable into extended memory and expanded memory. The expanded memory shall be one combo drive (DVD, R / CD RW), (7200 RPM); 27" colors monitor - 04 nos. and 22" colors monitor - 02 nos.

- (b) Lap Top Computers with carry cases – 1 nos. of approved brand & quality – with at least 15.6" display, as approved by the Employer.

Both the desktop & laptop computers shall at least have the following specifications:

1. Processor: Intel core i7 or higher, 5.0 GHz (hyper technology) with in-built LAN, Modem, AGP card, Audio Card, and Wi-Fi Internet Card.
 - i. Cache Memory: 512 KB L2 cache
 - ii. Memory: 16GB DDR RAM Expandable up to 32GB
 - iii. Hard Disk: 1 TB or at least 500 GB - preferably SSD
2. At least 1920 X 1080 resolution, S3 VIRGE MX 3D Graphics Controller Chip, 64 Bit Graphics Accelerator, Bit BLT hardware
3. Pointing Device: 102 multimedia Keyboard Acupoint Point Device
4. Ports: 1 Parallel, 1 Serial, at least 2 USB Ports, PS I 2 Mouse I Keyboard, SVGA Video Port, Line in Jack, Headphone & External Microphone Jack, 1 Serial Infrared Port, USB port with Wi-Fi LAN.
5. Card Bus: 2 x PCMC1A Slots (Type II) or 1 x PCMC1A Slot (Type III) Card Bus ready.
6. Battery I Power: AC Adaptor I Li-Lon rechargeable battery with built in battery charger & Software Power Management.
7. OS I Software: Pre-installed Windows 11 professional or Mac OS as approved, latest version of MS office, Windows Utilities, Mediamatics Arcade Pak, Diagnostic Utilities, Ring Central, MS Internet Explorer, Norton Anti-Virus, Speech activated typing software, latest version of Primavera (as approved).
8. Communication: 56 Kbps Integrated Fix I data Modem with V.90 support; Speakers
9. Carrying Case: Laptop carrying cases (for all the Lap top computers) of approved brand and quality.

NOTE: Recoupment of batteries of cordless keyboards and mice, as per the requirement, are included in the scope.

- (c) Printers – 01 nos. (A4 and A3 size)

- (d) Languages:

Python (latest version), Java and any other language as directed by the Engineer.

Application Software:

- (i) Microsoft office, latest release
 - (ii) A database management package as approved by the Employer
 - (iii) Latest licensed version of AUTOCAD Civil 3-D.
- (e) Project Management Package (Primavera V. P6-2 licenses (1 Core Module and 1 Web based Module), as approved Multimedia, as approved
- (f) UPS system with sufficient power backup (with minimum backup time of 2 hrs.) to meet the power load in case of power disruption.
- (g) Surge Protection Devices (one for each computer and printer as given above) Power supply for the systems is to be AC 240 volts, 50 Hz from normal building wiring circuit mains, Power regulator, stabilizer or transformer should be supplied by the contractor for the computer systems such that the systems can function efficiently.
- (i) Four mice with cord (not cordless) for standby purpose.

NOTE: Though the above requirement of computers and others is mentioned for each office, Engineer / Employer may redistribute the total requirement as per the need in each quarter or earlier and transporting and reinstalling the equipment from / to each project / site office each quarter or earlier, based on need, forms a part of the scope of the work.

NOTES:

- a. The items under Clause 2.0 above can be retained by contractor (except 2.0 (e)-Application Software) after the completion of the project / DLP, as specified.
- b. The tenderer is supposed to take all the above requirements and the above retention clause into account while quoting the price. The above requirements are for effective execution and close monitoring of the progress and quality of work and the all the conditions and provisions will be enforced in letter and spirit.

Details of Penalty*, in case of delay beyond the limits):

3 Documentation

- 3.1 A complete set of documentation will be supplied with each System. The documentation should be self-tutorial in nature and be readily understood by non-computer personnel.

The following manuals shall be supplied with the system:

- a. Manual on how to operate the equipment; and
- b. Manual on how to use the facilities and software provided by the supplier. (Including languages and utilities)

4 Auto CAD Operator:

The contractor shall provide one sufficiently experienced Auto CAD operator with a separate desk top computer, 27" monitor, computer table, computer chair, keyboard, mouse and all other relevant items and software including licensed version of latest Auto CAD software exclusively for the Engineer till six months beyond the date of completion of contract. This is in addition to the requirement of CAD operators specified earlier. The candidature of the above personnel shall be as approved by the Employer.

Appendix VII - Document Submission and Response Procedure

1 Project Management Information System (PMIS)

The Contractor shall utilize a PMIS integrating with BIM software such that all documents generated by the Contractor can be transmitted to the Engineer by electronic means (and vice versa) and that all documents generated by either party are electronically captured at the point of origin and can be reproduced later, electronically and in hard copy. A similar link shall also be provided between the Engineer office at site and the Employer's Office by the Contractor. Make or standard of PMIS shall be as directed by Employer.

IFC format (Industry foundation Classes)

IFC list format is a platform neutral format. Hence all / any BIM program used by tenderer should provide files in IFC format for interoperability between different BIM programs.

2 Submissions To the Engineer

The general requirements are as follows:

2.1 Project Management Information System (PMIS)

- 1) The Employer shall provide a web-based information management system of transmittal for formal project correspondence, documents and information to ensure efficient information management on the Project. Where it is necessary to transmit original signed documents, these shall be acceptable forms of correspondence only when they have been issued via the system first.
- 2) The Employer shall provide the Project-wide use of the system during the Design and Construction Phases and also the Defects Notification Periods.
- 3) The system shall be capable of issuing a list of outstanding responses from the Engineer 7 days before the due date of the response.

2.2 Drawing And Specification Register

The Contractor shall submit drawings and specifications register to the Engineer in electronic copy and hard copy with each submission of drawings and at an interval agreed by the Engineer. The drawings and specifications register shall be in a format submitted for review and agreed without objection by the Engineer and shall include each document reference number, version, date, title and data-filename.

2. Records And Reports

a) Format

Reports and records are to be submitted via the system to the Engineer and shall be in a format agreed by the Engineer. Reports and records shall be signed prior to submission by the Contractor's agent or by a representative authorized by the Contractor.

b) Project Document Control Procedure

Within twenty-eight (28) days after Commencement Date, the Contractor shall submit via the system a Project document control procedure to the Engineer for review, which shall include but not be limited to the following:

- 1) a document approval system which shall specify the level of authority for approval of all documents and material before submission to the Engineer;
- 2) a system of issuing documents to ensure that pertinent documents are issued to all appropriate locations;
- 3) a document change or re-issue system to ensure that only the latest revision of a document can be used; and
- 4) a submission identification system that identifies each submission uniquely by the following:
 - a) contract number;
 - b) discipline;
 - c) submission number; and
 - d) revision indicator.

c) Project Record

Project records will eventually be used by the Employer to manage, operate and maintain the Works after the completion of the Project under construction and for future reference.

d) Adequacy Of the Project Record

The Contractor shall submit the documents as required by the Engineer as Project records in full and on time. The Engineer shall determine the adequacy of the Project record.

3. Submission And Response Procedure**4.1 General**

Except where specific procedures are given for certain items, all submissions shall be submitted and reviewed according to the procedure laid down in the following clauses.

4.2 Proposal

Each submission shall be accompanied by a brief introduction to explain which sub-system, part or section of the Works to which the submission refers, listing the documents enclosed with the submission, and describing in outline how all relevant requirements of the Employer's Requirements are achieved by the proposals.

4.3 Submission Response Request

For each stage of submittal, the Contractor shall prepare a Submission Response Request (SRR) carrying the date of submission, the submission reference number as defined in Clause 2.2 (4) above, the submission title, the stage of submission (e.g., Technical Design, etc.), and the authorized signature of the Contractor's responsible engineer to confirm that, in the opinion of the Contractor, the submission:

- 1) Complies with all relevant requirements of the Employer's Requirements;
- 2) conforms to all interface requirements;
- 3) contains, or is based on auditable and proven or verified calculations or design criteria;
- 4) has been properly reviewed by the Contractor, according to the Contractor's Quality Assurance System, to confirm its completeness, accuracy, adequacy and validity; and
- 5) has taken account of all requirements for approval by statutory bodies or similar organizations, and that where required, such approvals have been granted.
- 6) contains 2 (two) properly signed copies of Independent Design Checker Certificate (Form IDCC) and 2 (two) properly signed copies of the Construction Design Pack Certificate (Form CDPC).

4.4 The Engineer's Response

The Engineer's response to all the submission from the Contractor will be made within 21 calendar days of receipt of the submission. If the submission is made later on the Design Submissions Programme, the Engineer may extend the review period depending on the amount of documentation accompanying the submission.

4.5 Monthly Design Review Meetings

Throughout each Design Stage, the Contractor shall attend monthly design review meetings with the Engineer. At these Engineer's review meetings, the Contractor shall present information, drawings and other documents to the Engineer in respect of all submissions programmed to occur during the following five-week period. The Contractor's presentations shall be in sufficient depth to enable the Engineer to obtain a clear understanding of the Contractor's proposals and to discuss the methodology and process used in reaching the proposed design solutions.

4.6 The Engineer's Observations

The Contractor shall record all of the Engineer's observations and any agreed actions resulting from the Engineer's review meeting and shall address each of these fully before submission of the respective documents for formal review.

4.7 Notification

If, in the Engineer's opinion, following receipt of a submission there is benefit to be gained from a meeting with the Contractor to clarify or discuss any of the contents of the submission, he will notify the Contractor accordingly with not less than 3 days' advance notice, and the Contractor shall attend at the time and place appointed by the Engineer.

4.8 Notice Of No Objection

The Contractor in respect of the Works or any sub-system, part or section may make no submission thereof unless a Notice of No Objection with Comments has been received for the previous stage of the same Works or any sub-system, part or section thereof.

5. Responed Procedure**5.1 Responed Procedures**

The Engineer will respond in one of the following three ways:

- 1) "Notice of Rejection" (with "A" Comments)
- 2) "Notice of No Objection"
- 3) "Notice of No Objection with Comments" (with "B" or/and "C" Comments)

5.2 Response Definition

Definition of the Engineer's response:

- 1) "Notice of Rejection" (with "A" Comments) if following his review of the submission, the Engineer discovers major non-compliance, discrepancies or omissions etc. that in his opinion are of a critical nature, the Engineer will issue a "Notice of Rejection" (NOR) with type "A" comments. The Contractor shall revise and Re-Submit within 15 calendar days of receipt of "Notice of Rejection" from the Engineer addressing the Engineer's comments. Subsequently the Engineer shall respond within 15 calendar days of receipt of the resubmission. Following the issue of a NOR by the Engineer the Contractor is not entitled to proceed to the next programmed stage for that section of the work until all of the Engineer's comments have been fully addressed and a NONO issued.
- 2) "Notice of No Objection" if following his review of the submission the Engineer has not discovered any non-compliance with the contract the Engineer will issue to the Contractor a formal "Notice of No Objection (NONO). A NONO from the Engineer irrespective of with or without comments does not in any way imply the Engineer's consent of the submission nor does it remove any responsibility from the Contractor for complying with the Contract. Issue of a NONO from the Engineer entitles the Contractor to proceed to the next stage of the programmed work.
- 3) "Notice of No Objection" (With Comments) if following his review of the submission the Engineer discovers discrepancies or omissions etc. that in his opinion are not of a critical nature the Engineer may issue a "Notice of Objection" with Comments, (NOWC) the comments will be of either type B or type C as defined below. The Contractor shall respond to the comments in accordance with the requirements of Clause 4.3. Following the issue of a NOWC by the Engineer the Contractor is entitled to proceed to the next stage of the programmed work subject to the inclusion of amendments necessary to address the comments.

6.0 The Contractor shall respond to Type B and C comments and get the Engineer agreement and closure prior to full inclusion in the Final Design.**6.1 The Engineer's Comments**

Definition of the Engineer's comments:

- 1) Type "A" Comments are of a critical nature that renders the submission non-compliant with the Contract, the submission shall be corrected and resubmitted.
- 2) Type "B" Comments are of an intermediate nature that shall be responded, agreed and incorporated.
- 3) Type "C" Comments are of a minor nature or may affect future submissions.

7 Records

The Contractor shall establish and maintain a place for the storage and archiving of all the documents relating to the Works and are not required to be submitted to the Engineer under Clause 2.

8 Implementation Of Bim System

(i) Civil Contractor shall implement BIM system for executing and delivering the services set out in this Agreement. Building Information Modelling (BIM) uses computing power and systems to create 3D models of all kind of buildings and infrastructure, with information about its design, operation and current condition. At the planning and design stage it enables designers, owners and users to work together to produce the best possible designs and to test them virtually before they are constructed. During construction, it enables Employer, contractors and suppliers to integrate all components cutting out waste and reducing the risk of errors. In operation it provides users with real-time information about available services and facility managers with accurate assessments of the condition of assets.

(ii) All station structure designs/proof checking shall be done using BIM modelling. Civil Contractor shall implement the necessary hardware, software and human resources towards this end. 3D Coordination between all disciplines shall be achieved by incorporating them in a single model.

(iii) Contractor shall be required to produce, update and present to Employer on a fortnightly basis an integrated 3D BIM model incorporating rail track (Viaduct), topography, architecture, structure, plumbing and all other building services and system wide requirements in design review meetings. These models shall be 3D rendered and shall help in design visualization and clash detection of elements as well as finalization of design.

In addition, Contractor shall also provide following individual models: -

1. Rail alignment Modelling
2. Structure design modelling
3. Terrainmodelling
4. Quantity take-off from BIM model wherever required
5. Visualization and Animated Walk through
6. Clash detection

(iv) Final coordinated GFC drawings of all disciplines shall only be generated from the BIM model.

(v) The contractor shall develop as built" BIM Model up to LOD 500 level and submit the same to Employer at the time of completion of the project. Schedule of BIM implementation Plan and standards to be adhered to, shall be provided after award of contract.

(vi) **IFC format (Industry foundation Classes)**

IFC list format is a platform neutral format. Hence all / any BIM program used by tenderer should provide files in IFC format for interoperability between different BIM programs.

Appendix VIII - Drawing List

Deleted

Appendix-IX - Work Areas

No land shall be made available by the Employer for casting yard, site offices, and site laboratories. Contractor shall make his own arrangements at his own cost. In case, the Railway land / Govt. land is available adjacent to railway track for contractor's temporary construction use / enabling works yard, the necessary land rent / lease charges shall be levied as advised by Railway concerned / Govt. authority norms / Bi-RIDE norms and the same will deducted from IPC 's of the Contractor.

Appendix-X - Works Areas & Temporary Power Supply

1. Introduction

- (1) The Contractor shall provide within the designated principal Works Areas, at locations agreed with the Engineer, the compounds and facilities for the Engineer and other contractors of the Employer defined under Clause 2 of this Appendix.
- (2) The standard conditions applying to the use of any Works Area by the Contractor for its site facilities are given under Clause 2 of this Appendix.
- (3) The Conditions for supply of electricity by the Contractor to Designated Contractors are given under Clause 3 of this Appendix.

2. Standard Engineering Conditions

The following standard engineering conditions apply to all Works Areas:

- (1) Formation
 - (a) The Works Areas shall be formed to the levels that the Engineer has given his consent. No such levels shall be amended without prior consent of the Engineer.
 - (b) The Works Areas shall be surfaced in a manner agreed with the Engineer, compatible with their intended use, and, in particular, footpaths and roadways connecting facilities shall be clearly defined. Measures shall be taken to the satisfaction of the Engineer to ensure all areas are properly drained and kept free of static water.
 - (c) The removal, diversion or reinstatement elsewhere as may be required of any existing works or installation whatsoever within the Works Areas shall be carried out to the satisfaction of the Engineer.
- (2) Roads & Parking
 - (a) Space shall be provided within the Works Areas for parking, loading / unloading and maneuvering of motor vehicles.
 - (b) Any damage done to the adjoining public roads and fixtures and properties (public or private) shall be made good to the satisfaction of the Engineer.
- (3) Drainage & Sewerage
 - (a) All storm or rainwater from the Works Areas including any access roads thereto shall be conveyed to the nearest stream course, catch-pit, channel or storm water drain as required by the Engineer. All temporary and permanent works shall be carried out in such a manner that no damage or nuisance are caused by storm water or rain water to the adjacent property.
 - (b) No drain or water course shall be used without consent of the Engineer.
 - (c) Damages or obstructions caused to any water course, drain, water-main or other installation within or adjoining the Works areas shall be made good to the satisfaction of the engineer.
 - (d) Treatment and disposal of sewage and waste water from the works areas shall be provided to the satisfaction of the engineer.
- (4) Buildings
 - (a) No permanent structures other than those required for the Permanent Works shall be permitted on the Works Areas.
 - (b) Electricity, water, telephone and sewerage shall be provided by the Contractor, as required, for all temporary buildings.
 - (c) No potable water obtained from the Govt. Sources shall be used for heating, cooling and humidification purposes, or vehicle washing without the written consent of the Engineer.
- (5) Pedestrian Access

Every existing pedestrian access throughout the Works Areas shall be maintained in a usable condition at all times to the satisfaction of the Engineer including lighting, signing and guarding.
- (6) Fencing

The Works Areas shall be secured against unauthorised access at all times. In particular fencing or the like shall be maintained, removed and re-erected in the new location wherever and whenever a Works Area is relinquished in stages.

3. **Applicability**

- (1) Where the Contractor is required to provide temporary electrical supplies, or to use, extend or expand on temporary supplies installed by others, all such activity shall be executed in accordance with Paragraphs of this Appendix.
- (2) When the Contractor makes use of temporary electrical supplies provided by others he will observe and comply with the requirements of this Appendix.

4. **Work On Site**

- (1) The contractor shall nominate a representative whose name and qualifications shall be submitted in writing to the Engineer for review not later than 4 weeks before the appointment and who shall be solely responsible for ensuring all the necessary electrical equipment on site. The contractor shall not install or operate any temporary site electrical systems until his representative is appointed and has commenced duties.
- (2) The name and contact telephone number of the representative having been reviewed without objection by the Engineer shall be displayed at the main distribution board for the temporary electrical supply so that he can be contacted in case of an emergency.
- (3) Schematic diagrams and the details of the equipment for all temporary electrical installations shall be submitted by the Contractor, and these diagrams together with the temporary electrical equipment shall be submitted to the Engineer for his consent.
- (4) All electrical installation work on Site shall be carried out in accordance with the requirements laid down in BS 7375 and the Specification. All work shall be supervised or executed by qualified and suitably categorized electricians, who are registered as such under the Electricity Ordinance 1990 / Electricity (Registration) Regulations 1990.

5. **Electrical General**

Temporary electrical Site installation and distribution systems shall be in accordance with: -

- (1) Indian Electricity Rules
- (2) The Power Companies' Supply Rules;
- (3) Electricity and its subsidiary Regulations;
- (4) IEE Wiring Regulations (16th Edition);
- (5) BS 7375 Distribution of Electricity on Construction and Building Sites;
- (6) BS 4363 Distribution Assemblies for Electricity Supplies for Construction and Building Sites; and
- (7) BS 6164 Safety in Tunneling in the Construction Industry.
- (8) Any other applicable national standards

6. **Materials, Appliances And Components**

All materials, appliances and components used within the distribution system shall comply with BS 4363 and BS 7375 Appendix A.

7. **Design Considerations**

- (1) Distribution equipment utilized within the temporary electrical distribution system shall incorporate the following features:-
 - a) Flexibility in application for repeated use;
 - b) Suitability for transport and storage;
 - c) Robust construction to resist moisture and damage; and
 - d) Safety in use.
- (2) All cabling shall be run at high level whenever possible and firmly secured to ensure they do not present a hazard or obstruction to people and equipment.
- (3) The installation on Site shall allow convenient access to authorized and competent operators to work on the apparatus contained within.

8. **Mains Voltage**
- (4) The site mains voltage shall be as per the electricity authority, 415V/3 phase 4 wire system.
- ii. Single phase voltage shall be as per the electricity authority, 230V supply.
 - iii. Reduced voltages shall conform to BS7375.
10. **Types of Distribution Supply**
- The following voltages shall be adhered to for typical applications throughout the distribution systems:
- iv. fixed plant-415V/3phase;
 - v. movable plant fed by trailing cable-415V/3 phase;
 - vi. installations in Site buildings- 230V/1phase;
 - vii. Fixed flood lighting-230V/1phase;
 - viii. Portable and hand held tools-115V/1phase;
 - ix. Site lighting (other than flood lighting)-115V/1phase; and
 - x. Portable hand-lamps (general use)-115V/1phase.
11. When the low voltage supply is energized via the Employer's transformer, any power utilized from that source shall be- either 415 V. 3 phase or 230 V. 1 phase as appropriate. The Contractor shall carry out any conversion that may be necessary to enable him to use power from that source.
12. **Protection of Circuits**
- d) Protection shall be provided for all main and sub-circuits against excess current, under and over voltage, residual current and earth faults. The protective devices shall be capable of interrupting (without damage to any equipment or the mains or sub-circuits) any short circuit current that may occur.
 - e) Discrimination between circuit breakers, circuit breakers and fuses shall be in accordance with: -
 - (i) BS 88;
 - (ii) BSEN 60898; and
 - (iii) BS 7375;
 - (iv) Any other appropriate Indian Standards.
9. **Earthing**
- (1) Earthing and bonding shall be provided for all electrical installation and equipment to prevent the possibility of dangerous voltage rises and to ensure that faults are rapidly cleared by installed circuit protection.
- (2) Earthing systems shall conform to the following standards: -
- a) IEE Wiring Regulations (16th Edition);
 - b) BS 7430;
 - c) BS 7375; and
 - d) IEEE Standard 80 Guide for Safety in AC Substation Grounding.
10. **Plugs, Socket Outlet and Couplers**
- Low voltage plugs, sockets and couplers shall be colors coded in accordance with BS 7375, and constructed to conform BSEN 63809 high voltage coupler and 'T' connections shall be in accordance with BS3905.
11. **Cables**
- (1) Cables shall be selected after full consideration of the conditions to which they will be exposed and the duties for which they are required. Supply cables up to 3.3KV shall be in accordance with BS 6346.
- (2) For supplies to mobile or transportable equipment where operation of the equipment subjects the cable to flexing, the cable shall conform to one of the following specifications appropriate to the duties imposed on it:
- c) BS6708 flexible cables for use at mines and quarries;
 - d) BS6007 rubber insulated cables for electric power and lighting; and
 - e) BS6500 insulated flexible cords and cables.
- (3) Where low voltage cables are to be used, reference shall be made to BS 7375. The following specifications shall also be referred to particularly for under ground cables:-
- a) BS6346 for armored PVC insulated cables; and

- b) BS6708 Flexible cables for use at mines and quarries.
- (4) All cables which have a voltage to earth exceeding 65 V (except for supplies from welding transformers to welding electrodes shall be of a type having a metal sheath and/or armour which shall be continuous and effectively earthed. In the case of flexible or trailing cables, such earthed metal sheath and/or armour shall be in addition to the earth core in the cable and shall not be used as the sole earth conductor.
- (5) Armoured cables having an over sheath of polyvinyl chloride (PVC) or an oil resisting and flame retardant compound shall be used whenever there is a risk of mechanical damage occurring.
- (6) For resistance to the effects of sunlight, overall non-metallic covering of cables shall be black in colour.
- (7) Cables which have applied to them a voltage to earth exceeding 12 V but not normally exceeding 65 V shall be of a type insulated and sheathed with a general purpose or heat resisting elastomer.
- (8) All cables which are likely to be frequently moved in normal use shall be flexible cables. Flexible cables shall be in accordance with BS 6500 and BS 7375.
- 12. **Lighting Installation**
 - (1) Where Site inspection of the Works is required during the nights, the Lighting circuits shall be run separate from other sub-circuits and shall be in accordance with BS 7375 and BS4363.
 - (2) Voltage shall not exceed 55V to earth except when the supply is to a fixed point and where the lighting fixture is fixed in position.
 - (3) Luminaries shall have a degree of protection not less than IP54. In particularly bad environments where the luminaries are exposed to excesses of dust and water, a degree of protection to IP65 shall be employed.
 - (4) The Contractor shall upgrade the lighting level to a minimum of 200 lux by localized lighting in all areas where required by the Engineer.
 - (5) Mechanical protection of luminaries against damage by impact shall be provided by use of wire guards or other such devices whenever risk of damage occurs.
- 13. **ELECTRICAL MOTORS**
 - (1) Totally enclosed fan cooled motors to BS4999:Part 105 shall be used.
 - (2) Motor control and protection circuits shall be as stipulated in BS 6164. The emergency stops for machinery shall be provided
- 14. **Inspection And Testing.**
 - Electrical installations on Site shall be inspected and tested in accordance with the requirements of the IEE Wiring Regulations (16th Edition).
- 15. **Identification**
 - Identification labels of a type reviewed without objection by the Engineer shall be affixed to all electrical switches, circuit breakers and motors to specify their purpose.
- 16. **Maintenance:**
 - (1) Strict maintenance and regular checks of control apparatus and wiring distribution systems shall be carried out by an electrician (duly qualified to carry out the said checks) to ensure safe and efficient operation of the systems. The Contractor shall submit for review by the Engineer details of his maintenance schedule and maintenance works record.
 - (2) All portable electrical appliances shall be permanently numbered (scarf tag labels or similar) and a record kept of the date of issue, date of the last inspection carried out and the recommended inspection period.
- 17. **Metering**
 - The Contractor shall install separately metered and invoiced supply or supplies of electricity for: -
 - (a) Site fabrication facilities;
 - (b) Site work shops and work yards; and
 - (c) Site offices and stores.

Appendix - XI – Utilities

SI NO	DESCRIPTION	PAGE NO
1	Utilities.	341
2	Diversion and Protection of Underground/Overhead Utility Lines	342
3	Additional Conditions for Diversion/Protection of BWSSB Utilities	343
4	Electrical Utilities (BESCOM/KPTCL)	343
5	BBMP Utilities diversion	345
6	BSNL Utilities diversion	345
7	GAIL Utility Diversion	345
8	Indian Railway (IR) Utility Diversion	346
9	General	346

DEFINITIONS**1. Utilities:**

Utilities are defined as public utilities above or below ground and include all live water mains, sewer mains, water wells, power cables, streetlights, transformers, pillar boxes, telephone posts, telecommunication cables, gravity sewers, storm water drains, gas lines which are either shown on the Employer's Drawings (charted) or identified on site by the Contractor (uncharted).

1.1 Chartist Utilities:

Charted Utilities are the utilities (as defined above) which are shown on the Employer's Drawings.

1.2 Uncharted Utilities:

Uncharted Utilities are the utilities (as defined above) which are not shown on the Employer's Drawings.

1.3 Responsibility of the Contractor.**1.3.1** The Contractor shall make his own enquiries and investigations, including excavating trial holes/pits, to ascertain the existence, nature, location, and size of utilities. A schedule of utility diversions and utilities to remain but to be supported / protected (the utility diversion plan) shall be prepared by the Contractor and submitted.

The schedule will list out utilities that:

- will be diverted by the Contractor during the course of the Works, and
- will remain in place and require the use of specific construction protection methods to complete the underground structures around and below the utilities including support of the utilities during construction by the Contractor.

1.3.2 The Contractor shall take into consideration the time required for utility diversions into the overall Works Programme for the Contract. However, efforts shall be made to avoid diverting/disturbance of any utility and continue the Works by supporting the same but the required services being provided by these utilities shall be maintained at all the times by the Contractor. Any delay to construction works due to delay in Utility diversion work will be responsibility of contractor, no claims shall be entertained in this regard.**1.3.3** The diversion work shall be undertaken by the Contractor as per the approval of the Utility owning Agencies and a notice from the Engineer. Temporary supports and protection by methods proposed by the Contractor and agreed by the Utility Agency shall be provided to the utilities. Permanent supports and protection shall be provided wherever required for the safety and security of the utility service.**1.3.4** The Contractor shall immediately inform the Engineer and the Utility Agencies of any

- (a) damage to utilities.
- (b) leakage of utilities.
- (c) discovery of utilities not previously identified.

1.3.5 When diverting and/or protecting sewerage and storm water lines the Contractor shall ensure that drainage to the site and adjacent areas is maintained at all times and that at no times flooding/overflow or other nuisance occurs.**1.3.6** The Contractor shall inform the Employer/Engineer of the programme of all works of utility diversion/ protection works and shall take all steps to enable the utility diversions to proceed in accordance with the programme. The Contractor shall maintain close liaison with the Utility Agencies. The Contractor shall set up and manage a Utility Liaison Group of experienced personnel for the duration of the Contract.**1.3.7** Records of the existing utilities encountered shall be kept by the Contractor on the Site and a copy provided for the Employer/Engineer. The records shall contain the following details:

- (d) location of utility.
- (e) date on which the utilities were encountered.
- (f) nature and sizes of the utilities.

- (g) condition of utility.
 - (h) temporary or permanent supports provided, and
 - (i) Diversions made –Temporary or permanent
- 1.3.8 The Contractor shall include the details (plan, location, ownership, size, and material) of all such utilities on the As Built Drawings.
- 1.3.9 The diversion/protection of utilities (Charted/Uncharted) shall be covered under the provisional sum given in the Pricing Summary. The Contractor shall be paid as per the current Schedule of Rates of the respective departments (KPWD, IR-USSOR, BWSSB, BESCOM, BSNL, or any other Govt agency etc.) plus 10% for overhead and profit. The priority of reference for deriving rate shall be in the same order as stated above. Until such time as such rate(s) are agreed or fixed, the Engineer, after consultation with the Employer, shall determine the provisional rate(s) to enable IPC to be issued by the Engineer.
- 1.3.10 Temporary diversion of each utility is allowed for one time. If the utility is to be restored, permanent restoration shall be considered in addition to the temporary diversion.
- 1.3.11 NOC & Approval of schemes for Diversion of Utilities from the concerned regulatory /statutory/Local Authority is the responsibility of the Contractor in coordination with Employer, Employer will only assist in getting permission and nothing extra is payable on this account. Similarly, necessary precautions which are specified from time to time by the utility owning agencies shall be followed. Contractor should make his own survey for identification of underground/above ground utilities.

2. Diversion and Protection of Underground/Overhead Utility Lines

- 2.1 The work comprises of replacement, relocation, diversion and protection of existing subsurface, surface and overhead public utilities viz. sewer mains, water lines, water wells, storm water drains, gully pits including connection pipes, house drains, gas pipe lines, electric and telephone cables, optical fibre cables including their appurtenance structure, O.H. electrical transmission line, electric poles, traffic signals, etc. which will be disturbed due to construction of the stations, where applicable.
- 2.2 The Contractor shall effectively protect all public utilities falling within the stations, station entry & exit locations and their immediate adjoining areas or which are likely to be exposed, disturbed or damaged during the execution of the work or in consequence thereof, in such a manner and using such materials as required or specified by the concerned public Utility Agencies and as per instruction of the Engineer, and hold them in proper position without any damage being caused to them during execution of work. Where adequate spaces are not available adjacent and outside the stations, the utilities may have to be hanged within the station-box itself to facilitate the construction work.
- 2.3 The contractor shall provide and lay pipes, water wells, gas mains/gully pit connections/house drains and other electric, telephones, copper telecom cable, optical fibre cables and other cables or any other underground structures or services falling within the station and their immediate adjoining areas which may be found to have been disturbed or damaged due to the Contractor's fault and/or defective and careless workmanship. The decision of the Engineer in this respect shall be binding and final and all costs of rebuilding or repairing of such damaged services or structures as foresaid shall be deducted from the Contractor, if the same is not taken care of within a reasonable time frame, mutually agreed between the Engineer and the Contractor. The claim or penalty imposed by the concerned utility department for the damage of utilities done by the contractor shall be recovered from the Contractor.
- 2.4 The Contractor shall enquire of and collect information from all concerned public Utility agencies, owners, Government Departments and local bodies in connection with the sewer lines, water mains, water wells, cables, wires and any other obstruction either overhead or on ground or underground which may be encountered in the course of execution of the work and which are likely to affect the progress of the work, at

his own cost and risk. No idle labour charge will be admissible on account of delay in collecting the above-mentioned information.

- 2.5 The Contractor shall have to excavate trial trenches of suitable sizes for satisfactorily exploring all the underground utilities as required and as instructed by the Engineer before commencement of any permanent work below ground level. All works related to utility identification and preparation of drawings obtaining stake holders approval shall be included in the Contractors quoted price. The time of completion for the project is inclusive of diverting and/or protection (temporary as well permanent) of utilities.

3. Additional Conditions for Diversion/Protection of BWSSB Utilities

- 3.1 It is the responsibility of the Contractor to get the approval of the proposed water/sewer/storm water/ pipeline etc., diversion/shifting from the concerned Agency/Authority. However, Engineer / Employer may facilitate the co-ordination work with concerned agency for getting the necessary approval.
- 3.2 In case the concerned utility agency/authority maintains a list of registered/approved contractors for undertaking such works and desires such shifting/diversion of pipeline/utility etc. work to be undertaken by such registered/approved contractors, then such shifting/diversion of pipeline/utility etc., shall have to be carried out by engaging the registered/approved contractors.
- 3.3 In case the Engineers of concerned utility agency intend to supervise the work, the Contractor (or sub-contractors engaged by the Contractor) have to carry out the work as per the instruction of the utility agency during diversion work by the Contractor.
- 3.4 In case of permanent diversion of water/sewer/storm water/pipelines etc., it is the responsibility of the Contractor to carry out such work without affecting water supply/without affecting sewage disposal etc. If required alternative temporary arrangement shall have to be made by the Contractor without any additional cost.
- 3.5 In case of temporary water pipe/sewer pumping mains (without manholes) diversion (which means divert the pipeline temporary away from station box and brought back to the original position after completion of station work), it is the responsibility of the Contractor either to use the retrieved diverted pipes or new pipes to restore back the original place without affecting the water supply/utility service.
- 3.6 In case of temporary diversion of gravity sewer pipelines with manholes are required, the Contractor, initially before taking up the station work has to ensure that the flow is diverted by laying sewer pipeline and constructing manholes away from the station box and then only divert the flow. After completion of station work, the Contractor shall have to lay again another sewer pipelines and again construct new manholes for restoring back to the original place.
- 3.7 In case of temporary supporting of water/sewer pipelines, if any damages occur during construction period it is the responsibility of the Contractor to rectify the damages to the satisfaction of concerned agency. The cost of the rectification works shall have to be borne by the Contractor.
- 3.8 It is the responsibility of the Contractor to obtain completion certificate from concerned utility agency for each diversion work. The payment for such diversion work will be made to the Contractor after obtaining completion certificate from concerned utility agency.
- 3.9 The Contractor shall handover all the retrieved material to the stores of the concerned utility agency/concerned department at the Contractor's cost and submit the proof of handing over.

4. Electrical Utilities (BESCOM/KPTCL)

- 4.1 The Contractor shall submit the utility diversion programme to Engineer / Employer with diversion justification based on trial pit information.
- 4.2 The Contractor shall submit the diversion plan to Engineer at least 60 (sixty) days in advance of work commencing to obtain approval from Electrical utility agencies. For utility diversion proposals of BESCOM /

- KPTCL, the Contractor shall submit diversion justification with trail pit information and drawing(s) with the proposed diversion route(s).
- 4.3 The Contractor would submit application of diversion works to electrical utility agencies with diversion plans. The Contractor shall render necessary assistance.
- 4.4 The Contractor shall coordinate with the local officials to assess quantities and specifications of materials required for diversion works. Necessary assistance would be provided by the Employer and the Engineer.
- 4.5 The Contractor shall obtain necessary permission from the concerned departments/agencies to carry out the diversion/shifting works and get necessary permission from Traffic Police Department.
- 4.6 Wherever possible, horizontal directional drilling method shall be adopted at location where utility diversion works crosses roadways and require lane closures for excavation to avoid inconvenience to the traffic.
- 4.7 The electrical utilities diversion/ shifting should be carried out by the Contractors/agencies registered with the electrical utility agencies / KPWD and have the required grade license from the Chief Electrical Inspector to Government. The Contractor should be well acquainted with electrical works so as to maintain the standard. The Contractor shall inform the same to Employer/Engineer for getting consent from the concerned electrical utility agency.
- 4.8 The Contractor shall identify the quantity of materials required for the contract such that the material can be procured by the Contractor in bulk and in advance to the implementation of the utility diversion works. The quality of materials to be procured shall be approved by the concerned utility agency. Materials used for diversion/ shifting shall be of quality conforming to the applicable standard of the electrical utility agency and as per relevant BIS.
- 4.9 The source of materials and the guarantee for the materials to be used shall be submitted to Engineer for obtaining approval from the concerned utility agency. Any failure of the material within the guarantee period shall be replaced and installed free of cost by the Contractor.
- 4.10 Contractor shall inform the local officers/officials of the concerned utility agency about the diversion works at least 15 (fifteen) days before the execution of diversion.
- 4.11 The diversion / shifting utility work shall be carried out under the direct supervision of officials and the utility agency decision shall be final in this regard. The Contractor shall provide free access to officers/ officials / workman for the purpose of inspection/supervision.
- 4.12 After restoration of regular service completion certificate shall have to be obtained from the concerned departments/agencies. The regulations for working with utility agencies shall be as follows.
- a. The diversion/shifting utility work should be carried out without causing any inconvenience to the operation and maintenance of Sub-Station and other departmental works of the concerned utility agency.
 - b. The Contractor shall execute and complete the work strictly in adherence to the time schedule and to the satisfaction of the engineers and adhere strictly the direction of the utility agency in any matter.
 - c. The Contractor shall be responsible to protect the public and the employees of the utility agency against any accident that may arise during the execution of diversion/shifting utility works. The Contractor shall indemnify the Employer for any claims for damages/injuries to the person/property resulting from any such accident. The Contractor shall Compensation Act by the way of obtaining an accident risk type insurance to meet all purpose of relief, failing which or otherwise the Contractor shall be solely responsible for meeting the compensation awarded under the said Act.
 - d. The Contractor shall undertake to ensure free flow of traffic during execution of the diversion / shifting works and shall be responsible for any accident/loss of lives/property. Damage to the other existing utilities during diversion shall have to be rectified by the Contractor at his own cost.
 - e. The Contractor shall employ qualified technical personnel to carry out the diversion/shifting of utility works.

- f. The Contractor shall apply well in advance for Line Clearance (LC) for carrying out the joint works/shifting works. Employer would authorise the Contractor to take LC from the concerned utility agency. If needed, Employer would provide assistance to the Contractor to get the LC. LC will be given by the concerned utility agency depending upon exigencies, which have to be strictly adhered to.
- g. The Contractor shall handover all the retrieved / unused material to the stores of the concerned utility agency /concerned department at the Contractor's cost.
- h. Contractor to pay the penalty/charges imposed by the utility agency for damage to the utilities on their own.
- i. The Contractor shall undertake not to revoke the above conditions until the completion of diversion/shifting works.

5. BBMP Utilities diversion

- 5.1 Diversion of Storm water drain shall be carried out as per the design, standard and general specifications of BBMP /PWD/concerned Highways Department.
- 5.2 The diversion route for storm water drain shall be approved by BBMP /concerned PWD/ Highways Department.
- 5.3 The invert level of diverting drain shall be maintained on par with upstream/downstream of connecting drains.
- 5.4 The Contractor shall make alternate arrangements to divert and ensure smooth flow of water from upstream side during construction.
- 5.5 The Contractor shall provide the adequate sizes of drain or follow the existing sizes as agreed by the concerned agency.
- 5.6 Diversion of storm water drain shall be carried out through the registered Contractors of BBMP/PWD/Highways Department (if such a list of approved/registered contractors is maintained by the utility agency).
- 5.7 Streetlights shifting shall be carried out as per the specification of BBMP.

6. BSNL Utilities diversion

BSNL utilities such as copper cable and OFC cables which are likely to be affected to be identified based on trial pit information. Contractor to prepare the diversion plan in coordination with the BSNL utilities agencies and get approval for the diversion plan. Employer/Engineer may provide assistance in this regard. Contractor to assess the required quantities based on the diversion plan. Cables procured to be Quality control checked by the concern wing of BSNL. Contractor to coordinate and arrange for the Quality control check by BSNL. Diversion of BSNL utilities to be done by the BSNL approved subcontractors and the completion certificate to be obtained from BSNL for the utility's diversion done. Private Telecom/OFC cable Contractor to manage the existing private telecom and OFC cables.

7. GAIL Utilities diversion

GAIL utilities such as gas pipelines which are likely to be affected to be identified based on trail pit information. Contractor to prepare the diversion plan in coordination with the GAIL authorities / agencies and get approval for the diversion plan. Employer/Engineer may provide assistance in this regard. Contractor to assess the required quantities based on the diversion plan. Contractor to coordinate and arrange for the Quality control check by GAIL Authority. Diversion of GAIL utilities to be done by the GAIL approved subcontractors and the completion certificate to be obtained from GAIL for the utility's diversion done.

8. Indian Railway (IR) Utilities diversion

IR utilities which are likely to be affected to be identified based on trail pit information. Contractor to prepare the diversion plan in coordination with the Railway authorities / agencies and get approval for the diversion plan. Employer/Engineer may provide assistance in this regard. Contractor to assess the required quantities based on the diversion plan. Contractor to coordinate and arrange for the Quality control check by Railway Authority. Diversion of Railway utilities to be done by the Railway approved subcontractors and the completion certificate to be obtained from Railway for the utility's diversion done.

9. General

The Contractor shall provide 6 months rolling programme every 3 month.

Appendix-XII - Contractor's Site Laboratory

1. SITE LABORATORY

- (1) The Site Laboratory shall be approximately 250 sqm in area. It shall consist of the following accommodation:

1 concrete laboratory	60 Sqm floor area
Soil laboratory	30 Sqm floor area
2 Office each	15 Sqm floor area
1 store room	10 Sqm floor area
1 kitchen	10 Sqm floor area
Male/Female toilets, changing room & shower	sufficient for 6 persons

- (2) The remainder of the 250 sqm shall consist of storage area for concrete cube curing tanks. The laboratory, office etc. shall be in one building; the curing tank storage building may be in a separate building, but if so, it shall be adjacent to the laboratory building & connected to it by a level, weather proof passageway. In addition, an area of covered hard standing of 50 sqm for motor vehicles shall be provided adjacent to the laboratory.

2. STANDARD OF CONSTRUCTION

- (1) The laboratory shall be constructed to the best Engineering practice and as approved by the Engineer. Two independent telephone lines with two extensions each shall be provided for the laboratory. Telephones shall be located in areas as agreed with the Engineer.
- (2) A water tank with minimum capacity of 2000 liters shall be installed. Constant water pressure of 15Kpa minimum shall be ensured in each laboratory.
- (3) In the case of sinks used for washing samples, adequate trapping and/or separating devices shall be provided to ensure the proper functioning of the facility.

3. FURNISHINGS AND FIXTURES

The contractor's site laboratory shall be provided with required furnishings and fixtures.

4. LABORATORY EQUIPMENT

- (1) The laboratory equipment, as listed below, shall be approved by the Engineer. The Contractor shall submit for the Engineer's approval within 2 weeks of the order to commence work the name of the supplier it intends to use for each piece of apparatus together with the relevant catalogue number.
- (2) The layout of the equipment in the testing laboratory shall be instructed by the Engineer. The equipment shall be maintained to accuracy appropriate to the required testing methods with routine calibration by an accredited organisation as recommended by the appropriate Authority. Equipment shall also be calibrated after maintenance or relocation.
- (3) The Contractor's site laboratory shall be equipped with the following material testing equipment as a minimum. The nature and quality of equipment required for pre-stressing may be varied by the Engineer depending on the detail of the Contractor's Design and Construction methods or for any other reason which

he deems to be valid and necessary for the proper control of quality:

- (4) The Contractor shall be responsible for all on-site and off-site testing and for all in-situ testing. All appropriate laboratory tests shall be carried out in the Contractor's laboratory, unless otherwise permitted or required by the Engineer. Where the laboratory is not appropriately equipped and/or staffed for some tests, or if agreed to by the Engineer, tests may be carried out in other laboratories. All materials required approval of Engineer after 3 rd party test at approved or reputed NABL accredited laboratory at the discretion of engineer.
- (5) Employer / Engineer in charge may recommend any test pertain to work or material to any laboratory of repute if they are accredited for the relevant work to a standard acceptable to the Engineer. The cost of such tests shall be borne by contractor.

Determining Liquid Limit (1 complete set)

Liquid limit device (Casagrande type)	1set
Grooving tools	1No
Evaporating dish	1No
Spatula 100mm blade	1No
Laboratory balance, capacity 500gm, (Sensitivity 0.01gms.)	1No
Wash bottle, capacity 500ml.	1No
Moisture cans capacity 50ml.	24No

Determining Plastic Limit (1 complete set)

Evaporating dish	1No
Spatula 100mm blade	1No
Glass plate 250mm x 250mm x 12mm	2No
Moisture cans capacity 50 ml	12 No
Stainless steel rods, 3mm dia.	2No

Determining Moisture Content (1 complete set)

Micro Oven, capacity 35 liters, control temperature upto	200°c
1 No weighing machine, capacity 200gm., sensitivity 0.01gm.	1No
Lab. Tongs	1No
Moisture cans 75ml. with lid	36No

Compaction Characteristics (1 complete set)

Standard compaction mould 100mm dia.	1No
Modified compaction mould 150 mm dia.	1N
Standard compaction Rammer,2.5kg.	1No
Modified compaction Rammer,4.5kg.	1No
Straight edge 300mm long	1No
Sample ejector for 100mm and 150mm	1No
Mould Sample tray 60x60x8cm	3No
Wash bottle, 500ml.	2No
Moisture cans 250ml	24No

Density of soil in-place by sand replacement method (2 complete set)

Sand density cone apparatus 150ml	2No
Plate, 300mm X 300mm	2No
Chisel 25mm X 150mm	2No
Hammer	2No
One gallon's field cans	24No
Sampling spoons	2No
Soft hair brush	2No
Moisture cans 250ml	48No

Sieve Analysis

Sieve shaker (portable)	1 unit Coarse sieves in sizes from
100mm to 10mm	(1 set Fine sieves #4, #8, #16,
#30, #40, #50, #100, #200 each)	

Pans & covers

Specific gravity and absorption of coarse aggregate

Wire basket, 200mm dia Heavy duty suspension balance,	
20kg X 1gm with accessory for weight in water	1 set
Suitable water container	1 No.

Unit wt. of aggregate

Balance, 100Kg cap. With 10gm precision	1No
Tamping rod 16mm dia X 600mm long	1No
Measuring containers (3,10,15, 30 ltrs)	1each

Flakiness & Elongation

Flakiness gauge, Elongation Index	1set
-----------------------------------	------

Soundness Test

Sodium Sulphate	25Kg
Soaking Tank	1nos
Balance, Cap. 3Kg, sensitivity 0.1gm	1set
Sieves: coarse, Fine	1set

Concrete

Bickets for concrete sampling	12Nos
Slump Cone	12Nos
Tamping rod	12No
Base plate	12No
Mixing pan for concrete	2No
Scoop for general purpose	2No
Concrete thermometer	2 No
Concrete cylinder mould 150mm*300mm;	
100mm*300mm	10each
Concrete cube mould, 100mm cube & 150 mm cube	10each
Adjustable spanners for Dismantling cube moulds	6No.
Capping set	2No

Capping compound

Concrete curing tank with capacity for 270 cubes, temperature controlled, with circulation system drain and lockable cover	5No.
--	------

Schmidt test hammer	1No.
Compression testing machine (simple hand operated)	1 No.
Mould oil Temperature chart recorder	1No.

Miscellaneous

Vernier callipers to measure up to 200 mm, with elongated jaws	5 Nos
Steel rule, 300mm long graduated	2Nos
Rubber gloves	10Pair
Cotton working gloves	20Pair
First aid kit	1set
Wire brush	6Nos
Steel tape, 3m, 5m, 30m	3each
Ball peen hammer, 1kg	2Nos
Paint scraper. Approx. 100mm wide	8Nos
Float, steel Approx. 280 x 120mm	8Nos
Sack barrow	1No
Shovel: Square Mouthed	2Nos
Round Mouthed	2Nos
24-wheel trolley, heavy duty, approx. 0.7m X 1.0m long Pneumatic tyred type	1no
Wheelbarrow, rubber tyred	
Comprehensive tool kit	1no
Claw hammer, multi-grips, spanners (adjustable)	1No
Type NR Schmidt Hammer and tester with recording device	1No
Testing Anvil for Schmidt Hammer test (SHT)	1No.
Chart recording paper for SHT	10 pkts
Cover meter for detecting metal objects to depth of 100mm	
Below the surface of non-magnetic objects	3 No.
Noise meter	1 No.
RCPT Testing Machine	1No.
Permeability Testing Machine.	

APPENDIX-XIII
PROJECT INTERFACE MATRIX

DELETED

APPENDIX XIV
IGBC NORMS

Deleted

APPENDIX XV

KEY DATES

The contractor shall prepare and submit his detailed Programme of Work so as to achieve key dates of various activities on time. The contractor shall complete the work in a phased manner by fixing priorities to different stretches of work to give access to the other interfacing contractors as per the requirement of project from time to time and as per the key dates (mile stones) indicated below:

Key Dates No.	Description of stage	Period (Days)	Liquidity Damages for non-achieving the key dates
KD 1	Completion of Casting of Foundations complete including backfilling.	D + 120	0.001% of total contract price per day of delay for the key date
KD 2	Completion of works up to Pier cap casting including all associated works	D'+ 210	0.001% of total contract price per day of delay for the key date
KD-3	Completion of erection works on approach span including all associated works	D + 300	0.001% of total contract price per day of delay for the key date
KD 4	Completion of erection works on Railway span including all associated works	D + 420	0.007% of total contract price per day of delay for the key date
KD 5	Completion of Reinforced earth works including road works complete	D + 480	0.007% of total contract price per day of delay for the key date
KD 6	Completion of all works and handing over with all respect	D+ 540	0.036% of total contract price per day of delay for the key date

Note: 1. D is the Commencement date

Annexure – I : Right of Access to the Site

Time for access to, and possession of the Site

The Right of access shall be handed over progressively, generally taking into account the approved program of works. The Right of Access to the site for One (1) LC will be handed over within Sixty (60) days from commencement date.

The schedule Right of Access of remaining LC location will be given progressively and in line with the requirement of the approved Programme. If any delay in access to, and procession of the site, the extension of time as per relevant clause of contract shall be given for the delay of effected portion of the works.

The Contractor shall bear all costs and charges for special and/or temporary rights-of-way which he may require, including those for access to the Site. The Contractor shall also indicate the, extra railway land or Govt land or private land beyond what is shown in the tentative tender drawing with the view to achieve best fit alignment for improved operational efficiency. On review by Engineer and Employer, the Contractor will be advised with the approved Horizontal/Vertical alignment for permanent works. For additional land if needed by the Contractor beyond the right of way the same shall be arranged by the contractor at his own cost.

In case any operation connected with traffic necessitates diversion, obstruction or closure of any road, railway or any other right of way, the proposal is to be developed by the contractor for review for the approval of the Engineer/Employer and the consents and approval of the concerned authorities shall be obtained well in advance by the Contractor.

Provided that if it is found necessary for the Contractor to move one or more loads of heavy constructional plants and equipment, materials or Pre-constructed units or parts of units of work over roads, highways, bridges on which such oversized and overweight items that are not normally to be moved, the contractor shall obtain prior permission from the concerned authorities.

Payments for complying with the requirements, if any, for protection or strengthening of the roads, highways or bridges shall be made by the contractor and such expenses shall be deemed to be included in his quoted contract price.

Annexure – II: General arrangement drawings (GAD)

The GAD of LC125, LC126 and LC127 are under approval by SWR/IR. The approved GAD will be provided in due course of time. Contractor shall deploy design personnel for approval of GAD by SWR/IR if required by Engineer / Employer.

Annexure – III : Tree Cutting and Forest Clearances–in Process

The permission for obtaining tree cutting / translocation is in progress with BBMP and Forest Department. The tree numeration list and joint inspection with Forest officers / BBMP / TEC is in progress.

Tree cutting, preservation and disposal (or) Translocation along the alignment for cutting / disposal / translocation / afforestation (as per the norms of Forest Department) in lieu of cutting / translocation is in the scope of Contractor. The applicable permits / permissions for felling of trees / Translocation shall be arranged by Employer. The tree cutting and disposal is included in the scope of work. The cut trees will be the property of the contractor. However, the contractor shall deposit an amount not less than Reserve Price of the trees (as fixed by Forest Department / BBMP) plus FDT (Forest Development Tax) to Bi-RIDE for onward transmission to Railways / BBMP / Forest Department, as the case may be.

Annexure – IV :

- Deleted -

Annexure – V : Applicable Permits

i. Applicable Permits

1.0 The Contractor shall obtain, as required under Applicable Laws, the following Applicable Permits:

- (a) Permission of the State Government for extraction of boulders from quarry;
- (b) Permission of Village Panchayats and Pollution Control Board for installation of crushers;
- (c) Licence for use of explosives;
- (d) Permission of the State Government for drawing water from river/reservoir;
- (e) Licence from inspector of factories or other competent Authority for setting up batching plant;
- (f) Clearance of Pollution Control Board for setting up batching plant;
- (g) Clearance of Village Panchayats and Pollution Control Board for setting up asphalt plant;
- (h) Permission of Village Panchayats and State Government for borrow earth; and
- (i) Any other permits or clearances required under Applicable Laws.

Annexure – VI : Provisional Certificate

- 1 I/We, (Name of the Authority's Engineer), acting as the Authority's Engineer, under and in accordance with the Agreement dated (the "**Agreement**"), for construction of the section (km to km) in the State of in- BSTP (the "**BSTP Project**") on Engineering, Procurement and Construction (EPC) basis through (Name of Contractor), hereby certify that the Tests in accordance with the Agreement have been undertaken to determine compliance of the BSTP Project with the provisions of the Agreement.
- 2 Certain minor works are incomplete and these are not likely to cause material inconvenience to the Users of the BSTP Project or affect their safety or the movement of rail traffic in any manner. These works have been specified in the Punch List appended hereto, and the Contractor has agreed and accepted that it shall complete all such works in the time and manner set forth in the Agreement.
- 3 In view of the foregoing, I/We am/are satisfied that the BSTP Project from km to km can be safely and reliably placed in service of the Authority for railway freight and passenger traffic, subject to authorisation by the Commissioner of Railway Safety in accordance with Applicable Laws. In terms of the Agreement, the BSTP Project is hereby provisionally declared fit for entry into operation on this the day of 20.....

ACCEPTED, SIGNED, SEALED

AND DELIVERED

For and on behalf of

CONTRACTOR by:

(Signature)

(Signature)

SIGNED, SEALED AND

DELIVERED

For and on behalf of

AUTHORITY's ENGINEER by:

Annexure – VII : Completion Certificate

- ii. I/We, (Name of the Authority's Engineer), acting as the Authority's Engineer, under and in accordance with the Agreement dated (the "**Agreement**"), for construction of thesection (km to km) of in the State of in- BSTP (the "**BSTP Project**") on through (Name of Contractor), hereby certify that the Tests in accordance with the Agreement have been successfully undertaken to determine compliance of the BSTP Project with the provisions of the Agreement, and the authorisation by the Commissioner for Railway Safety under Applicable Laws has been obtained.
- iii. It is certified that, in terms of the aforesaid Agreement, all works forming part of Railway Project have been completed, and the BSTP Project is hereby declared fit for entry into operation on this the day of 20.....
- i. The test on completion of civil works shall also include the integrated testing. The objective of the contract is the Design and construction, testing and commissioning of the permanent works, construction and removal of the Temporary Works and the rectification of defects appearing in Permanent Works by the contractor in the manner stipulated by the Contract..
- ii. The completion certificate is as per railway standard format. Please refer CI.30.6 at page 161, para 12 and para 2 . The format can be altered as per the contract conditions. The tender conditions prevails.

SIGNED, SEALED AND DELIVERED
For and on behalf of the Authority's Engineer by:
(Signature)
(Name)
(Designation)
(Address)