C L OF PRO. FUTURE STN ATGRADE (SUB-URBAN) STATION (Km. 43.950)
KM 44
Refer Drawing No.- KRDD01-TDR-CR04-GEN-OCS-PGP-00016
TENTATIVE LOCATION OF DA SHOWN, OHE TO BE SUPPORTED FROM TRUSSES AND DISTANCE OF TRUSSES REQUIRED FROM STATION BUILDING CONTRACTOR.
UP LINE
MUDDANA HALLI (SUB-URBAN) STATION
DN LINE
RAMP END
UIOL FOR UP LINE CH: 44691.908
UIOL FOR DN LINE CH: 44691.908
ACC CENTRE FOR UP MAIN
ACC CENTRE FOR DN MAIN
T.L. =562.500m Loc: 43/25 CH: 43644.408m
T.L. =563.000m Loc: 44/33 CH:44769.908m
T.L. = 962.500m Loc: 45/27 CH: 45576.408m
T.L. =1125.500m Loc: 43/25 CH: 43644.408m
PRO.CURVE NO.105(UP&DN) R = 905.5m, D = 1.93° A = 2°33'21.74" TL = 17.55 m CL =35.09m TRL =40 m SE = 60mm V = 90 kmph
PRO.CURVE NO.106(UP&DN) R = 914.5m, D = 1.91° A = 2°31'40.35" TL = 17.72m CL =35.44 m TRL =40 m SE = 60mm V = 90 kmph
KM 45
RAMP END
T.L. = 1761.000m Loc: 43/21 CH: 43549.908m
T.L. = 1234.000m Loc: 46/39 CH: 46544.908m
T.L. = 1112.500m Loc: 46/39 CH: 46544.908m
IOL FOR UP LINE CH: 45504.408
IOL FOR DN LINE CH: 45504.408
T.L. =962.500m Loc: 44/25 CH: 44613.908m
PRO.CURVE NO.107(UP&DN) R = 1241 m, D = 1.41° A = 16°37'24.67" TL = 181.29 m CL =360.03 m TRL = 30 m SE = 45 mm V = 90 kmph
C L OF PRO.RAJANKUNTE ATGRADE (SUB-URBAN) STATION (SUB. Km.45.875)
TENTATIVE LOCATION OF DA SHOWN, OHE TO BE SUPPORTED FROM TRUSSES AND DISTANCE OF TRUSSES REQUIRED FROM STATION BUILDING CONTRACTOR.
PLATFORM END
KM 46
SSP RAJANKUNTA CH: 46+200 KM
T.L. = 346.500m Loc: RNJK/1002 CH: 46369.408m
T.L. = 310.500m Loc: RNJK/1002 CH: 46369.408m
PRO.CURVE NO.108(UP&DN) R = 1245 m, D = 1.94° TL = 18.26m CL =36.63 m TRL = 20 m SE = 45mm V = 90 kmph
RNJK/1002
RNJK/1004
T.L. =346.500m Loc: 46/6 CH: 46022.908m
T.L. =310.500m Loc: 46/10 CH: 46058.908m
46/31 Mast Type--- Chainage 46387.408
46/33 Mast Type--- Chainage 46436.908
46/35 Mast Type--- Chainage 46477.408
46/37 Mast Type--- Chainage 46513.408
46/39 Mast Type--- Chainage 46544.908
46/32 Mast Type-- Chainage 46387.408
46/34 Mast Type-- Chainage 46436.908
46/36 Mast Type-- Chainage 46477.408
46/38 Mast Type-- Chainage 46513.408
46/40 Mast Type-- Chainage 46544.908
RCA/OPCA T.L. =1234.000m Loc: 45/13 CH: 45310.908m
T.L. =1112.500m Loc: 45/19 CH: 45432.408m
T.L. =1112.500m Loc: 45/20 CH: 45432.408m
RCA/OPCA T.L. =1234.000m Loc: 45/14 CH: 45310.908m
UP LINE
DN LINE
BWA
TC:4.50
PRO.BSRP GRADIENT
END OF CORRIDOR


HEELALIGE
KM44
KM45
KM46
ACC UP MAIN
562.500m
563.000m
CH: 44+206.908
1125.500m
962.500m
UIOL
CH: 44+691.908
499.000m
463.500m
CH: 45+112.908
962.500m
1112.500m
IOL
CH: 45+504.408
590.500m
522.000m
CH: 46+022.908
ACC DN MAIN
㉓
FUTURE STN (SUB-URBAN)
CH: 43+950 Km
㉔
RAJANKUNTE (SUB-URBAN) STATION
CH: 45+875 Km
UP LINE
MUDDANA HALLI (SUB-URBAN) STATION
DN LINE
CS
BM
LA
TC=4.50
SSP
RAJANKUNTA CH: 46+108 KM

LEGEND

Sr. No.	DESCRIPTION	SYMBOL
1	OHE Span length in metres	(30)
2	Insulated Overlap (IOL)	
3	Un insulated Overlap (UIOL)	
4	Section Insulator	
5	Single Pole Isolator	
6	Double pole Isolator with Earth Heel	
7	Normal Mast with Single Cantilever Assembly at Viaduct	
8	Normal Mast with Multiple Cantilever Assembly at Viaduct	
9	Normal Mast with triple Cantilever Assembly at Viaduct	
10	Portal with Drop Arm and Single Cantilever Assembly at Viaduct	
11	Portal with Drop Arm and Double Cantilever Assembly at Viaduct	
12	Two Track Cantilever Assembly (TTC 5.50/8.0) at Viaduct	
13	Normal Mast with Single Cantilever Assembly at Grade	
14	Normal Mast with Multiple Cantilever Assembly at Grade	
15	Normal Mast with triple Cantilever Assembly at Grade	
16	Portal with Drop Arm and Single Cantilever Assembly at Grade	
17	Portal with Drop Arm and Double Cantilever Assembly at Grade	
18	Two Track Cantilever Assembly (TTC 5.50/8.0) at Grade	
19	Drop arm support with single cantilever (6"x6" DA)	
20	Drop arm support with Double cantilever (8"x6" DA)	
21	Drop arm support with triple cantilever (8"x6" DA)	
22	Anchoring stay with Fixed Termination-conv.	FTA
23	Anchoring Stay with Spring Termination Anchor	BWA
24	Versine	300
25	Anticreep Anchor	ACA
26	Anticreep Center	ACC
27	Tension Length	TL
28	Upright Details (Clearspan)	BFBU/GU(CS:xx)
29	Sub-Sectioning and Paralleling Post (SSP)	
30	Sub-Sectioning Post (SS)	
31	Sectioning and Paralleling Post (SP)	
32	Feeding Post (FP)	
33	Obligatory	OBL
34	To Be Decided	TBD
35	Interrupter(BM)	
36	Potential Transformer (PT)	
37	Lightning Arrestor (LA)	
38	Booster Transformer	
39	Spare	
40	Overhead Protection Conductor Anchor	OPCA
41	Return Conductor Anchor	RCA
42	Tramway OHE	
43	In-Run Wire	
44	Out-of Run Wire	
45	PTFE	
46	Overhead Protection Conductor	
47	Return Conductor	
48	Cross feeder	
49	Slack feeder	
50	Full Feeding Jumper	
51	Potential Equalising Jumper	
52	In-Span Jumper	
53	RC and OPC Support	
54	Track at UP/DN line (Corridor 2)	
55	Track on Viaduct	

NOTES:-

1. ALL DIMENSIONS ARE IN METERS UNLESS NOTED OTHERWISE.
2. ALL DIMENSIONS ARE TO BE READ AND NOT TO BE MEASURED.
3. ALIGNMENT OF THE PEGGING PLAN HAS BEEN PREPARED ACCORDING TO THE ALIGNMENT DRAWING RECEIVED FROM GC / KRIDE DT. 22-06-2024.
4. OHE CHAINAGES OF THE PEGGING PLAN HAS BEEN TAKEN WITH REFERENCE TO THE OHE SPAN FROM THE PREVIOUS LOCATION.
5. SPANS ARE ROUNDED OFF TO NEAREST SINGLE DECIMAL.
6. 6. MAST TYPE SHALL BE DEMARCATED IN PEGGING PLAN AFTER FINALIZATION OF OHE LOAD CALCULATIONS.
7. OHE HEIGHT CLEARANCE UNDER/OVER LINE STRUCTURE (HT. LINE X-ING ETC.) TO BE CONFIRMED OR SPECIAL CARE TO BE TAKEN BEFORE ERECTION FOR THAT PARTICULAR AREA WHEREVER REQUIRED.
8. OHE LOCATIONS IN THE ELEVATED SECTION WILL BE FINALIZED AFTER RECEIVING OF PIER SPAN ARRANGEMENT.

NOTES:

1. ALL DIMENSIONS ARE IN METER UNLESS MENTIONED OTHERWISE.
2. ALL DIMENSIONS ARE TO BE READ AND NOT TO BE MEASURED.
3. ANY DISCREPANCY IN THE DRAWING MUST BE BROUGHT TO THE NOTICE OF THE DESIGNER.
4. INTERFACE WITH OTHER DESIGN DISCIPLINE WILL BE DONE AS PER AVAILABILITY OF DETAILS.

REV	DATE	DESCRIPTION	Originator	Checked	Approved
R0	09-09-2024	First Submission	KB / SB	CK/NP	RK/SK

K RIDE

DM / ELE / KRIDE | Sr. DGM / ELE / KRIDE | AGM / ELE / KRIDE

Certified that this document has been designed and checked in accordance with GC Quality Assurance Plan.

EGIS-AECOM-WSP

Senior Discipline Expert | Chief Discipline Expert | Project Director

Certified that this document has been designed and checked in accordance with DDC Quality Assurance Plan.

Detailed Design Consultant for design of Traction & Auxiliary Power Supply and Distribution for BSRP

SYSTRA MVA CONSULTING (INDIA) PVT. LTD.
10th and 11th Floor, Tower-B, 12/3, Vatika Mindscapes, Mathura Road, NH2, Sector 27D, Faridabad, Haryana 121013

Drawn		Checked:		Approved:	
I. Alam		D. Kalyan		R. Kapoor	
S. Bhati		N. Parmar		S. Kumar	

FOR TENDER PURPOSE ONLY

Client:
RAIL INFRASTRUCTURE DEVELOPMENT COMPANY (KARNATAKA) LIMITED

Project Title: Bengaluru Suburban Rail Project (BSRP)
(Detailed Design Consultant for design of Traction & Auxiliary Power Supply and Distribution for BSRP)

Corridor-4 (Heelalige -Rajankunte)

Drawing Title:
OHE Pegging Plan for Main Line
CH: 43+825.000Km to CH: 46+544.908Km

Project Stage: Tender Drawing

Paper Size: 297X5000
Discipline: Power Supply & Traction System
Date: 09/09/2024
Scale: NTS

Drawing no.: KRDD01-TDR-CR04-GEN-OCS-PGP-00017
Revision: R0